IN THIS ISSUE

STEEL
The Metalworking Weekly

December 2, 1957
Vol. 141 No. 23

Published every Monday by The Penton Publishing Co., Penton Bldg., Cleveland 13, Ohio. Subscriptions in the U. S. and possessions and Canada, $10 a year; all other countries, $20. Current issues, 50 cents each. Metalworking Yearbook issue, $2. Accepted as controlled circulation publication at Cleveland. Copyright, 1957, The Penton Publishing Co.

Index available semiannually. STEEL is also indexed by Engineering Index, 29 W. 39th St., New York 18, N. Y.

from cold strip
to finished tubing
IN SECONDS!



with a
YODER
ELECTRIC-WELD
TUBE MILL

One of the fastest . . . and one of the least expensive . . . methods of making steel tubing is with a Yoder Electric-Weld Tube Mill. The Yoder method eliminates the need for time-consuming heat treatments and costly conditioning furnaces for most tube needs. Scrap losses, too, are far lower than any other method . . . usually less than 2%.

The Yoder Type-M Mill shown above is operated by one man and a helper. Coiled strip on this mill is continuously cold-roll formed, welded and cut to required lengths in a matter of seconds . . . at speeds up to 340 f.p.m. The quality of the resulting tube is *constantly* better than the requirements of commercial standards. This is one of many reasons why manufacturers and users of tubing the world over are using more Yoder mills than all other makes combined.

If your business requires pipe and tubing, ferrous or non-ferrous, in sizes from ¼-inch up to 26-inch diameter, Yoder can supply the engineering service and machines to produce it faster and better for less! For complete details, write for the Yoder Tube Mill Manual. It's yours for the asking.

THE YODER COMPANY
5502 Walworth Ave. • Cleveland 2, Ohio

ENGINEERING YODER MANUFACTURING
PIPE AND TUBE MILLS
(ferrous or non-ferrous)

behind the scenes



En Garde, Le Pentagon!

He who leadeth with his chin frequently windeth up sporting lumps. This time, however, in spite of our mousey attitude, we are about to pitch into U. S. Government.

STEEL had a wonderful story about missiles a few weeks ago. It would have been of particular interest to the metalworking world. We even had a picture of Associate Editor Austin Brant peering from a window in the tail of a rocket. Pictures of this rocket have been published before; perhaps thousands of persons are familiar with the metal fabrication of the thing, and it's even more than possible that the Russians know all about it, anyway. Worse than that, the Russians probably regard it as old hat. They're already shooting for the moon, and we are scarcely off the ground.

Well, after allowing STEEL to assemble the story, the Pentagon suddenly did a double take, reversed itself, and declared the article off limits, top secret, extra confidential, and intimated that if we printed it we would be better off in a sputnik. We don't question the Pentagon's authority, nor will we ever fail to conform with its rulings, but . . .

We Tote Heavy Load

Old wine, old cheese, old friends, and old chestnuts have an ever-lovin' flavor. When George O. Hays, president, Penton Publishing Co. (publisher of STEEL) came across the following lament in the Building Trades Employers' Association *Bulletin,* he grinned as happily as he did when he first saw it—possibly when he was teaching school in rural Indiana. Titled "Executive Manager's Lament," the piece goes:

Population of U. S.	160,000,000
People 60 years and older	62,000,000
Balance left to do the work.....	98,000,000
People 21 years and younger	54,000,000
Balance left to do the work.....	44,000,000
People working for government....	21,000,000
Balance left to do the work.....	23,000,000
People in Armed Forces	10,000,000
Balance left to do the work.....	13,000,000
People in city and state offices....	12,800,000
Balance left to do the work....	200,000
People in hospitals, institutions....	126,000
Balance left to do the work....	74,000
Bums and others who don't work..	62,00
Balance left to do the work.....	12,00
Persons in jail	11,9
Balance left to do the work....	

Two! You and I. And you'd bett get a move on. I'm tired of runnin this country alone!

Caution in Labor?

That mess of traffic lights o the front cover suggests that La bor ought to use caution before barges ahead with new demands. Th story (Page 53) lists Labor's gain examines its prospects, and brin the reader up to date on bargainin points. There's some mention, to about a strike the UAW may pu next June, probably against Gener Motors. From a quick reading of th article, we learned that Labor quite concerned about its interna strife, Congressional hearings, an unwanted officers. Automation, elec tronics, atomic power, shifts of em ployment, and dips in the nationa economy help influence Labor at th bargaining table—and it's lucky the do, too, because otherwise Labo would demand the table, as well.

They Asked for It

Miss Bernice Hunter is librarian a Rayonier Inc., Olympic Researc Div., Shelton, Wash. Among th magazines that cross her desk eac month is *Automation,* a sister publi cation of STEEL. In the Novembe issue the editor, in a burst of gen erosity, invited his readers to submi their knottiest automatic operatio problem to the *Automation* Proble Forum. The invitation was heade "What's Your Problem?" Miss Hunt er didn't dawdle around; she unlim bered her typing machine and wrot this beautiful note: "Gentlemen: O Page 69 of the November issue o *Automation* is the question, 'What' your problem?' Our problem is tha Pages 37-68 of this issue are alter nately blank and double printed."

When last seen, the editor was i a sinking condition.

Shrdlu

(Metalworking Outlook—Page 47)

Another Transfer-matic by Cross



This Transfer-matic performs the finishing operations on rear axle housings with differential bearing caps assembled.

Rated capacity is 90 pieces per hour at 100 per cent efficiency with each cycle producing two finished axle housings.

A novel feature is the arrangement of the precision finishing operations. All bearing diameters are precision bored in the same station to assure precise gear centers. The vertical boring unit finishes first one and then the other of the two pinion shaft bearing diameters. In the same station, opposed horizontal units back-bore the differential bearing diameters. Perfect concentricity and squareness of the shoulders are obtained between the two pinion bearing seats since both are bored with the same spindle.

Other features are complete interchangeability of all standard and special parts for easy maintenance, construction to JIC standards, hardened and ground ways, hydraulic feed and rapid traverse and automatic lubrication.

Established 1898

THE **CROSS** CO.

First in Automation

PARK GROVE STATION • DETROIT 5, MICHIGAN

KILL RECORD VAULT FIRES FAST

with a Kidde automatic carbon dioxide fire extinguishing system . . . the fastest, safest 'round-the-clock fire protection you can buy. At the first hot breath of fire, Kidde's rate-of-temperature-rise actuators trigger the system. Instantly, clean carbon dioxide smothers fire, vanishes into thin air. Leaves no mess. The Kidde system features all operating parts completely enclosed for safety. No falling weights, no clumsy mechanical triggering methods. Pressurized, no outside power needed. Visual indicators to show if system is set or released. Easy testing of all operating parts. No parts to replace after operation or test. For more information write for Kidde's automatic carbon dioxide fire extinguishing systems booklet today.

Kidde

Walter Kidde & Company, Inc.
1260 Main St., Belleville 9, N. J.
Walter Kidde & Company of Canada Ltd., Montreal—Toronto

LETTERS TO THE EDITORS

Editorials To Be Mailed

Please send 1325 copies of your ed cellent editorial, "Don't Run for th Hills!" (Nov. 4, Page 63). We plan mail these to our distributor-salesme

W. S. But
Superior Tube C
Norristown, P

I read with interest your timely ed torial, "Why Not a Profit?" (Oct. 2 Page 35). We have a mailing list about 100 reinforcing steel fabricato in the seven western states, and would like to send each of them a cop

F. S. Clou
Manag
Western Reinforcing Steel Fabricat
Associati
Oakland, Cal

Quotable Article

Please mail a copy of the articl "Needed: Better Training" (Nov. 1 Page 114). I'm sure you won't mind m quoting from it when talking to eng gineering groups.

E. W. Allar
Chief Engine
Tubular Products D
Babcock & Wilcox C
Alliance, Oh

Small Business Going Places



I enjoyed the Program for Manage ment article, "Small Business—Its Plac in Our Future" (Nov. 11, Page 99), an think that you did a splendid job o presenting it.

James G. Garwic
Regional Direct
Region V
Small Business Administratio
Clevelan

Ideal Information

Could you please send a copy of th two-part article, "How To Avoid Crack ing Die Steels" (Sept. 30, Page 79, an Oct. 7, Page 200)? I'm a diemakin apprentice instructor at Pratt & Whit ney Aircraft, and this is ideal informa tion for our apprentice diemakers.

James R. Suite
Pratt & Whitney Aircra
Division of United Aircraft Corp
East Hartford, Conn

Usage at Policy Meeting

Please forward 25 copies of the ar ticle, "Pattern Bargaining Spreads (Nov. 11, Page 59). I plan to use ther at the next meeting of the managemen policy committee of the National Meta

(Please turn to Page 12)



Cut-away drawing of a Salem-Brosius rectangular soaking pit as installed in one of the mills of a leading steel producer.

Users are the best salesmen of Salem-Brosius soaking pits

"We have again specified Salem-Brosius rectangular soaking pits for our expansion program," reports an operating official of a major steel company using pits installed by several manufacturers. "The previous installation heated more steel ingots ready for rolling with less fuel consumption, less maintenance cost, and better temperature uniformity than any other type of pit in our plant."

Reports like this are typical, not only about these rectangular soaking pits, but all other Salem-Brosius heating and heat-treating furnaces as well. Salem-Brosius engineers, both here and abroad, possess an enviable record for designing furnaces which produce maximum, high-quality output at minimum operating cost. If your expansion or modernization plans call for ingot soaking pits or any other heating or heat-treating furnaces, Salem-Brosius, Inc. would appreciate an inquiry.

SALEM-BROSIUS, INC.

CARNEGIE, PENNSYLVANIA

In Canada: Salem Engineering Limited, 1525 Bloor Street West, Toronto, Ontario

Announcing

a significant broadening of
Duraloy High Alloy Casting Service...

SHELL-MOLDED CASTINGS



DURALOY

We are now in position to accept and process substantial orders for shell-molded castings in the Chrome Iron, Chrome Nickel class.

Shell-molded castings provide several values over conventional castings:

a . . . dimensions are exceptionally accurate
b . . . thinner walls are practicable
c . . . surface finish is superior

Shell-molding is ideal for mass or repetitive production of parts particularly those with intricate design.

With our conventional static and centrifugal casting service now broadened by our shell-molded casting service, we are in a better position than ever to serve industry in connection with its high alloy casting requirements. May we quote on your casting requirements that call for shell-molding?

The DURALOY Company

OFFICE AND PLANT: Scottdale, Pa.

EASTERN OFFICE: 12 East 41st Street, New York 17, N. Y.
ATLANTA OFFICE: 76—4th Street, N.W.
CHICAGO OFFICE: 332 South Michigan Avenue
DETROIT OFFICE: 23906 Woodward Avenue, Pleasant Ridge, Mich.

LETTERS

(Concluded from Page 10)

Trades Association, of which I am presi-
dent.

Warren W. Walke
General Manage
Graphite Metallizing Corp
Yonkers, N. Y

Editorial Hits Home

I recently visited an account that ha
taken time to frame and hang on th
wall your July 15 editorial, "Parabl
of the Prices" (Page 51). Will you ma
me several copies? The article hit hom
and I enjoyed it immensely.

Edward J. Fo
Manage
Westbury Offic
Morris Abrams In
Westbury, N. Y

Indian Appreciates Value

In regard to your article in full colo
"How To Get More from Ma
chine Tools" (Sept. 23 insert), I hav
rarely come across so well written an
so well printed an article with so muc
practical value. Kindly send a copy.

V. S. Kudv
Technical Direct
Canara Workshops Ltd
Mangalore, Indi

Steel Study: Excellent

Your special study in the Nov. 4 is
sue, "Stainless Steels" (Page 107), is ex
cellent. Could I have a dozen copie
for distribution to the major stainles
users in this area?

J. R. Mille
District Sales Manage
Chicago Steel Service Co
Appleton, Wis

You are to be highly complimented
I find it quite accurate and highly edu
cational. May we have two copies fo
our salespeople?

R. M. Conne
Manager of Sale
New York Distric
G. O. Carlson Inc
East Orange, N. J

Plan Distribution

We enjoyed the Program for Manage
ment article, "Dealing with Workers
(Sept. 16, Page 119). May we have 2
reprints of the article to distribut
within our organization?

M. C. Deter
Modine Mfg. Co
Paducah, Ky

Helpful to Supervisors

The two-part article, "Choose th
Right Lubricant" (Oct. 14, Page 132
and Oct. 21, Page 100), was most in
teresting. Please send five reprints. Ou
supervisory personnel will find the ar
ticle informative and helpful.

F. C. Ballar
Manager, Plant No.
Reynolds Metals Co
Louisvill

Prefab Institute Address

In the Metalworking Outlook of Oct
28 (Page 113), you make reference t
the Prefabricated Home Manufacturer
Institute. Can you give me the institute'
address?

Charles C. Ha
Vice President-Sale
United Steel Fabricators Inc
Wooster, Ohi

• *The institute is at 908 20th St
Washington 6, D. C.*

CALENDAR
OF MEETINGS

Dec. 1-6, American Society of Mechanical Engineers: Annual meeting, Hotel Statler, New York. Society's address: 29 W. 39th St., New York 18, N. Y. Secretary: C. E. Davies.

Dec. 2-6, Exposition of Chemical Industries: Coliseum, New York. Information: International Exposition Co., 480 Lexington Ave., New York 17, N. Y. President: E. K. Stevens.

Dec. 4-6, American Institute of Mining, Metallurgical & Petroleum Engineers: Electric furnace steel conference, William Penn Hotel, Pittsburgh. Institute's address: 29 W. 39th St., New York 18, N. Y. Secretary: E. O. Kirkendall.

Dec. 4-6, Building Research Institute: Conference on adhesives and sealants in building, Shoreham Hotel, Washington. Institute's address: 2101 Constitution Ave., Washington 25, D. C. Executive director: William H. Scheick.

Dec. 5-7, National Association of Manufacturers: Congress of American Industry, Waldorf-Astoria Hotel, New York. Association's address: 14 W. 49th St., New York 20, N. Y. Managing director: Kenneth R. Miller.

Dec. 10-11, Society of the Plastics Industry Inc.: Conference on vinyl products in the consumer field, Hotel Commodore, New York. Society's address: 250 Park Ave., New York 17, N. Y. Executive vice president: William T. Cruse.

Dec. 11-12, National Construction Industries Conference: Hotel Sherman, Chicago. Sponsor: Armour Research Foundation, 10 W. 35th St., Chicago 16, Ill.

1958

Jan. 6-8, Southern Industrial Distributors' Association: Midyear meeting, Roosevelt Hotel. New Orleans. Association's address: 1626 Fulton National Bank Bldg., Atlanta 3, Ga. Secretary: E. L. Pugh.

Jan. 13-17, Society of Automotive Engineers Inc.: Annual meeting, Sheraton-Cadillac and Statler Hotels, Detroit. Society's address: 485 Lexington Ave., New York 17, N. Y. Secretary: John A. C. Warner.

Jan. 16-17, National Industrial Conference Board Inc.: General session for all associates, Hotel Commodore, New York. Board's address: 460 Park Ave., New York 22, N. Y. Secretary: Herbert S. Briggs.

Jan. 17, Malleable Founders' Society: Semiannual meeting, Hotel Cleveland, Cleveland. Society's address: 1800 Union Commerce Bldg., Cleveland 14, Ohio. Executive vice president: Lowell D. Ryan.

Jan. 19-22, Institute of Scrap Iron & Steel Inc.: Annual meeting, Eden Roc, Fontainebleau, and Deauville hotels, Miami Beach, Fla. Institute's address: 1729 H St. N. W., Washington 6, D. C. Executive vice president: Edwin C. Barringer.

Jan. 20-22, Truck Trailer Manufacturers Association: Annual meeting, Palm Beach Biltmore Hotel, Palm Beach, Fla. Association's address: 710 Albee Bldg., Washington 5, D. C. Managing director: John B. Hulse.

Jan. 20-23, American Road Builders Association: Annual meeting, Sheraton-Park Hotel, Washington. Association's address: 600 World Center Bldg., Washington 6, D. C. Executive vice president: Louis W. Prentiss.

Jan. 20-24, American Institute of Electrical Engineers: Winter meeting, Hotel Statler, New York. Institute's address: 33 W. 39th St., New York 18, N. Y. Secretary: E. O. Kirkendall.

Jan. 21-22, Steel Shipping Containers Institute Inc.: Winter meeting, St. Regis Hotel, New York. Institute's address: 600 Fifth Ave., New York 20, N. Y. Secretary: L. B. Miller.

To ease your needs for . . . **NEW CAPITAL EXPENDITURES**



This Ultra-Modern, High Precision **GEAR MAKING** Facility . . . . . **AVAILABLE TO YOU**

Simple arithmetic explains why, TODAY, many of America's leading manufacturers no longer undertake to solve the problems involved in making gears. For them, FAIRFIELD IS THE ANSWER!

Every facility is available at Fairfield — cost-cutting, ultra-modern equipment kept busy by volume production. This makes for economy and efficiency that can benefit YOU.

Check with Fairfield NOW on your gear production schedules. As one of the nation's largest independent producers, Fairfield can usually give you quickest service available and handle any production requirement. *Become a Fairfield customer; it pays!* CALL OR WRITE.

FAIRFIELD
MANUFACTURING CO.
2313 S. Concord Rd. Lafayette, Indiana
TELEPHONE: 2-7353



Gears and Differentials For FINE GEARS *Made to Order for:*

TRACTORS • HEAVY DUTY TRUCKS • AGRICULTURAL MACHINERY • POWER SHOVELS AND CRANES
MINING MACHINES • ROAD GRADERS • BUSES • STREET SWEEPERS • INDUSTRIAL LIFT TRUCKS

ENTHONE

Which metal do you want to strip?

There's an Enthone metal stripper for most applications:

☐ **ENSTRIP "S"** — an additive for sodium cyanide solutions used to dissolve nickel, copper, gold, silver, zinc, cadmium and alloys of these metals from steel without attacking the base metal in any way.

☐ **ENSTRIP "A"** —a fully-prepared alkaline mixture already containing sodium cyanide, used for the same purpose as Enstrip "S".

☐ **ENSTRIP "Z"** —an alkaline stripper that rapidly strips zinc from steel.

☐ **ENSTRIP 103** —an economical, alkaline electrolytic stripper for removing nickel, copper, brass, zinc, silver, gold, cadmium, tin and lead from steel.

☐ **ENSTRIP CR-5** —a rapid, acid-type dry salt stripper that dissolves heavy deposits of chromium from steel, nickel, copper base alloys, stainless steel and aluminum.

☐ **ENSTRIP "T-L"** —a fast-acting, dry alkaline stripper for dissolving tin, lead, solder alloys, tin-zinc alloys and zinc from steel base metals.

☐ **ENSTRIP 165S** — a neutral dry-additive for acid solutions for quick removal of nickel, tin, lead, zinc, cadmium, iron and aluminum from copper and copper base alloys.

☐ **ENSTRIP L-88** —a completely prepared acid electrolytic stripper for removing copper, nickel, chromium, brass, bronze, iron and white brass from zinc-base die castings.

These eight outstanding strippers are "stock" items in the Enthone line of chemicals for the metal finishing and electroplating industries. In most cases, one of the "Enstrips" will prove to be the answer to your problem. On the other hand, special developments are available from Enthone to meet requirements not covered by the Enstrips featured above. Write us, outlining your needs, and include a sample of your product, if possible. We'll be glad to recommend the best stripping method possible.

Write to Dept. S-12

DISTRIBUTION AND SERVICE THROUGHOUT THE UNITED STATES, CANADA, MEXICO, BRAZIL AND EUROPE

PRODUCTS OF Enthone THE SCIENTIFIC SOLUTION OF METAL FINISHING PROBLEMS

ENTHONE

ENTHONE
INCORPORATED
442 ELM STREET. NEW HAVEN 11, CONN.
Metal Finishing Processes • Electroplating Chemicals

SUBSIDIARY OF AMERICAN SMELTING AND REFINING COMPANY

Metalworking Outlook

Wave of Small Auto Strikes?

Look for a long series of small, but production-cutting strikes in the auto industry until next June 1. The United Auto Workers doesn't want too many cars in dealers' hands by the time auto contracts expire six months from now because that would dilute the effects of a major strike. A big walkout is likely in June (see Page 53). The assemblies of '58 models have already been hurt by work stoppages at General Motors Corp.'s Detroit Transmission Div. and Chrysler Corp.'s engine plant.

Teamsters Will Leave AFL-CIO

The Teamsters will probably get kicked out of the AFL-CIO this week. The nation's top labor federation holds its annual convention beginning Dec. 5. Its executive board has already recommended dropping the truck drivers. The Teamsters' president-elect, James Hoffa, has been busy trying to persuade local labor councils to swing enough delegates to defeat the ouster, but it doesn't look like he'll succeed.

Score on Russian Science Grads

As of mid-1957, the Russians had about 1.5 million graduates in all scientific disciplines, compared with 1.3 million in the U. S. What's more, about 15,000 Chinese and students from other satellite countries are studying in Russia. The U. S. has some 12,000 foreign students.

Needed: Office Revolution

An office revolution is long overdue in America, says R. C. Sollenberger, executive vice president of the Conveyor Equipment Manufacturers Association. A factory worker today can produce 14 times as much as his ancestor did 100 years ago, but productivity of the office worker has increased only 40 per cent in that time, he says, urging the use of more conveying equipment in the office.

Electronic Exports Dip, Imports Rise

Exports of commercial electronic equipment and parts have declined to $210.5 million during the first eight months of 1957, vs. $223.5 million in the corresponding 1956 period. During the same time, imports of radio and TV equipment and parts rose to $9.4 million, compared with $8.6 million for all of 1956. West Germany, Japan, and Great Britain are the major foreign sources (in that order), says Electronic Industries Association.

Machine Tool Orders Continue Slide

New orders for machine tools continue to slide, and shipments in 1957 may not equal the $886.2 million delivered in 1956. October bookings

dipped to $27.9 million, compared with $28.8 million in September, and $66.1 million in October, 1956. Average industry backlogs are down to 3.4 months. Look for net new orders to total about $525 million in 1957, compared with $924 million last year. The new order pace for 1958? About $500 million, believe some industry people.

Rectifier Sales Soar

Sales of semiconductor rectifiers and rectifier equipment will hit a high of $100 million this year and will pass $200 million in ten years. This year's volume is triple that of seven years ago, says General Electric Co.'s Frederick M. Spaugh. Rectifier components and equipment convert alternating to direct current in products ranging from household appliances to steel mill drives.

The Scrap Situation

About one-fifth of all iron and steel, copper, and aluminum that goes into America's metalworking factories comes out as scrap, reports the Business & Defense Services Administration. The average scrap generation ratio is 19.4 per cent for iron and steel, 20.3 per cent for copper, and 18.4 per cent for aluminum. Nearly two-fifths of the iron and steel industrial scrap reported was generated by the motor vehicle and part industry; over one-fourth of the aluminum by the aircraft industry; and almost one-fourth of the copper by manufacturers of valves, fittings, and plumbing fixtures.

Census on Housing

We had 55.3 million dwelling units in the U. S., as of Dec. 31, 1956, compared with 46.0 million as of Apr. 1, 1950. The Census Bureau says that represents an average annual gain of about 1.4 million units, exceeding the average annual gain of 870,000 units between 1940 and 1950.

Straws in the Wind

Firth Sterling Inc., Pittsburgh, has received a $1.5 million contract to produce 40,000 lb of zirconium alloy mill products a month for one year. They'll be used by Westinghouse Electric Corp. in atomic power applications . . . Universal-Cyclops Steel Corp., Bridgeville, Pa., will acquire Empire Steel Corp., Mansfield, Ohio, and Reeves Steel & Mfg. Co., Dover, Ohio; a wholly owned Universal-Cyclops subsidiary, Empire-Reeves Steel Corp., will be formed to operate the Mansfield and Dover plants . . . Large quantities of high-grade iron ore concentrates will be available in the state of Minas Gerais, Brazil, according to a survey conducted for Brazil by Armour Research Foundation . . . GM's hourly employees won't get a cost-of-living boost in the next three months because the consumer price index hasn't gone up sufficiently . . . The U. S. auto industry will produce about 6.2 million cars in '57—1.5 million in the fourth quarter, compared with 1.3 million in the third, 1.6 million in the second, 1.8 million in the first . . . U. S. Steel Corp. hopes to build 12 big lake ore carriers.



Potomac Curtain

Adding to the confusion on the Potomac resulting from Sputniks I and II is the curtain dropped by the Defense Department on essential information needed by industry.

For contrast, let's turn back to World War II. In February, 1942, Donald B. Nelson, war production director, called the editors of STEEL and other business publications to Washington. Mr. Nelson said many of the golden months in which the nation could have prepared were wasted. Only ten months remained in crucial 1942 to stop the onrushing enemy. One plane or tank made in 1942 would be worth ten made in 1943.

The business publications were asked to give industry the word on what was needed and how to make it—and to do it quickly. Washington had no way to establish lines of communication except through time-consuming contact work in the field.

The publications told industry where to get contracts, what materials were needed, what the production problems were, and how to solve them through improved techniques.

Industry, fully mobilized, literally swamped the enemy with airplanes, ships, field artillery, tanks, and other materiel that streamed from its factories.

The situation today is potentially more serious than the one we faced in World War II. Only the cast and setting are changed. We are faced by a more formidable and ruthless enemy. His industrial might is comparable to our own, and he is armed with new weapons that can bring a new conflict to our shores at any moment.

The pressing problem is how to catch up with the Russians quickly on missiles. The solution requires suppression of the rivalry, bureaucratic bungling, and inefficiency among the armed services.

More than that, it requires lifting the curtain on information needed by industry so it can help the nation out of its dilemma.

That the Pentagon is not doing.

Irwin H. Such
EDITOR-IN-CHIEF

P.M. of another good day

"Good" because this Inland Steel mill representative has just spent the day with a custome Tired though he is, he's had the satisfaction of helping another steel user solve a knotty problen That's his job—his and other Inland men like him who bring expert metallurgical knowledge t every assignment. They can help you select proper steels, establish specifications and may eve suggest techniques to speed production, lower manufacturing costs. It's this kind of service tha makes it good business to call on Inland for your steel needs.

INLAND STEEL COMPANY • 38 South Dearborn Street • Chicago 3, Illinois

Sales Offices: Chicago • Milwaukee • St. Paul • Davenport • St. Louis • Kansas City • Indianapolis • Detroit • New York

Average Negotiated Wage Boost in '58: Still High?



*Estimated by STEEL. Source for other figures: Associated Industries of Cleveland, for bellwether northern Ohio area.

'58 Worries Labor Unions

Auto workers show some signs of moderation, but they'll still seek a 40-cent package, plus the short week. An auto strike is likely next year, probably against GM

AN AUTO STRIKE, probably against General Motors Corp., next June 1 is likely.

Although the expiration date for GM, Ford Motor Co., and Chrysler Corp. contracts is still six months away, enough indirect maneuvering has already taken place to indicate the strong possibility of an impasse. Examples: The "$100 affair" at which United Auto Worker President Walter Reuther suggested and auto companies rejected a price reduction on 1958 models; speeches on both management and labor sides which indicate positions that are poles apart.

Why GM?—Ford, Chrysler, and American Motors Corp. all want to bargain jointly with the UAW as an industry. GM favors separate negotiations because it believes its bargaining abilities are superior and because it doesn't want to be bound by an industry compromise. The UAW also favors separate parleys because it has waxed strong on divide-and-conquer tactics. If the union goes after anyone but GM first, it fears the chance of a near-united front against it.

That's the main reason GM will probably be the prime target next spring. It is also in the best position economically to stand a strike, if there is one. The UAW is no charitable organization, but it doesn't want a strike to ruin a company. On the basis of ability to weather a walkout, Ford would be target number two.

The Pattern—Whatever the auto agreement turns out to be, it will prove the most important settlement in 1958 because it will set the pattern for others next year

Fringe Benefits: Average Hourly Cost per Employee

(For northern Ohio firms surveyed by Associated Industries of Cleveland)

	1955	1957
Bargaining & Grievance Time	$0.0042	$0.0047
Bonuses (excluding production)	0.0332	0.0299
Cafeterias	0.0069	0.0044
Credit Unions	0.0036	0.0011
Death in Family (pay for time not worked)	0.0017	0.0024
Education	0.0023	0.0038
Free Coffee, Milk, etc.	Not Included	0.0066
Gifts & Awards	0.0041	0.0315
Holidays (pay for time not worked)	0.0513	0.0570
Insurance		
Group Life	0.0125	0.0128
Sickness & Accident	0.0122	0.0158
Hospitalization	0.0192	0.0278
Surgical-Medical	0.0086	0.0082
Hospitalization (Surgical-Medical)	0.0358	0.0470
Total Cost of Group Life, Sickness & Accident, Hospitalization (Surgical-Medical)	0.0510	0.0623
Jury Duty (pay for time not worked)	0.0021	0.0016
Legally Required Payments		
Old Age & Survivors Insurance	0.0396	0.0483
Unemployment Compensation	0.0107	0.0112
Workmen's Compensation	0.0136	0.0163
Total Cost of Old Age & Survivors Insurance, Unemployment Compensation, Workmen's Compensation	0.0638	0.0729
Lunch Periods (pay for time not worked)	0.0259	0.0307
National Guard, Army & Naval Reserve (pay for time not worked)	0.0006	0.0004
Pensions	0.0869	0.1142
Profit Sharing	0.1120	0.1720
Recreational Activities	0.0058	0.0063
Rest Periods (pay for time not worked)	0.0639	0.0811
Severance Pay	0.0026	0.0007
Sick Leave (pay for time not worked)	0.0471	0.0391
Supplemental Unemployment Benefits	0.0500	0.0381
Uniforms, Work Clothes, Gloves, etc.	0.0052	0.0070
Vacations (pay for time not worked)	0.0851	0.1083
Wash-Up Time (pay for time not worked)	0.0314	0.0312
Welfare Funds (Money, Flowers, etc.)	0.0043	0.0017
Miscellaneous	0.0048	0.0177
Total average cost of employee benefits	**$0.3854**	**$0.4950**
Average number of benefits per company	**11.2**	**12.1**

and even in 1959. The first big 1958 metalworking negotiations will be in aircraft next March and April. They'll be followed by: The climactic auto talks; negotiations in farm implements in July and August; and sessions (covering only employee security) in electrical equipment (General Electric Co. and Westinghouse Electric Corp.) in October.

In aircraft, look for relatively modest settlements—under 8 cents an hour for wages and less than 2 cents an hour for fringes. (International Association of Machinists will demand 26 cents in wage hikes plus fringes.) The metalworking average for the year will be somewhat higher because the auto pattern will be higher—about 8 cents in wages (see Page 53) and 2 or 3 cents in fringes (see table at left).

UAW Demands—The auto companies would be delighted to get off with the metalworking average. At this time, it looks like the UAW will demand 30 cents an hour in wages, plus 5 cents for more pensions and insurance, 2 cents for an additional paid holiday, and 3 cents for miscellaneous fringes, including more for Supplemental Unemployment Benefits.

The 40-cent package doesn't include the short-week demand. It will be presented this way: Start premium pay after 32 weekly hours, not the present 40. To its members, the UAW will soft-pedal the possibility of reduced hours, having discovered they are not enthusiastic about less work time. Instead, it will plug the fact that a 40-hour week, with overtime beginning at 32 hours, would boost earnings by 10 per cent even if the base pay remains the same. Possible compromise: **Premium hours** to start after 36 or 38.

Softened? — Possibly — but not probably—those demands will be softened next Jan. 23-25 when the UAW goes into convention at Detroit to hammer out the final package. The 1958 economic outlook holds little promise of more than a 6-million sales year in autos, about the same as the 1957 figure. With such production, the automotive industry had fairly serious layoffs this year. The UAW knows it can't go too far with demands.

On the noneconomic side, the UAW will seek a two-year, not a

hree-year contract. It wants orker protection in plant reloca- ion and separate contracts for killed employees.

UAW Position—The auto union, f course, doesn't dream of win- ing its full demands. In an Oc- ober speech, Mr. Reuther said: "The collective bargaining road vill not be strewn with roses (be- ause of) underproduction, reduced onsumer purchasing power, and he industry's price-raising in the ace of lowered demand."

Students of the UAW president's hetoric claim he sounded unusual- y cautious. Some management op- imists believe he's trying to pre- pare the members for a mild set- lement. As a politician, he's in a tough spot. Auto workers used to be the best paid in America. Here's how they stand now (latest figures for average gross straight-time hourly rates):

Petroleum & refining	$2.79
Blast furnace, steel	2.71
Tires, rubber	2.61
Railroad equipment	2.53
Automobiles	2.47

What's more, Mr. Reuther must settle (or strike) by June 1, while the steel employees automatically get about 10 cents more one month later. In 1957, his auto people got 6 cents in straight wage boosts, but steelmen got an average 10.4 cents (not counting cost-of-living increases in either case). To just stay even with steelworkers, the UAW chief must win 14.4 cents in wages for his men.

Auto Position—Auto companies believe their hand is strong. They'll argue that higher wages will bring on more inflation (union leaders are unusually sensitive about this). They'll play for public opinion's support, as never before. For example, GM next month will start a wide publicity campaign to show what higher wages and the short week could do to the economy.

Revelations about corruption in some unions won't directly enter next spring's talks, but indirectly that issue will play a part. It has put all labor on the defensive with the public. It's no accident that the auto companies are going to the public in '58 with their case.

• *An extra copy of this article is available until supply is exhausted. Write Editorial Service,* STEEL, *Penton Bldg., Cleveland 13, Ohio.*

Philadelphia Story

Quaker City area has steel capacity of 17 million ingot tons, 60% of eastern district

PHILADELPHIA is the center of a 100-mile circle that contains more than 60 per cent of the steelmaking capacity of the eastern district. More than 17 million tons can be made in the area annually, says Max D. Howell, executive vice president, American Iron & Steel Institute.

Mr. Howell told a regional AISI technical meeting in Philadelphia that the eastern district will produce a record amount of raw steel this year. "It will probably turn out over 25 million tons of ingots and steel for castings this year for the first time," he said.

The eastern district has increased its production 96 per cent since 1946, he said; the national rate is 71 per cent.

Foreign Ore Climbs — The increase of foreign ore shipped into Delaware River ports is even more remarkable, Mr. Howell said. The first half of 1957 saw a 20 per cent hike over the same period last year. The total for 1956 was 10.6 million tons, compared with less than 1 million in 1950.



Huge Welding Positioner

Bethlehem Pacific Coast Steel Corp.'s San Francisco shipyard built it for Mare Island Naval Shipyard, Vallejo, Calif. Weight: 100 tons. Height: Over 20 ft. Table diameter: 33 ft. A 2000-lb hydraulic system tilts the table to angles up to 60 degrees

Steel Labor Force Stable

An AISI survey of 88 per cent of the steel producing industry shows that the average age of employees in 1956 was 42; average length of service of each worker with his present employer was 13 years. The figures were the same in 1955.

Of the hourly steelworkers, 19 per cent were 18 to 29; 27 per cent were 30 to 39; 26.5 per cent were 40 to 49. Twenty-seven steelworkers out of each 1000 were over 65 and had elected to remain employed rather than retire with pensions and social security benefits.

Thirteen per cent of all hourly employees had been hired after 40.

Doxsey Aids Chilean Group

Walter S. Doxsey, former president of the American Steel Warehouse Association Inc., Cleveland, is advising a group of Chilean metalworking associations on trade association practices and policies.

A graduate of Case Institute of Technology, Cleveland, he was editor of *Daily Metal Trade,* once a sister publication of STEEL, from 1927 to 1934. Before retirement, he was president of the warehouse association for 21 years.

While in Chile, he will help found an institute for all steel producers in Latin America. It will compile steel and iron statistics for Latin America and—in co-operation with the American Iron & Steel Institute—for the Western Hemisphere. Twenty other U. S. associations in the steel industry will also participate.

Mr. Doxsey's address in Santiago, Chile, will be the Hotel Carrera.

Give Utility Program Cost

Under the three postwar planning programs for water and sewerage construction projects partially financed by the federal government, 1373 remain to be built, reports the Department of Commerce. They will require about $880 million for completion, in terms of 1956 construction costs.

The Next Ten Years in Appliances

	CABINET RANGES		CUSTOM RANGES		REFRIGERATORS	
Year	Shipments	% Saturation	Shipments	% Saturation	Shipments	% Saturation
1967	900,000	17.2	1,600,000	19.8	5,100,000	97.15
1963	900,000	21.8	1,150,000	11.7	4,500,000	96.9
1961	950,000	24.0	925,000	8.1	4,100,000	96.7
1960	975,000	25.0	800,000	6.5	3,900,000	96.5
1959	1,000,000	25.8	650,000	5.1	3,700,000	96.3
1958	940,000	26.3	500,000	4.0	3,500,000	95.9
1957	920,000	26.8	420,000	3.1	3,320,000	95.4

	DISHWASHERS		DISPOSERS		AUTOMATIC WASHERS	
Year	Shipments	% Saturation	Shipments	% Saturation	Shipments	% Saturation
1967	1,140,000	14.4	1,200,000	17.5	4,100,000	51.2
1963	750,000	10.1	870,000	12.9	3,950,000	49.2
1961	600,000	8.3	730,000	10.9	3,750,000	45.6
1960	540,000	7.5	660,000	9.9	3,650,000	43.3
1959	475,000	6.6	600,000	9.0	3,450,000	40.5
1958	415,000	5.9	550,000	8.2	3,200,000	37.7
1957	360,000	5.2	500,000	7.4	2,800,000	35.0

Hotpoint Co. predicts the electric appliance industry will ship about 286 million major appliances with a value exceeding $85 billion during the period. Sales of built-in ranges will increase ten times. Water heaters will find only a replacement market. Washer-dryer combinations will move to replace single units; color will overtake black and white TV, according to the firm's ten-year forecast.

FREEZERS		AIR CONDITIONERS		WATER HEATERS		WIRED HOMES
Shipments	% Saturation	Shipments	% Saturation	Shipments	% Saturation	(millions)
1,110,000	28.8	3,700,000	32.0	760,000	16.7	58.2
1,070,000	25.6	2,900,000	23.4	800,000	17.8	54.6
1,040,000	23.5	2,500,000	18.6	800,000	18.3	52.8
1,020,000	22.4	2,200,000	16.2	800,000	18.6	51.9
1,000,000	21.3	2,000,000	14.0	825,000	18.8	50.9
950,000	20.1	1,800,000	11.7	835,000	18.9	49.8
890,000	19.0	1,750,000	9.8	790,000	19.03	48.6

DRYERS		WASHER-DRYERS		TELEVISION SETS		WIRED HOMES
Shipments	% Saturation	Shipments	% Saturation	B/W Shipments	Color Shipments	(millions)
1,925,000	27.1	1,900,000	15.0	2,600,000	8,500,000	58.2
1,675,000	21.7	1,100,000	7.0	4,800,000	5,200,000	54.6
1,500,000	18.1	700,000	4.0	7,200,000	2,000,000	52.8
1,400,000	16.2	550,000	2.8	7,700,000	1,000,000	51.9
1,300,000	14.4	400,000	1.9	7,700,000	450,000	50.9
1,150,000	12.6	260,000	1.2	7,350,000	300,000	49.8
900,000	10.8	165,000	0.7	6,800,000	200,000	48.6

Starts Mining Rutile

Metal & Thermit Corp. re-enters domestic market with $1.25-million investment in Virginia

METAL & THERMIT Corp., New York, is making a bid for the domestic titanium ore (rutile and ilmenite) market. It's counting on its mine and ore processing plant in Hanover County, near Richmond, Va., to supply 12 per cent of the nation's rutile needs next year. About 70 per cent now comes from Australia. Florida (see STEEL, Sept. 2, p. 97) and South Carolina were the only two previous domestic sources.

The processing plant has a capacity of 100 tons per hour. Its annual output is rated at 5000 tons of rutile, worth about $1 million. Rutile and ilmenite reserves on the 800-acre tract are expected to last 10 to 20 years.

Operation—Ore will be stripped at depths of 1 to 18 ft. Via a belt conveyor, it will be fed to an outside hopper, then to the processing plant. After being crushed, ground, and separated by water, gravity, electrostatic and magnetic devices, it will be kiln dried and bagged.

A water recycling process prevents contamination of the nearby South Anna River. Water is taken from the river, piped to the plant, then sent to a waste disposal system where the silt settles into 20 acres of wasteland.

Markets — Titanium production takes about 50,000 tons of rutile annually. In 1956, about 13,000 tons went into coatings for welding electrodes—by 1960 this market is expected to hit 20,000 tons. Other uses, accounting for some 7000 tons in '56, are in the manufacture of chemicals, ceramics, and glass.

Ilmenite serves as the basis for white pigments in paints, lacquers, varnishes, rubber, linoleum, and textiles. The U. S. consumed 865,000 tons in 1956.

Edwards Adds Third Plant

Edwards Co. Inc., Norwalk, Conn., reports that its new plant at Pittsfield, Maine, is operating at near capacity. Full operation is expected before the end of the year, when employment will reach 125. Products produced include doorbells, buzzers, door openers, transformers, pushbuttons, and contact devices.

Maker of Controls Builds

Controls Co. of America is building a 20,000 sq-ft manufacturing plant at Crystal Lake, Ill., for its wholly owned subsidiary, Lake City Inc. The plant, expected to cost about $180,000, will be in operation in early 1958. It will employ 200 to 300 to make automatic timers and synchronous timing motors. Lake City's present quarters will be leased or sold.

The company is also building a plant at North Manchester, Ind.

Detroit Firm Expands Lab

Michigan Chrome & Chemical Co., Detroit, broke ground at its Grinnell Avenue plant for an 18,000 sq-ft laboratory addition. It will be used by the firm's plating and chemical divisions.

Special sections will be assigned to plating control, new product research, chemical product development, and technical service. Also included will be a plating pilot plant, chemical pilot plant, instrument lab, library, light equipment room, and conference room.

J&L Gets More Water

Jones & Laughlin Steel Corp.'s Aliquippa (Pa.) Works can now pump 345 million gallons of water per day from the Ohio River. By means of underwater construction, bridge building, tunneling, and crosscountry pipe laying, Dravo Corp., Pittsburgh, boosted the supply 40 million gallons.

Installed were two 40-million-gallon per day pumps (one is on emergency standby), traveling water screens in the river intake, a bridge, three-quarters of a mile of 42-in. line from the pumping station to rolling mills, and a 40-ft tunnel that's 17 ft below the mill floor. Also added was a third line to the five Aliquippa blast furnaces to provide uninterrupted water service.

Divers had to remove 25 tons of steel which were 30 ft under water to install the intake water screens.

Furnace Treats Zirconium for Atomic Reactor Use

Wolverine Tube Div., Calumet & Hecla Inc., built this special furnace at its Detroit plant to treat zirconium alloy tubing under vacuum. (Furnace gases contaminate the metal.) A ram pushes the tubing through the cooling section into the furnace; it's heated and the ram pulls it back into the cooling section

GSA To Sell Nicaro Plant

Ample supply, the administration's policy to get out of competition with private industry, and no fear of a giveaway under present conditions prompt the offer

THE GENERAL Services Administration is campaigning to get rid of its nickel plant at Nicaro, Cuba. It sent brochures to over 300 U. S. firms, offering to sell or lease. About 20 have expressed interest. A few have sent representatives to Washington and Cuba to dig up operating facts and check profit potentials.

Inco Is Out—The facility with an annual capacity of 50 million lb will not be sold to a foreign firm, which eliminates International Nickel Co. But, says a GSA spokesman: "We would favor some sort of private Cuban participation in the ownership." GSA unofficially does not look forward to the Cuban government buying in.

The plant is being operated for the U. S. by a subsidiary of National Lead Corp. Its contract expires Dec. 31, but it will be extended to cover the bidding time.

Timetable—GSA hopes to call for sealed bids by Dec. 31 and announce the winner by March. The possibility that National Lead will stay is strengthened by a GSA spokesman's comment that one firm wants it that way. National Lead may submit a bid.

GSA is advising all bidders to submit offers to buy and lease. It is generally agreed in Washington that a sale is preferred, but GSA will lease if it doesn't get a price that will stand up before Congressional criticism and meet its stated decision to take nothing less than $85 million.

GSA is offering full co-operation to all interested bidders because of the complicated nature of Nicaro. One firm estimates it will cost it $100,000 to prepare a bid. After running the facility for five years, National Lead has good insight into its potential—presumably, that's one reason for GSA's open-door policy on information.

Over Capacity—In October, the plant produced 4.2 million lb, a little better than its capacity. November also ran over, with 19 of 21 furnaces operating. (Two are always down for maintenance.)

Sales Clauses—A buyer, says GSA, will have to make 75 per cent of his production available to U. S. consumers at current market prices. The sale will also be subject to the National Reserve clause, keeping it available for defense needs.

The agency is negotiating with Cuba on taxes. The government pays none. Cuban laws allow special benefits for new industries, so the buyer could receive exemptions to the point where he paid a tax of only about 17 per cent of net income.

Ample Supply—All ore now comes comes from a subsidiary of Freeport Sulphur Co., though under that contract, only one-third of Nicaro's consumption must come from there. The contract can be canceled on six-month notice. GSA believes it can be assigned to the new owner.

However, in 90 days, a railroad will be completed which will enable Nicaro to get to U. S.-owned ore bodies never before touched. They will be sold with the plant and railroad. There is a 17-year supply (39 million tons) of ore there, compared with a 25-year supply belonging to Freeport.

Labor Situation—GSA discounts civil strife in Cuba, reporting there has never been any trouble at Nicaro. The plant has 3140 employees, but 900 are on construction projects. Normally, it takes 2400 men to run the unionized plant. Annual labor turnover is less than 1 per cent.

Financial Statement—As of Aug. 31, Nicaro shows assets of $87 million, including $1.2 million in cash, $1.2 million in accounts receivable, $12.5 million in inventories.

Net sales were $22.4 million in the year ended June, 1957. Net profits were $5.2 million. The ratio of profits to sales must take into consideration the tax arrangements with Cuba. Sales in the 1955-56 fiscal period were $16.8 million, with profits of $2.9 million.

Sinter production from the 1955-56 period to the 1956-57 period jumped from 28.6 million lb to 31.3 million lb. Ingot output went from 2.8 million lb to 14.3 million lb.

A view of the Nicaro nickel plant which GSA is trying to sell or lease

Plans Center for Societies

A $10-million United Engineering Center is planned for the United Nations Plaza in New York City. It will serve as headquarters for 16 national engineering societies, replacing the Engineering Societies Bldg. in New York. Occupancy is scheduled for the fall of 1960.

The building will be financed by $2 million from present sources, $3 million from society members, and $5 million from a business and industry campaign.

Do Defense Dollars Keep Economy at Par?

TO PUT the question another way: Does spending for defense contribute to, or detract from, the national wealth? You have heard this statement: We are spending ourselves into bankruptcy!" You have also heard: "Without defense dollars, we'd all be out of work!"

Both are extremes, but the question should be resolved, says the Joint Economic Committee's Subcommittee on Fiscal Policy. With sputniks aloft, Rep. Wilbur Mills (D., Ark.) admits his group is not ready to cut the Defense Department's budget, but, he believes, along with many sincere congressmen, that we can't write a blank check payable to the Pentagon.

When Congress returns in January, some enthusiasts (perhaps more than we expect) will be ready to write that check. The administration says we can compromise; how well it controls the headstrong Congress remains to be seen.

Crash Programs Are Outlined

Here are two examples of what Congress will soon be talking about: 1. The Army's plan to spend $7 billion on an antimissile missile. 2. Sen. Henry Jackson's (D., Wash.) proposal for 100 atomic submarines at $45 million each. Equipped with the Polaris missile, they would cost over $5 billion.

That money would provide an immediate stimulus, agree most economists, but the long range effect might be something else, some argue. The submarine dollars might directly affect our capacity to deliver heavy plates to normal users, while the antimissile dollars could tie up enough scientific personnel to slow consumer product development.

There is no rule of thumb to calculate the most compatible level of spending, although some administration economists argue this way: Russia appears to be operating at her maximum capability. If she is ahead of us at all in development and production of the ICBM and IRBM (and perhaps more fantasic weapons), she is as far ahead of us as we can allow. Any increase in our defense effort will shorten the gap. Administration economists say we need not endanger the economy with a defense budget of, say $50 billion (with corresponding tax hikes or deficit spending); we need one of only about 10 per cent of our gross national product (GNP), $43 billion at most, to enable us to close the gap rather fast.

10% of GNP Will Support Defense

Assuming a normal rise in GNP of $15 billion annually, we can afford to boost our defense budget $1.5 billion a year. We are currently supporting a defense budget of 10 per cent of the GNP. If tax receipts hold, we can pay for it out of new income without any tax hikes.

That's the way we may attack the defense budget for fiscal 1959. At the Mills hearings, David Novick, chief cost analyst for Rand Corp. (a nonprofit group specializing in futuristic weapons), pointed out that we cannot spend much more in fiscal 1959 than we did in 1958 because we didn't make the plans in 1955 or 1956. Leadtime on the new weapons, including missiles, is the determining factor.

Hints from high government officials indicate a spending program of $40 billion at the most for defense (not including foreign aid) next year. If we incorporate the new weapons programs for manned satellites, for example, into our budget, we won't spend much more money for at least another two years.

Consensus: A spending program of $45 billion in fiscal 1960 is probably realistic, in terms of both needs and ability to pay.

Atom Power Czar Is Added

Since sputniks, we've added a man (a special science adviser to the President) to the corps of people most responsible for our defense. We have given our missile chief a little more responsibility. And we will name a space weapons manager soon. Last week the Pentagon continued to fatten the line-up by giving Air Force Maj. Gen. D. J. Keirn, chief of the Atomic Energy Commission's aircraft reactors branch, the additional duties of heading a Defense-AEC project on atomic power for aircraft and missiles.

The move was reportedly at the request of the Joint Atomic Energy Committee, which continues to be excited about neglect of the atom-powered airplane. One Pentagon source figures Russia will beat us to that, too.

Flanders Hits Escalator Clauses

Sen. Ralph Flanders (R., Vt.), a machine tool company owner, hits escalator clauses as "disastrous" to industry and labor. Seeking a formula for basing wage boosts on productivity increases, the senator suggests Congress take a look at the possibilities of dividing profits achieved by automation into three equal parts: 1. As a wage hike. 2. As profits. 3. As a reduction in the cost of goods.

The idea found some favor before Rep. Wright Patman's (D., Tex.) Economic Stabilization Subcommittee. Representative Patman, incidentally, recognizes the good in automation, as well as its necessity.



Valves Show Steady Rise*

	Sales
1957	$1,359,000,000†
1956	1,270,400,000†
1955	1,104,660,000
1954	969,500,000
1953	977,850,000
1952	958,200,000

†Estimated by STEEL.
Other figures: Census Bureau.
*All valves, except plumbing.

Warner & Swasey Co.

Expanded applications for hydraulic control types help . . .

Valve Sales Hit Record

WHILE MANY industries find their sales leveling off or declining in 1957, valve producers expect to set another record. They're looking for a 7 per cent increase in dollar volume.

The main reason for the showing is the tremendous growth of hydraulic control valves. Sales have climbed over 400 per cent in the last ten years to a dollar volume of $160 million plus this year.

Outlook—Not quite so bright is the picture for 1958. While half the producers queried by STEEL expect sales to continue at this year's level, 30 per cent think 1958 will be worse; 20 per cent expect sales to keep on climbing.

C. B. Hunt & Son Inc., Salem, Ohio, thinks sales in 1958 may be off slightly but that another upturn will begin late in the year. Proving its optimism, the firm is adding 27,000 sq ft of manufacturing space and spending $100,000 for new equipment. Several firms specializing in solenoid-operated valves are looking for 10 to 20 per cent higher sales in 1958. The reason: Continued emphasis on automation.

Says one Eastern manufacturer: "Valvemakers traditionally don't feel the leveling off as soon as some of the other component people. It's possible that our business will dip during the first half of 1958." Some such signs are already showing. Backlogs are generally about 15 per cent below their year-ago levels. Most producers report orders have slowed down slightly in the fourth quarter.

New Horizons—In addition to the numerous new applications found each year, whole new markets are now opening in nuclear power, missiles, and high pressure chemical systems. Lawrence Gardner, president, Airmatic Valve Inc., Cleveland, says 347 stainless has a fine potential in missiles because of its resistance to varied atmosphere, temperature, and fungus conditions.

Bronze and brass continue to be the materials most used, though stainless, 5 per cent nickel iron, and aluminum have gained wide popularity in the past year. Carbon steel and cast iron continue to hold a big chunk of the market. Some copper is used. Edward Valves Inc., East Chicago, Ind., reports that 18-8 stainless steels show the best growth potential. Robert G. Hess, executive vice president, Walworth Co., New York, feels that recent advances in nodular iron will increase its use for valves.

Growing — Polyvinyl chloride sales have doubled in the past year. PVC is used in valves for oil and gas, irrigation, food, and chemical processing industries. Its growth potential is good because it offers: 1. Corrosion resistance. 2. Lightness. 3. Smooth interior walls. 4. Resistance to galvanic and electrolytic action. 5. Low maintenance cost.

On the minus side: Its strength is less than one-fifth that of steel; it loses shape at high temperatures.

Competition — Price cutting is prevalent in the industry. Says one Midwest producer: "There are over 700 firms that make valves. A lot of the business is done on fixed price contracts. We throw away our price lists when we bid on these long term jobs." Low cost imports from Italy and Japan are a complicating factor.



Sales blossom better, says DeVilbiss, when you're . . .

Growing the New Products

WHAT else can it be used for? How can it be modified?

Seeking answers to these questions about each of its 1200 products has enabled DeVilbiss Co., Toledo, Ohio, to come up in the last two years with ten new or modified items or uses for existing ones to add to its widely diversified line.

Idea Is Born—"By accident we discovered a new application for an old product which greatly increased its sale," says Henry M. Kidd, vice president-sales. "We decided that everyday operations might be blinding us to possibilities lying all around. So we took two of our young engineers with high degrees of curiosity and formed a Products Analysis & Market Research Dept."

The two curious young men—William T. Miller and Wesley C. Smith—began a careful scrutiny of DeVilbiss' products, ranging from a tiny perfume atomizer to a 2000-lb compressor.

They spent hours studying advertisements in business magazines. Whenever they found a product that resembled something DeVilbiss makes, they dug deeper. They asked themselves: Can our product be made to do the same thing economically? Can we improve on it? Is there a market?

Wild Geese — "They went on many a wild goose chase," says Mr. Kidd, "which was to be expected." But DeVilbiss, a manufacturer of spray paint equipment, has greatly increased its sales with new applications or new products.

One day, an office machine repairman was having difficulties in the DeVilbiss office. He had to get an anticorrosive onto a small connection buried inside the wires and rods of a complicated machine. He was trying to avoid dismantling it.

Mr. Miller happened by and watched the serviceman drip the fluid into the machine, hitting everything but the connection. Mr. Miller went away and returned with a medicinal atomizer with a long, thin nozzle.

Bull's-Eye—"Will this help?" he asked. The repairman tried it. Success was immediate. "Where can I get one of these?" he asked. He was told to keep that one and DeVilbiss was off with a new product application. The item has become standard in repair kits for radio, TV, and office machines.

While on a social visit, one of the engineers watched friends go through the tedious job of changing the water in a home aquarium. The next day he was back with small air compressor used b asthma sufferers.

It aerated the tank completel and continuously to the delight c the fish fanciers. It is now bein used throughout the country fo large and small aquariums.

Gun Gives Fun—A hand greas gun which DeVilbiss has long mad for industrial uses was modifie for use by lumbermen. Markin trees for the cutters required th worker to fight or cut his wa through underbrush to daub re paint on the tree to be cut.

Now he rarely gets off his horse He fires a glob of red paint at th desired tree from as far as 20 f away, marking it plainly.

"All these, and others, have pro vided new markets for basic De Vilbiss products at little researc cost except the salaries of ou two curious young engineers," say Mr. Kidd.

"Our approach is probably th most unscientific anywhere, but i is paying off."

Here's an example of a projec that hasn't matured yet, but which DeVilbiss hopes will eventu ally ripen: Mr. Smith has spent some time riding garbage barges into and out of New York doing research on the possibility of de odorizing the refuse.

Firm Expands Lab System

Federal Pacific Electric Co. has set up new testing and develop ment units at Newark, N. J., Northampton, Pa., and Palo Alto, Calif.

At Newark, low voltage research is carried on in a lab designed for alternating and direct current studies, with currents ranging up to 10,000 amperes. The range of work includes bus duct, service entrance equipment, molded case circuit breakers, motor controls, switchboards, and panelboards.

Medium and high voltage product performance is measured at Northampton and Palo Alto. Analyzed are internal corona, transient voltage recovery rates, and mechanical, heating, and dielectric factors affecting oil circuit breakers, distribution transformers, disconnect switches, and high voltage bushings.

While important, new products will fail unless you're . . .

Growing the New Markets

WHAT do you do after you have unearthed new markets for new or present products? DeVilbiss and others experienced with this situation agree: Spurring salesmen to develop new markets when there's no promise of a quick return is one of metalworking's toughest assignments.

Brooks & Perkins Inc., Detroit fabricating firm, faced that problem when it brought out an ambulance litter that permits moving an accident victim from the scene of his mishap to a hospital bed without recourse to other carriers for any treatment he may get.

A. O. Smith Corp., Milwaukee, had trouble of the same kind when it began production of home heaters and air conditioners. Reynolds Metals Co., Richmond, Va., meets the problem every day in promoting new automotive applications for aluminum.

What Price Success?—The companies agree that it takes more than money to get results. It's hard enough to enlist the support of new salesmen, harder still to mobilize the old timers. In the absence of clearcut rules, the companies have tried these methods:

Rent To Buy—To penetrate an unfamiliar market (medical) with a brand new product (Transaver), Brooks & Perkins turned its ambulance litter over to three hospital supply companies which had large distributor organizations. For the first quarter of 1957, results were disappointing. Although the $800 Transaver cost substantially more than competing stretchers, it got little attention from salesmen accustomed to selling $30,000 x-ray machines. A jobber in Tennessee hit upon the idea of renting the stretcher to hospitals and allowing them to apply 70 per cent of the accrued payments to the purchase price. His sales have quadrupled since last spring.

In addition, Brooks & Perkins is sending its own salesmen into the field to help build up markets. Sales Manager Harry Dunne explains: "Each prospect our men turns up is handed over to the local dealer to show him we're trying to help. What our men lack in medical sales experience, they more than make up with a fresh, enthusiastic approach."

Task Force—A. O. Smith used a similar method in developing a market for its home heating and air conditioning units. Result: Sales doubled in two years. Says Stanley E. Wolkenheim, marketing director: "These products were aimed at a market which was new to us, so we trained five salesmen to sell them and to show our district representatives how to handle the products." Mr. Wolkenheim thinks the task force method works well in itself, or as a supplement to incentive quotas.

Creative Selling—Finding markets for products which haven't been developed calls for a different approach. John Blomquist, Detroit regional sales manager for Reynolds Metals Co., explains: "First we propose a new application for aluminum. Then we create a product that will function properly in the application we suggested. To sell our idea, we must convince the manufacturer that a change will save him money."

To meet Reynolds' requirements, a salesman must have high potential. "Only one job applicant in 15 is accepted," says Mr. Blomquist. "Ninety per cent are under 26. All take a 12-week course aimed directly at creative selling in an expanding market."

Does creative selling pay off? M. F. Garwood, Chrysler Corp.'s chief materials engineer, says within a few years his company will use 50 per cent more aluminum in trucks and cars than it did in 1957.

Summary—You can get off on the right foot in new markets, experts agree, by using incentive quotas, a special selling task force, extra help for distributors, or unusual devices such as rent-to-buy plans. They add up to the need for special creative approaches.

• *Extra copies of the product and market articles are available until supply is exhausted. Write Editorial Service,* STEEL, *Penton Bldg., Cleveland 13, Ohio.*

To Open Computer Center

Mid-Century Instrument Corp., New York, will open its $250,000 Manhattan Computer Center in February. Work on the high precision analog facility was started last June.

The firm has received security clearance and is booking time at $28.50 per hour for the use of 48 amplifiers. It expects to operate continuously seven days a week.

Robert Stern, Mid-Century president, expects many small firms working as defense subcontractors to use the facilities.

We hate to admit it but we had trouble with a **Bellows Air Motor** in Reading, Pennsylvania

Bellows Air Motors — the unique air cylinder with the built in valve — have established enviable records for trouble free performance. Operating cycles of 20,000,000 to 30,000,000 without maintenance of any kind are quite common. Fifty million cycles nothing unusual.

But trouble sometimes occurs — even in the best regulated families. A few weeks ago we received a phone call late at night. A Bellows Air Motor on an important production line had gone haywire. Could we ship a replacement immediately? We did better than that. We had a Bellows Field Engineer at his plant at 8:00 the next morning. At 9:00 the line was back in operation.

More than 125 Bellows Field Engineers (one or more in every major industrial area in the United States and Canada) are your assurance that if you ever do have trouble with any Bellows equipment it will be remedied quickly with minimum down time. (But between us girls, trouble with Bellows "Controlled-Air-Power" Devices is most unusual!)

The Bellows Co.

AKRON 9, OHIO

MANUFACTURERS OF CONTROLLED-AIR-POWER DEVICES FOR FASTER, SAFER, BETTER AND **LOWER-COST** PRODUCTION

630-B



This machine assembles vacuum transfer tubes and gas inlet valves into carburetors. Fixtures hold any Ford unit



A special locating fixture is used in hand drilling 0.026-0.048 in. diameter gas metering holes in carburetor bodies

Ford Makes Own Carbs

Reject rate is expected to be less than 3 per cent when all production kinks are ironed out. Rawsonville, Mich., facility turns out carburetors for all Ford cars

QUALITY CONTROL is one of the reasons Ford Motor Co. set up a line at Rawsonville, Mich., to cast, machine, and assemble carburetors for all its cars.

Until last year, the company bought aluminum carburetor shells from suppliers. This year, it's making all but a few of the bodies.

Reject Problem—As one of the aluminum companies explains it, porosity leaks and cavities in castings often can't be spotted until they've been partly machined. Ford faced the perpetual problem of having to reject large inventories of rough castings if the defects were spotted during machining. The company decided to set up its own production facilities.

It began by starting a do-it-yourself program in temporary facilities, but it went back to venders for its 1957 carburetor bodies because of its own mounting reject troubles.

New Start—A permanent line was set up when the Rawsonville plant opened this September. Ford's preliminary reject rate on carburetors has been 7 per cent—less than half the rate in its previous model run.

Ford says it expects rejects to drop below 3 per cent as early production kinks are ironed out.

Room for Errors—The line turns out 4000 castings daily, which gives plenty of opportunity for errors. "That's why we want to do the whole job—so we can spot defects and correct them quickly," says Ford.

All through casting, machining, and assembly, carburetors undergo a series of rigid inspections and checks.

Many Parts — Ford casts five basic carburetor shells, using SAE 308 aluminum. The shells are built up into ten different carburetors. Ford reports the average four-barrel carb has 270 parts, the average two-barrel 220 parts.

Since the five basic bodies are similar in appearance, Ford has to mark each type shell with colored graphite lead as soon as it's out of the casting machine.

Five different dies are used for casting, but the company has developed an ingenious single die which can trim flashing from all the shells. A water test checks for porosity leaks before the flashing is removed.

Fit Tight—Close tolerances are required in machining and assembly. They call for automatic gaging on most machining operations.

The first 40 station, in line, drilling unit, for example, has a battery of automatic gages to spot rejects at the halfway mark. Any carburetor bodies that have been spoiled in the first 20 operations are automatically shunted out of the machine.

Locating holes are kept to 0.006 in. tolerances. Hard-to-reach vacuum passage holes are automatically drilled and reamed to 0.125 in. in diameter.

But Clean—Before being transferred to the belt assembly line, machined bodies are cleaned in a bubble bath, then cycled through a sealing solution. More pressure tests follow.

"During assembly, valves and seats on each carburetor are 100 per cent vacuum tested to make sure there are no leaks," Ford adds.

Some 27 subassemblies go into the average carburetor. They are built up in the center of the as-

(Material in this department is protected by copyright, and its use in any form without permission is prohibited.)

sembly area. Ford is rearranging the subunits so they will flow into the assembly line at point of use.

And Ready—Finished carburetors are conveyed to flow chambers where the volume of gas going through different passages is checked, and each unit is calibrated before being packaged and shipped.

Although Ford is just starting full carburetor production, its Rawsonville plant also makes instrument clusters, heater motors, distributor bases and shafts, and powdered metal parts. The facility covers 567,000 sq ft.

Car Registration Up

Some 56.1 million cars will be registered in the U. S. this year, compared with 54.3 million registrations last year, says the American Petroleum Institute, New York.

The API also looks for truck and bus registrations to hit 11.1 million, compared with 10.88 million in 1956. The institute says it means a 3.1 per cent increase in vehicle registrations. The estimates do not include cars, trucks, or buses operated by the military services.

By mid-November, car producers had built 5.3 million passenger cars and 966,688 trucks and coaches, reports the Automobile Manufacturers Association. The total (6.2 million vehicles) compares with 5.9 million built in the same period last year.

Detroit Tooling Gains

The reported 30 per cent increase in automotive tool and die work is substantiated by Chester A. Cahn, managing director, Automotive Tool & Die Manufacturers Association, Detroit.

"It looks like the 1959 automobiles will have fairly extensive changes, compared with 1958's," says Mr. Cahn. Because of two and three year model change cycles, he points out that 1958 tooling contracts should be compared with those in 1956.

Several Detroit area shops indicate their work load for the coming year is about equal to what it was in 1956—well above last year's.

Mr. Cahn says major boosts in tool and die employment have come since the first week in October. "While employment hasn't increased 30 per cent over 1957's, we expect peak work loads after the first of the year," he adds.

Another Importer Speaks

A west coast importer of Germany's Goliath car says he expects a U. S. market of 275,000 foreign cars in 1958. In contrast, others are anticipating import sales of half a million cars next year.

Robert H. Peterson, president of Goliath Importers, U.S.A., Burlingame, Calif., believes his car will account for approximately 30,000 units.

The economy Goliath has been marketed on the West Coast for more than a year. Mr. Peterson now plans to distribute it across the country. The line includes station wagons, a convertible, and two premium models.

Port of entry prices (Los Angeles) start at $1995 and go up to $2834 for a sports coupe. The car is powered by a front mounted, water cooled engine. The 4-cylinder plant is rated at 46 hp. Fuel consumption is supposed to be around 30 mpg.

Goliath's wheelbase is 89.4 in., with an over-all length of 13.3 f The car weighs 2020 lb. It closer to GM's Opel and Vauxha in price; it's between them and th Volkswagen in size.

U. S. Auto Output

Passenger Only	1957	1956
January	642,089	612,078
February ...	571,098	555,596
March	578,826	575,260
April	549,239	547,619
May	531,365	471,675
June	500,271	430,373
July	495,629	448,876
August	524,354	402,575
September ..	274,265	190,716
October	327,362	389,061
10 Mo. Total	4,994,498	4,623,829
November		581,803
December		597,226
Total		5,802,808

Week Ended	1957	1956
Oct. 19	72,180	88,557
Oct. 26	104,987	104,269
Nov. 2	126,139	117,583
Nov. 9	136,742	132,087
Nov. 16	141,902	135,641
Nov. 23	153,917†	118,949
Nov. 30	133,400*	159,976

Source: *Ward's Automotive Reports.* †Preliminary. *Estimated by STEEL.

GM Holds Wage Levels

General Motors Corp. reports it 390,000 hourly rated workers wi continue to receive a 19 cent cos of-living allowance through Fe ruary, 1958.

GM's allowances are based o the Consumer Price Index of th Bureau of Labor Statistics. Th last BLS index is 121.1, compare with 120.8 for July 15. The chang is insufficient for a wage boos Some 106,000 salaried employee will continue to receive a quarterl cost-of-living allowance of $95.

Exhaust Notes

• *Ward's Automotive Reports* say car and truck assembly plants fe 5 per cent behind anticipated N vember production schedules o 615,000 cars and 95,000 trucks.

• Ford Motor Co. reports its Co tinental Mark III has been sellin so well that its plant in Wixom Mich., will boost production 68 pe cent for December.

• Oldsmobile is scheduling 41,00 cars for December production.

• GM says it will build an aut finish testing laboratory in Miami Fla., to replace a small facility now used there. Earl M. DeNoom head of the Miami testing group says the move will permit mor operating space and provide bette atmospheric conditions for con trolled tests.

• A 10.5 per cent jump in powe brake installations and a 10 pe cent gain in power steering ove 1956 models is reported by GM's Buick Div., Flint, Mich. Edward T. Ragsdale, general manager says Buick equipped 61.9 per cen of its 1957 cars with power steer ing, 56.1 per cent with powe brakes.

• Central Foundry Div. of GM ha developed a stronger casting meta called 88M Armasteel. Because o its hardness (269 to 302 Brinell) it can be used without preliminary heat treating.



*Week ended Nov. 23.

Look for 'Adjustment' To Hit Its Low in '58

YOU'LL probably see another pause in the long, upward business trend next year. It'll be reminiscent of 1954 and 1949—but probably not so severe. One thing is certain: The economy is in the opening phase of a slight recession.

Production—The latest report on production by the Federal Reserve Board (see chart, Page 72) shows that when the index should have been gaining, it was losing ground from the summer's high of 145 (1947-49=100) in August to 142 in October. Between August, 1953, and the following March, the FRB index declined 9 per cent. To match that, the index would have to decline to 132 by next summer. Some economists believe it will average about 140, with a low of 135 during the summer. That would be slightly better than 1955 was.

STEEL's industrial production index (above) also indicates that the cutback started in September. Current trends point to a continuation of readings in the low 150s. During the 1954 recession, the index fell 13.5 per cent. A similar cut in 1958 would put the trend line down to 133 or 134 per cent of the 1947-49 average. It hasn't been that low since early in 1955, and it isn't likely to reach that level next year. An average of 145 would be more likely, and that would be only slightly below 1955 and 1956.

GNP—During 1954, gross national product dipped slightly to $361.2 billion. Since then it has gone up steadily to about $435 billion this year. If the over-all economy is to repeat the 1954 slump, GNP next year will be around $430 billion. That is the prediction of Sinclair Weeks, secretary of commerce. It is one of the lowest forecasts so far. Most people are predicting $435 billion to $445 billion, figuring on over-all volume about equal to this year's and allowing for 2 or 3 per cent inflation.

The main difference in GNP next year will be its composition. The

BAROMETERS OF BUSINESS

	LATEST PERIOD*	PRIOR WEEK	YEAR AGO
INDUSTRY			
Steel Ingot Production (1000 net tons)[2]	1,884[1]	1,945	2,489
Electric Power Distributed (million kw-hr)	11,950[1]	11,953	11,439
Bituminous Coal Output (1000 tons)	9,125[1]	9,400	10,327
Petroleum Production (daily avg—1000 bbl)	6,800[1]	6,831	7,195
Construction Volume (*ENR*—millions)	$332.3	$373.0	$357.6
Auto, Truck Output, U. S., Canada (*Ward's*)	186,188[1]	173,382	146,991
TRADE			
Freight Car Loadings (1000 cars)	645[1]	647	651
Business Failures (Dun & Bradstreet)	306	266	240
Currency in Circulation (millions)[3]	$31,336	$31,287	$31,269
Dept. Store Sales (changes from year ago)[3]	−5%	−1%	+6%
FINANCE			
Bank Clearings (Dun & Bradstreet, millions)	$24,575	$20,019	$25,277
Federal Gross Debt (billions)	$273.7	$273.7	$276.7
Bond Volume, NYSE (millions)	$26.6	$25.9	$23.5
Stocks Sales, NYSE (thousands of shares)	12,505	11,671	9,002
Loans and Investments (billions)[4]	$86.1	$86.3	$85.6
U. S. Govt. Obligations Held (billions)[4]	$24.8	$25.0	$25.6
PRICES			
STEEL's Finished Steel Price Index[5]	239.15	239.15	225.92
STEEL's Nonferrous Metal Price Index[6]	205.8	206.4	256.8
All Commodities[7]	117.8	117.8	115.7
Commodities Other Than Farm & Foods[7]	125.6	125.6	124.0

*Dates on request. [1]Preliminary. [2]Weekly capacities, net tons: 1957, 2,559,490; 1956, 2,461,893. [3]Federal Reserve Board. [4]Member banks, Federal Reserve System. [5]1935-1939=100. [6]1936-1939=100. [7]Bureau of Labor Statistics Index, 1947-1949=100.

FAST

PRODUCTION OF NEW PRODUCT *Fabrications* FOR QUICK DELIVERY OF

Spinformings

GUIDED MISSILES, TURBO JETS,

COMMERCIAL PLANES, PARTS,

Hydroformings



INDUSTRIAL PRODUCTS AND A



GROWING LIST OF NEW, UN-

Fabrications



PUBLISHED DEVELOPMENTS USE

THIS CREATIVE SHOP.

High speed facilities, unexcelled workmanship and consistent research keep this shop available to designer, engineer and purchasing agent working with advanced concepts. Send drawings for quotations and literature.

ROLAND TEINER

Company, Inc.

Dept. 48 — 134 Tremont Street
Everett 49, Massachusetts Tel. EV 7-7800

ENGINEERING REPRESENTATIVES IN MANY CITIES

THE BUSINESS TREND



(Seasonally Adjusted)

	Total Production		Primary Metals		Metal Fabricating	
	1957	1956	1957	1956	1957	1956
Jan.	146	143	144	148	180	170
Feb.	146	143	143	146	180	168
Mar.	145	141	137	145	179	167
Apr.	144	143	136	146	176	170
May	143	141	132	141	175	167
June	144	141	132	136	177	168
July	144	136	133	69	177	169
Aug.	145	143	136	125	177	172
Sept.	144	144	131	148	174	174
Oct.	142*	146	126*	147	170*	176
Nov.	...	146	...	147	...	180
Dec.	...	147	...	145	...	183
Avg	...	143	...	137	...	172

Federal Reserve Board. *Preliminary.



	Awards		(end of month)	
	1957	1956	1957	1956
Jan.	5,328	1,818	114,656	144,94
Feb.	6,065	1,675	111,965	141,43
Mar.	5,359	1,618	107,708	137,07
Apr.	6,429	6,559	105,190	137,43
May	3,423	2,403	97,006	133,67
June	4,918	2,859	91,810	129,40
July	1,251	2,642	85,229	126,19
Aug.	3,203	2,575	79,258	122,87
Sept.	3,257	3,949	71,981	122,42
Oct.	2,206	6,532	65,718	122,25
Nov.	....	4,172	.....	119,62
Dec.	....	4,992	.....	117,32
Total	....	41,794		

American Railway Car Institute.

Charts copyright, 1957, STEEL.

emphasis will be on soft goods, taking up the slack resulting from the slowdown in capital goods and consumer hard goods.

Metalworking Sales — The segment of the economy most likely to take the brunt of the decline next year is metalworking. The industry's sales this year will be about $140 billion, up from $133,538 million last year. But with capital goods expenditures on the downtrend, industrial building off, and a general softness in consumer durable goods, it would take a startling change of tide to increase sales in 1958.

Although the recession of 1953-54 and the current downturn got their starts in September, the two situations are not too similar. Backlogs were not as high in 1953-54 as they are now, but consumers had a backlog of desire to buy which was far from satisfied. Industry was just beginning an expansion program to meet those needs. All those things helped pull us out of the spin in 1954.

Today, even though the book value of backlogs is relatively high, there is an apparent lack of desire for hard goods on the part of the consumer. Cancellations are becoming more common. So far this year, they have amounted to over 10 per cent of new orders in the machine tool industry. Backlogs of freight cars are slipping far more than the shipments-new order ratio indicates they should. And for the first time since the end of World War II, there is more than enough industrial capacity to supply consumer demand.

Between Waves—Industry must realize that this is a trough between two tremendous waves of expansion, claims William P. Carlin, economist, Republic Steel Corp. He told a meeting of the National Industrial Conference Board in Milwaukee that business indicators "show clearly that this period we are entering is only a temporary breathing spell. . . . This means that it won't be too long before we will need more plant and equipment, and the capital goods industries will be booming again . . . this period ahead may be one of real opportunity to replace obsolete equipment at reasonable costs—opportunity to prepare for the future."

Purchasers See No Upturn

The November report of the National Association of Purchasing



	1957	1956	1955
Jan.	3,494.7	3,116.4	2,181.0
Feb.	3,337.9	3,124.8	2,184.5
Mar.	3,571.6	3,330.9	2,599.5
Apr.	3,462.6	3,166.2	2,579.5
May	3,311.4	3,350.7	2,644.4
June	2,912.1	3,094.5	2,645.1
July	2,767.5	2,737.4	2,180.0
Aug.	2,830.8	3,136.6	2,535.6
Sept.	2,708.8	2,858.6	2,666.8
Oct.	.....	3,442.3	2,897.2
Nov.	.....	3,205.7	2,935.7
Dec.	.....	2,931.2	2,891.1

Metal Treating Institute.



	All Commodities		Other Than Farm & Foods	
	1957	1956	1957	1956
Jan. ...	116.9	111.9	125.2	120.4
Feb. ...	117.0	112.4	125.5	120.6
Mar. ...	116.9	112.8	125.4	121.0
Apr. ...	117.2	113.6	125.4	121.6
May ...	117.1	114.4	125.2	121.7
June ...	117.4	114.2	125.2	121.5
July ...	118.2	114.0	125.7	121.4
Aug. ...	118.4	144.7	126.0	122.5
Sept. ..	118.0	115.5	126.0	123.1
Oct. ...	117.7	115.6	125.7	123.6
Nov. ...	....	115.9	....	124.2
Dec. ...	....	116.2	....	124.6

U. S. Bureau of Labor Statistics.

Agents points to anything but an upturn. Production and new orders have changed little from the October reports, and employment is continuing its downward slope. The agents say that all materials are in adequate supply. (It's the first time they've reported this situation since 1942.) The only bright spot in the report is the expectation that the present slowdown in inflation will continue into 1958.

Stampers Still Optimistic

There is still plenty of optimism. The Pressed Metal Institute says that 50 per cent of its reporting members expect shipments will be up an average of 15 per cent in the next three months. Another 34 per cent expect to hold to present levels, and another 10 per cent look for a downturn of about 10 per cent.

Says H. A. Daschner, managing director of the institute: "Since stampers are men of sound judgment and do not make wild guesses about their business, the fact that 84 per cent look for as good, or better, business is encouraging. . . . The companies are out beating the bushes, and it is paying off."

Trends Fore and Aft

• Machine tool net orders for October continued to decline, totaling only $27.85 million, reports the National Machine Tool Builders' Association. Shipments are holding at the $60 million level.

• Freight car builders delivered 8295 freight cars in October, but took orders for only 2206. Backlogs dropped from 71,981 on Oct. 1 to 65,718 on Nov. 1.

• Inflation has come to at least a temporary halt. Wholesale prices (see chart above) dipped in October to 117.7 (1947-49=100), while the consumer price index stood still at 121.1 per cent of the base period. This was the first time since August, 1956, that the cost of living failed to make a monthly advance.

• At the same time, weekly spendable earnings of factory production workers declined by about 85 cents from the September level. This lowered the average worker's purchasing power by more than 1 per cent.

• New orders for industrial furnaces dropped 59 per cent from the year-ago figure to $3,621,000 in October, reports the Industrial Heating Equipment Association Inc.

MONEL • NICKEL • COPPER • ALLOYS
THIN STRIP
no standard is too exacting



Temper requirements for the thin nickel strip (.002″) used in sensitive electronic tubes were too exacting to be checked by the usual methods. So Somers carefully hand checks several samples from each lot by the ultra-precise "bend test" illustrated above.

Since 1910 Somers Brass Company has specialized in producing thin strip: nickel and its alloys below .020″ and copper and its alloys below .012″ with the tensile properties, fatigue resistance, drawing properties and many other requirements which only the most exacting standards of production and quality control can meet.

Whatever your specifications may be, why not take advantage of Somers long experience? Write for field engineer or Confidential Data Blank for a complete survey of your problem at no cost or obligation.

FOR EXACTING STANDARDS ONLY
Somers
Somers Brass Company, Inc.
WATERBURY, CONN.

EACH BILLET...

A MILESTONE IN INDUCTION HEATING

● To you, these billets may be worth a few dollars. To us, they are priceless. They symbolize Magnethermic's specialized knowledge in one of the important applications of induction heating—the heating of large metal masses.

Each of these billets represents hundreds of hours of research, developing new concepts for efficient heating of copper, brass, aluminum, steel, titanium, and other metals by induction heating.

Research and over 70,000 KW's of Magnethermic installations give us the experience to design the proper induction heating equipment for hardening, brazing, heat treating, forging, extrusion.

Are you considering an induction heating application? We can give you an unbiased recommendation on the best frequency for your work, including material handling equipment tailored to your production line. Write Magnethermic for prompt, specialized attention.

Induction
Heating
Equipment
60 to 450,000
cycles

MAGNETHERMIC®
CORPORATION
3990 SIMON RD. • YOUNGSTOWN 7, OHIO



WILLIAM C. MILLER
National Precision sales mgr.

LINDSAY BLEAKLEY
E. Chicago Machine Tool post



WLADIMIR A. REICHEL
Norden-Ketay senior v. p.

ALAN R. EAKINS
Porter refractories post

William C. Miller was made sales manager, **National Precision Casting Corp.**, Paoli, Pa. He was a sales engineer with Beryllium Corp.

Lindsay Bleakley was named general manager, **East Chicago Machine Tool Corp.**, East Chicago, Ind. He joined the firm in 1950.

Quentin E. Charlesworth was appointed vice president-production, **Bristol Steel & Iron Works Inc.**, Bristol, Va. He was works manager.

Henry McConnell was made manager of **Sylvania Electric Products Inc.'s** wire plant in Warren, Pa. He was manufacturing superintendent of the plant. **Gerald L. Moran** was made general manager of the company's chemical and metallurgical division, Towanda, Pa. He was division chief engineer. **Calvin J. Sparrow** was named to the new post of manufacturing manager at Towanda.

H. Glynn Wood was made works manager; **Robert B. O'Brien**, general sales manager of the special products division of **Stromberg-Carlson**, division of General Dynamics Corp. at Rochester, N. Y. Former production manager, Mr. Wood now is in charge of engineering, purchasing, and production.

Lloyd C. Fitzgerald was made Chicago district sales manager, **U. S. Steel Supply Div.**, U. S. Steel Corp. He succeeds **Donnell W. Newman**, resigned.

Wladimir A. Reichel was appointed senior vice president, **Norden-Ketay Corp.**, Stamford, Conn. He was senior vice president for engineering at General Precision Equipment Corp.

Mervin T. Flock was named to the new post of production and procurement manager, **De Laval Steam Turbine Co.**, Trenton, N. J. **Richard P. Springle** was made purchasing agent.

Joseph S. Jonkey, former manager of product engineering at William R. Whittaker Co., joined **Consolidated Electrodynamics Corp.** as production manager of its Glendale, Calif., division.

Winston A. Shoenberger was promoted to assistant superintendent, finishing department, Campbell, Ohio, Works, **Youngstown Sheet & Tube Co.**

Richard Robertson, former sales manager, was made general manager, **Allan Herschell Co.**, North Tonawanda, N. Y.

Robert J. Beck was appointed assistant chief engineer, Jack Div., **Duff-Norton Co.**, Pittsburgh.

Allis-Chalmers Mfg. Co. appointed **W. F. Stowasser** and **W. A. Shockley** to new posts in its processing machinery department. Mr. Stowasser was named process development engineer and will also supervise operation of the Carrollville pilot plant. Mr. Shockley becomes supervisor of minerals processing machinery sales.

Alan R. Eakins was appointed general sales manager; **H. W. Gethin**, assistant general works manager, refractories division, **H. K. Porter Company Inc.**, Pittsburgh. Promoted from assistant sales manager, Mr. Eakins has been with General Refractories Co. since 1949, in various sales posts.

J. K. Ortega was named vice president and director of manufacturing at **Keystone Mfg. Co.**, Los Angeles.

Anthony Coorlim was appointed assistant sales manager of **Colson Corp.**, Elyria, Ohio. The sales department is now at the company's new Jonesboro, Ark., plant. Mr. Coorlim was assistant sales manager, Radiant Mfg. Co.

George W. Lambertson was promoted to a division sales manager of **Lunkenheimer Co.**, Cincinnati. Formerly Chicago branch manager, he is succeeded by **Jack W. Montgomery**, former sales representative at the Chicago office.

William A. Driscoll was named superintendent of **Republic Steel Corp.'s** cold strip tin mill at Niles, Ohio. He succeeds the late **George M. Kropp.**

Edwin N. Hower was appointed vice president, **Charles T. Brandt Inc.**, Baltimore. He was manager, engineering and construction sales, for Dravo Corp.

C. M. Blair was elected vice president-planning; **R. D. Glenn**, vice president - development, **Bakelite**

R. M. FRINK



E. C. WALTER

Wolverine Tube division directors

ROBERT M. POWELL

JAMES L. ROACH

Wyman-Gordon appointments

Co., division of Union Carbide Corp., New York.

Calumet & Hecla Inc.'s **Wolverine Tube Div.,** Detroit, established a separate new products division and an operations division. It named **R. M. Frink** to the new post of director, new products; **E. C. Walter,** director-operations.

Joseph D. Gavin was appointed manager of sheet and strip sales at the Chicago plant of **Joseph T. Ryerson & Son Inc.** He succeeds **Robert T. Stafford,** promoted to an executive post to be announced.

John W. Spoor was named vice president and director of sales for **Seaman-Andwall Corp.,** Milwaukee, a division of American-Marietta Co. He was formerly sales vice president, Power Products Corp. **Jack E. Davis** was elected vice president - operations; **Michael D'Amato,** vice president-engineering.

William S. Shira was appointed assistant chief engineer, **Smith Engineering Works,** Milwaukee.

George D. Nahm was made assistant purchasing agent, **Carpenter Steel Co.,** Reading, Pa. He was office manager in the purchasing department.

Frederick V. Branch was made project co-ordinator, industrial and plant engineering, at the Owego, N. Y., plant of **International Business Machines Corp.**

John J. Reardon was made industrial engineering supervisor, building products division, **American Welding & Mfg. Co.,** Warren, Ohio.

Robert M. Powell was elected executive vice president-sales; **James L. Roach,** general sales manager of **Wyman-Gordon Co.,** Detroit.

Charles Snyder was made sales promotion manager, **Stone Machinery Co. Inc.,** Manlius, N. Y. He was with Dewalt Machine Co.

John W. McCredie joined **Refractory Specialties Co.** as a sales representative at Pittsburgh. He was sales manager, refractories division, H. K. Porter Company Inc.

Orval J. Thomas was elected executive vice president of **Camedera Engineering Co.,** San Diego, Calif.

E. M. Offinger was appointed Detroit district manager, Electro Data Div., **Burroughs Corp.,** Detroit. He succeeds **James Ford,** now central regional manager for the division.

John P. Carr was named assistant central division manager, **Walworth Co.,** at Pittsburgh.

Lawrence M. Ferguson, sales manager, was elected vice president-sales, **Vulcan Containers Inc.,** Bellwood, Ill. He succeeds **Herbert B. Scharbach,** resigned. **Eugene W. Gehm** was made assistant sales manager.

Arnold Jensen was appointed manager-marketing for **General Electric Co.'s** conduit products department, Bridgeport, Conn. He succeeds the late **Raymond B. Elmendorf.**

Gordon A. Paul was appointed comptroller of **American Steel & Wire Div.,** Cleveland, U. S. Steel Corp., to succeed **Russell M[illegible] Braund,** now vice president-accounting for the corporation in Pittsburgh. **Stanley G. Harris** was made assistant comptroller at Cleveland.

W. W. Gould was made Chicago district manager, **Edison Storage Battery Div.,** McGraw-Edison Co. He transfers from Cleveland.

V. P. Masi, former manufacturing manager, Mound Road engine plant, **Chrysler Corp.,** was named plant manager, Joseph Campau engine plant, engine division, Detroit. **W. R. Gerber,** former general superintendent, pressed steel division, Dodge main plant, was appointed plant manager, Conant stamping plant, stamping division.

National Supply Co. appointed **Charles C. Brush** chief field engineer of its Spang-Chalfant Div., with headquarters in Dallas. He succeeds **Howard G. Texter,** retired. **Dane O. Egbert** was made San Francisco district manager for Spang-Howarduct Div.

Electro Metallurgical Co., division of Union Carbide Corp., assigned **Dr. Doyle Geiselman** to the metals research group, Metals Research Laboratories, Niagara Falls, N. Y., as a research metallurgist; **Arnold E. Hultquist** to the chemicals research group as an assistant research chemist.

Harold J. Goldman was made assistant sales manager for the southwest region by **Rolled Steel Corp.** He is at Houston.

Hugh Kane joined **William F. Horsch Co.,** Grosse Point, Mich.,

SOAKING PITS

of new and revolutionary design

Our current activity includes the construction of 17 batteries employing a unique method of firing, utilizing 100% blast furnace gas with excellent heating rates . . . plus 7 batteries which are one-way fired, with metallic recuperators supplying air to burners at very high temperatures and pressure. Your inquiries on modern Swindell-Dressler Soaking Pits are cordially invited.

Swindell-Dressler Corporation provides a complete engineering service for the steel industry in the design and construction of new plants, and modernization of existing facilities. Consultations arranged gladly on request.

SWINDELL-DRESSLER
CORPORATION
Engineers • Constructors • Manufacturers

PITTSBURGH 30, PENNSYLVANIA

RUSSELL A. SCHLEGEL
Daystrom-Weston gen. mgr.



LORING S. BROCK
U. S. Steel product mgr.



PAUL A. CHRISTENSON
Square D works manager



E. F. ECHOLDS
American Electronics eng.

GEORGE W. WOODSUM
IBM purchasing agent

E. F. MITCHELL
Vitrified Wheel v. p.

as district sales agent. He was with Bethlehem Steel Co.

E. F. Echolds was made chief engineer, electromechanical division, **American Electronics Inc.**, Los Angeles.

George W. Woodsum was made purchasing agent for **International Business Machines Corp.'s** manufacturing plant in Rochester, Minn. **Thomas H. Ferry** was made assistant purchasing agent in charge of contract procurement.

C. E. McCormick fills the new post of manager of engineering design at **Republic Rubber Div.**, Lee Rubber & Tire Corp., Youngstown. Formerly chief engineer, he is succeeded by **Edmund D. Jones.**

R. M. Middleton was made product sales manager of **Westinghouse Electric Corp.'s** standard control division at Beaver, Pa. He succeeds **W. G. Caputo,** named field sales manager for the lighting division in Cleveland.

E. F. Mitchell was appointed vice president and general manager, **Vitrified Wheel Co.**, Westfield, Mass.

Hugh Baumberger was appointed sales manager of **H. M. Keller Co. Inc.**, Burbank, Calif.

James A. Stewart was made manager, plant engineering department, aircraft engine division, **Ford Motor Co.**, at Chicago. He succeeds **E. M. Sirhal,** transferred within the company.

D. L. Bohon was transferred from regional sales manager for the West Coast to the home office sales department of **DeVilbiss Co.**, Toledo, Ohio. He is replaced at Los Angeles by **George W. Fulton.**

Walter Petillon was made assistant western district sales manager, Chicago, for **Buffalo Bolt Co.**, division of Buffalo-Eclipse Corp. **M. M. McCahill** was made sales representative for the Midwest, at Minneapolis.

Russell A. Schlegel was appointed general manager, **Daystrom-Weston Industrial Div.,** Daystrom Inc., at Poughkeepsie, N. Y. This newly formed division will be part of the Daystrom Controlonics Group. Mr. Schlegel was general sales manager of Weston Electrical Instrument Corp., a subsidiary.

Loring S. Brock was made manager of structural and plate products, **United States Steel Corp.,** Pittsburgh, to succeed **Fred H. Lucas,** retired. Mr. Brock was assistant manager.

Paul A. Christenson fills the new post of works manager, industrial controller division, **Square D Co.,** Milwaukee. He continues responsibilities of purchasing, production control, material control. In addition, he will plan and coordinate all manufacturing operations.

OBITUARIES...

David R. Burton, 47, sales manager, Detroit stamping division, **Eaton Mfg. Co.,** died Nov. 17.

David A. Coulter, a consultant, and formerly general sales manager for **Willard Storage Battery Co.,** Cleveland, died Nov. 20.

William E. Offenhammer, 69, vice president, **Niagara Blower Co.,** Buffalo, died Nov. 14.

Gerald Swope, 84, a former president, **General Electric Co.,** died Nov. 20 in New York.

Thomas J. Neilan, 70, president-chairman, **Reliance Steel & Aluminum Co.,** Los Angeles, died Nov. 17.

F. Hughes Moyer, 82, a former president of **Mackintosh-Hemphill Corp.,** died Nov. 19 in Sturgis, Mich.

Henry Kingsbury, 74, former chief engineer, **Hammond Machinery Builders Inc.,** Kalamazoo, Mich., died Oct. 18.

Herman J. Blaser, president and general manager, **Seneca Wire & Mfg. Co.,** Fostoria, Ohio, died Nov. 8.

Norbert G. Thompson, owner, **Thompson Machine Products Co.,** Toledo, Ohio, died Nov. 12.

Carpenter Gets Northeastern Steel

Electric furnace steel mill at Bridgeport, Conn., will be operated as a subsidiary under name of Carpenter Steel of New England Inc. Benefits to steel users cited

CARPENTER STEEL Co., Reading, Pa., officially assumed full ownership on Nov. 19 of the bankrupt Northeastern Steel Corp., Bridgeport, Conn. It will operate the property as a subsidiary under the name of Carpenter Steel of New England Inc.

An order was entered on Oct. 7 by the U. S. District Court in New Haven, Conn., confirming the purchase by Carpenter. The acquisition became final when time for filing an appeal ran out.

"We have been trying since 1940 to expand our capacity fast enough to meet the growing demand for our specialty steels," said Frank R. Palmer, Carpenter's president. "The acquisition of these additional steelmaking facilities will result in a combined annual production capacity of 170,600 ingot tons. This is approximately double our former capacity."

Benefits Users — Delivered cost of the kinds of steel to be produced in Bridgeport will be lower to users in New England and metropolitan New York than those brought in from outside the area, Mr. Palmer pointed out.

A Carpenter task force has reorganized Northeastern's supervisory and salaried personnel and has eliminated the salary cuts instituted by the reorganization trustees who operated the plant under the court's supervision. Hourly paid production employees who were furloughed by the trustees will be recalled as soon as a practical work load is reached.

As soon as production facilities are ready, Carpenter of New England will start making electric furnace quality alloy and stainless steels at the Bridgeport mill, which was rebuilt and modernized in 1955. The old open-hearth furnaces will be dismantled to allow space for future expansion.

The Bridgeport property was known as the American Tube & Stamping plant of the Stanley Works to December, 1954. As of Jan. 1, 1957, the plant had a rated capacity of 188,280 tons of basic open-hearth steel and 114,920 tons of electric furnace steel. Its capacity for rolling hot-rolled products included 166,400 tons of bars (other than concrete reinforcement) and 65,000 tons of blooms and billets for forging or for export. Annual capacities also included 70,000 tons of cold-finished bars and 3600 tons of wire.

Builds New Plating Dept.

A new plating department and waste treatment facilities are being constructed at the plant of Pitney-Bowes Inc., Stamford, Conn. They were designed by Graham, Savage & Associates Inc., Jenkintown, Pa., collaborating with the company's architects, Caproni Associates, New Haven, Conn.

Offers Ultrasonic Units

G. S. Blakeslee & Co., Chicago, builder of industrial washers and degreasing machines, has joined forces with Branson Ultrasonic Corp., Stamford, Conn., to design, sell, and service an advanced line of ultrasonic cleaning machines. Blakeslee is now incorporating Sonogen generators and transducers whenever ultrasonic equipment is required.

Roper Pump Div. Renamed

Roper Hydraulics Inc., Rockford, Ill., started operation Nov. 1 by taking over the pump business of Geo. D. Roper Corp., Pump Div. Officers are: President, John H. Makemson; vice president, Fred Dickerson; and secretary-treasurer, Charles Oehler.

Gulton Forms New Division

Gulton Industries Inc., Metuchen, N. J., established an Alkaline Battery Div. to produce nickel-cadmium and nickel-iron batteries and associated charging equipment. Simultaneously, the firm has

(*Please turn to Page* 85)



ANYTHING
IN
Perforated Metal

For **ANY** requirement in perforated-metal sheets, plates or parts, you'll do well to contact **DIAMOND.** Forty-three years of widely diversified experience and ample manufacturing facilities assure unsurpassed quality and delivery — at competitive prices.

Our 32-page catalog, No. 39, illustrates a complete line of round, square, oblong and ornamental patterns with unit openings from .020" to 9.50" in diameter. Specifies hole sizes, percentages of open area, gauge limits, etc.; shows many modern applications; gives all the information a designer needs to make a quick, accurate, selection.

Write today, for a free copy of Catalog 39 and tell us about any present or prospective requirement. Our experienced engineers welcome opportunities to make money-saving suggestions without charge or obligation.



DIAMOND MFG. CO.
WYOMING WILKES-BARRE AREA PA.
West Coast Plant,
DIAMOND PERFORATED METALS CO.
17915 So. Figueroa St., Gardena, California
Los Angeles Area

ALLIS-CHALMERS

roducts for steel: motors, m-g sets, rectifiers, ntrol, pumps, *Texrope* drive equipment, crushers, inding mills, screens, transformers, unit substations, itchgear, circuit breakers, turbine-generators, volt- e regulators, blowers, compressors, condensers, and ter conditioning equipment.

ALLIS

in Step with STEEL

The blooming mill

Maximum electrical efficiency is assured in blooming mill operations where Allis-Chalmers equipment is used. From switchgear to drive motors, Allis-Chalmers offers a tailored system — engineered by mill experts and designed to keep high quality blooms rolling fast and accurately.

From mine to final processing—Allis-Chalmers equipment is in step with the increasing tempo of expanding steel production. Contact the nearest A-C office in your district, or write Allis-Chalmers, Milwaukee 1, Wisconsin.



Blooming mill motor room view shows components of the Allis-Chalmers electrical package. Switchgear, control, constant and variable voltage motor-generator sets, *Regulex* motor-generator sets, liquid rheostat, and twin drive motors are designed to work together for peak mill output.

Regulex and *Texrope* are Allis-Chalmers trademarks.

CHALMERS

A-C ALLIS-CHALMERS

A-5411

PRODUCTION MACHINERY

GREENLEE

AUTOMATIC BAR MACHINES

HELP YOU BEAT RISING PRODUCTION COSTS

The cowman achieves speed and power in a good "using" horse by years of careful breeding . . . Greenlee develops these same qualities in its Bar Automatics by continuous research and design improvement. One of the many superiorities of this speed and power is that it enables you to take full advantage of modern tooling practices. Your Greenlee representative will be glad to show you how it is done. Please submit print when inquiring about a specific job.

Write for Catalog No. A-405



SIX AND FOUR-SPINDLE AUTOMATIC BAR MACHINES

GREENLEE Special Machine Tools

- Multiple-Spindle Drilling and Tapping Machines
- Transfer-Type Processing Machines
- Hydro-Borer Precision Boring Machines

GREENLEE
BROS. & CO.

1932 MASON AVE.
ROCKFORD, ILL.

(*Concluded from Page* 81)

been licensed to produce and market alkaline batteries in the U. S. under patent rights held by SAFT Corp. of America. Gulton has taken over the management and operation of SAFT's plant in Lodi, N. J.

Machine Tool Distributor

R. E. Duboc Associates has been organized as a machine tool representative and distributor. Headquarters and showroom have been established at 2353 S. Broadway, Denver 10, Colo. The firm will represent in Colorado, Wyoming, New Mexico, and Utah the following: Black & Webster Inc.; Brown & Sharpe Mfg. Co.; Clearing Machine Corp.; Denison Engineering Div., American Brake Shoe Co.; Detroit Broach & Machine Co.; Fosdick Machine Tool Co.; Govro-Nelson Co.; Induction Heating Corp.; R. K. Le Blond Machine Tool Co.; New Britain-Gridley Machine Div., Lucas Machine Div., and Hoern & Dilts Div., New Britain Machine Co.; Sciaky Bros. Inc.; and Vulcan Tool.

Expands Activities Abroad

Fluor Corp. Ltd., Los Angeles, established a wholly owned subsidiary, Fluor Engineering & Construction Co., in London, England. This move was made to take advantage of the rapid expansion of the petroleum and petrochemical industries in the sterling areas and Free Europe. Oil companies of the Free World are expected to invest $30 billion outside the U. S. in the next five years, says J. S. Fluor, president.

Massey-Harris Plans Shift

Massey - Harris - Ferguson Inc., Racine, Wis., plans to transfer all manufacturing operations of its tractor plant in Racine to Detroit. The firm is a subsidiary of Massey-Harris-Ferguson Ltd., Toronto, Ont. The Racine plant will be converted to a master replacement part warehouse for North American dealers and users of its farm machinery and tractors. Manufacturing operations in Racine will be terminated June 30. The firm's Detroit plant is undergoing a $4-



CRANE ASSEMBLIES

CHAIN HOISTS AND TROLLEYS

ELECTRIC HOISTS

Conco engineered Cranes rate top with **plant engineers** — for applica tion engineering that is outstanding for the service of trained field repre sentatives, for unmatched quality tha assures minimum maintenance, reduce accidents, increased output. Conco en gineers draw on over 37 years exper ence to design for the age of auto mation. Write for bulletin 5000A cov ering the complete line of Conc cranes, hoists and trolleys.

FROM ANY VIEWPOINT

A FINER CRANE

JIB CRANES

CRANES HOISTS CONCO
HAND GEARED CRANES


CONCO ENGINEERING WOR

Division of H. D. Conkey & Company 70-14th Ave., Mendota, Illinois

AFFILIATES: Conco Engineering Works–Domestic Heating Equipment • Conco Building Products Inc.,–Brick, Til



Parts are slotted faster at lower cost with continuous-cutting DoALL band machines. Note simplicity of fixturing shown in inset.

Shaping the Future with Tools...

Better means for moving people has become a multi-billion dollar problem for metropolitan leaders.

Easing of big city congestion involves everything from trains to traffic lights. Latest device under study to make the city more pleasing to the public is the "conveyor-belt sidewalk". Right now it's being used to channel pedestrian traffic more smoothly onto subway loading platforms.

In the picture above, industry's newest basic machine tool is cutting slots in parts for the moving sidewalk mechanisms. This DoALL band machine does the job in ⅔ the time required by the former method. The parts shown are slotted in 18 seconds, including load and unload time. Saving per year per machine is $7500, nearly 100% annual return on the machine investment.

The future is being shaped by tools like the new DoALL saw.

Conveyor-belt sidewalks, another convenience made possible by modern production tools.

Their ability to increase human productivity and reduce costs will make possible a growing abundance of goods and services to make living more comfortable for everyone.

Manufacturers seeking to give the public more for its money will find more than 1500 cost-cutting tools available through local DoALL stores—machine tools, cutting tools, gaging equipment, tool steel, black granite surface plates and supply items.

Reprints of this series on economics plus "economic kits" available for employee education.

ASK FOR CATALOG describing DoALL band machines for sawing, slicing, filing, grinding or polishing any material from aluminum to titanium, plastics to glass. Call DoALL locally, or write.

The DoALL Company
Des Plaines, Illinois
38 Local Sales-Service Stores E-29

million expansion which will double its size. When completed this month, its capacity will be 250 tractors a day.

Continental Changes Name

Continental Tooling Service Inc., Dayton, Ohio, changed its name to Continental Technical Service Inc. Much of the equipment designed by Continental is produced by the Con-Ray Corp., the firm's electronic and manufacturing division.

Organizes Research Firm

A group of engineers and scientists has organized Larkin Associates Inc., P. O. Box 296, Huntington Station, N. Y. The firm will offer research and development service to the aircraft, missile, plastic, and chemical industries.

Haverly To Move Plant

John Wood Co., Conshohocken, Pa., will move the manufacturing operation of its Haverly Equipment Div. from Syracuse, N. Y., to Royersford, Pa., on Jan. 1. The move will enable Haverly to more than triple production of refrigerated bulk milk coolers.

Dedicates Boron Refinery

United States Borax & Chemical Corp., Los Angeles. formally opened its $20-million open pit mine and refinery at Boron, Calif. It is expected U. S. production of boron will be increased by 30 per cent through the open pit mining method, which permits almost 100 per cent recovery of ore.

NEW PLANTS

Eutectic Welding Alloys Co. Inc. (Pacific division of Eutectic Welding Alloys Corp., Flushing, N. Y.), opened its new warehouse-service center at 5348 Jillson St., Los Angeles. R. C. Wilcox is in charge.

Barber & Ross Co. opened its new warehouse-store at 2323 Fourth St. N.E., Washington, D. C. In addition to stocks of building supply materials, the company maintains a Structural Steel Div.,

MBALLOY... A. M. BYERS ELECTRIC FURNACE QUALITY STEEL PRODUCT

YOU CALL...WE'LL COME WITH TECHNICAL HEL

You name the time, the place and the problem. A Byers metallurgist will be there with technical help. Often, as quick as a phone call.

Specialty steels—carbon, alloy and stainless—are areas of the metals business in which our experience could prove invaluable to you. We can work with you to determine which steels are best suited for your requirements. We've made detailed studies of strength, hardness and microstruc ture of metals. You'll find us adept in many of these skills

Or maybe you'd like to know something of the men wh make our steel? Our facilities? Our tests for quality? Ou packaging and loading? The Byers metallurgist has thes answers. Ask him to call, soon. A. M. Byers Company Clark Building, Pittsburgh 22, Pennsylvania.

A growth company with the emphasis on quality and service **A. M. BYERS COMPAN**

"2 KRANE KARs HANDLE ALL OUR MAINTENANCE, REPAIRS, and STORAGE," says CHARLES PRETSCH, Master Mechanic, SLATTERY CONTRACTING CO.

"The KRANE KARs Assemble and Disassemble equipment at Maspeth yards . . . buckets and shovels, tractor treads, graders, bulldozers, crane booms, backhoes, etc. Load and Unload trucks and trailers, recently loaded out 60 tons of wide flanged beams on one job alone. Stack and Store material in yard, and carry parts to shops, positioning them for repairs. We find KRANE KAR more economical for this type of work."

ALL-HYDRAULIC

SILENT HOIST KRANE KAR

SWING-BOOM MOBILE CRANE

1000 TO 25,000 LBS. CAPACITY

FLUID DRIVE POWER STEERING

ASK FOR BULLETIN NO. 79

Sold and serviced by Responsible, Well-Equipped Distributors throughout the World

SILENT HOIST & CRANE CO.

Pioneer Mfrs. of Heavy Duty Materials-Handling Equipment

849 63rd Street, Brooklyn 20, N. Y.

3,143 operating hours with only minor adjustments with this 400 amp.



WISCONSIN-POWERED WELDER

On-the-job service is what counts most in an engine. Here, for example, is a brief summary of a service report covering the performance of the Model VR4D 56 hp. Wisconsin Heavy-Duty AIR-COOLED Power Unit which drives the 400 Ampere Arc Welder illustrated above:

"Has operated exceedingly well . . . approximately 3143 operating hours . . . maintenance has been negligible after a few minor adjustments; appreciate fact that servicing is so simple; we are free of anti-freeze . . . no fooling with gadgets of water-cooled engines."

This is another typical case of outstanding service delivered by Wisconsin Heavy-Duty Air-Cooled Engines on many kinds of equipment. Basic load-holding High Torque, heavy-duty design and construction in all details, foolproof all-weather Air-Cooling and *exclusive specialization* in the design and manufacture of AIR-COOLED Engines are some of the factors that are responsible for Wisconsin Engine preference wherever dependable, economical power is required.

You can't do better than to specify "Wisconsin Power" for your equipment. Write for Wisconsin Engine Bulletin S-212.

WISCONSIN MOTOR CORPORATION

World's Largest Builders of Heavy-Duty Air-Cooled Engines

MILWAUKEE 46, WISCONSIN

A7-6149-⅓A

a Lumber-Millwork Div., and a Prefabricated Homes Div.

Carmody Corp. moved into its $150,000 plant at 2360 Wehrle Dr., Amherst, N. Y. The firm makes training devices for the armed services and industry.

Puerto Rican Can Co., subsidiary of American Can Co., New York, opened its 100,000 sq-ft plant at Bayamon, P. R. The $1-million plant is capable of turning out 150 million containers a year.

NEW ADDRESSES

Wolverine Tube, a division of Calumet & Hecla Inc., moved its administrative and sales offices to a new building at 17200 Southfield Rd., Allen Park, Mich. Plant personnel responsible for Detroit plant purchasing, engineering, production, and related plant operations will remain at the Detroit plant offices on Central Avenue.

Roy Bawden Ltd. moved to 150-154 Bentworth Ave., Toronto, Ont. The new plant more than doubles the company's capacity to produce pumps, converters, tanks, die sets, accessories, and special machinery.

ASSOCIATIONS

Loren Gillhouse, Quincy Compressor Co., Quincy, Ill., was elected president of the **Air Compressor Research Council,** Chicago. He succeeds D. R. B. Robson, Keystone Compressor Co., Philadelphia.

National Electrical Manufacturers Association, New York, elected W. V. O'Brien, Apparatus Sales Div., General Electric Co., Schenectady, N. Y., president. He succeeds A. A. Berard, Mt. Vernon, N. Y., president of Ward Leonard Electric Co.

British Iron & Steel Federation, London, England, appointed Lewis Chapman of William Jessop & Sons Ltd., president-elect to succeed the late Gerald Steel. Sir Andrew McCance, Colvilles Ltd., has been invited to continue as

resident of the federation next ear.

C. W. Diven Jr. was elected president of the **Steel Club of Philadelphia**, an organization made up of steel sales representatives working in the Greater Philadelphia area. Mr. Diven is district sales manager for Sharon Steel Corp., Sharon, Pa. Other officers are: Vice president, A. W. Taylor, Carpenter Steel Co., Reading, Pa.; and secretary-treasurer, C. W. Test, Youngstown Sheet & Tube Co., Youngstown.

CONSOLIDATIONS

P. R. Mallory & Co. Inc., Indianapolis, acquired plant facilities and majority interest of **Milliswitch Corp.**, Santa Monica, Calif., maker of electronic switches for missile and rocket parts.

Wisconsin Knife Works, Beloit, Wis., purchased **Bailey & Blendinger Co.**, Union, N. H., from Lodding Engineering Co., Worcester, Mass. The property will be operated as the B & B Knife Div. of Wisconsin Knife Works.

Johnson Bronze Co., New Castle, Pa., purchased **Apex Bronze Foundry Co.**, Oakland, Calif. The new subsidiary will make plain cylindrical, flanged, self - aligning bronze bearings, and miscellaneous bronze castings.

Wapakoneta Machine Co., Wapakoneta, Ohio, manufacturer of machine knives, purchased controlling interest in **California Grinding Works**, Oakland, Calif. Operating as a subsidiary, the west coast firm will specialize in machine knives, press brake dies, and all types of long, flat grinding.

Waukesha Co., Waukesha, Wis., purchased the **Climax Engine & Pump Mfg. Co.**, Clinton, Iowa, manufacturer of internal combustion engines. The Waukesha firm makes heavy duty, diesel, gas, and gasoline engines.

Transcontinental Industries Inc., Detroit, is purchasing **Highway Trailer Co.**, Edgerton, Wis.





Wayne takes the "Wiggle" out of Bus Bodies with Townsend Lockbolts

The world's foremost manufacturer of bus bodies—Wayne Works Division, Divco-Wayne Corporation—stresses strength, safety, and durability in construction.

Elimination of "rivet-wiggle" is one big reason why Wayne bus bodies are stronger. "Rivet-wiggle" and structural weakness occur when rivets fail to draw sheets completely together. Townsend lockbolts* have two qualities that enable Wayne to produce "wiggle-free" bus bodies.

First, these lockbolts produce absolutely uniform draw-down, or clinch, at each fastening because they are applied with an automatic gun that eliminates the element of human production-line error. Second, Townsend lockbolts, designed to lock with up to three tons of evenly distributed pressure, are far stronger than ordinary bolts, rivets, or spot welds.

In addition to uniform high clinch and vibration resistance, Townsend lockbolts offer ease and economy of installation. These are some of the reasons why Wayne has standardized on Townsend lockbolts for all structural fastening.

If you want these advantages in a fastener, a Townsend representative will be glad to demonstrate lockbolts right at your desk. For full information or a demonstration, write to Townsend Company, P. O. Box 237-C, New Brighton, Pa.

The Fastening Authority

Townsend

COMPANY • ESTABLISHED 1816

NEW BRIGHTON, PENNSYLVANIA

Sales Offices in Principal Cities

Cherry Rivet Division • Santa Ana, California

*Licensed under Huck patents RE22,792; 2,114,493; 2,525,307; 2,531,048; 2,531,049; and 2,754,703.

compact . . . power packed

New General Electric

GREATER



AUTOMATED TESTING FACILITIES check Tri-Clad '55' motors to assure conformance with high G-E manufacturing standards.

Technical Outlook

SHOP-SIZED NUMERICAL CONTROL—Electronic machine control is within the reach of the small shop. A numerical control system introduced by Electronic Control Systems Inc., Los Angeles, can be adapted to automatic positioning in drilling, spotwelding, riveting, tapping, countersinking, and template plotting. Called the Digimatic Model C-202 Point Positioner, the system includes a punched tape preparation unit, a tape reader and control unit, and a compound servopositioning table.

NEW STAINLESS USE—Sonotone Corp., Elmsford, N. Y., will use over 30 tons of Republic's Type 302 sheets this year in corrosion resistant cases for jet aircraft storage batteries.

EDGE MEASURE—A British gage measures infrared radiation from the edges of hot strip to calculate its width while passing through the mill. Accuracy is plus or minus 1/16 in.; delay time for readout is 0.15 second.

HEATS WITH LIQUID GLASS—A new furnace, designed to heat ingots for extrusion, uses liquid glass in a revolving chamber as the heating medium. Marketed by the Bal-Tate Furnace Co., Detroit, the unit was developed in Italy.

BREAKING TRADITION—A survival rifle weighing only 38 ounces has an aluminum alloy barrel with stainless steel liner. It also has an aluminum and stainless action. Armalite Div. of Fairchild Engine & Airplane Corp., Hagerstown, Md., developed it. Another tradition breaker: A chassisless bus with monocoque aluminum body, developed by Henschel und Sohne of Kassel, Germany.

COLUMBIUM ALLOYS—Du Pont's Pigments Dept. has developed a system of columbium alloys and has started a joint program with Thompson Products Inc., Cleveland, to develop fabricating techniques to use the metal in jet engines, missiles, and atomic reactor parts. Du Pont metallurgists say that if columbium is kept reasonably free of gases (nitrogen, hydrogen, or oxygen) its workability is good.

MOLYBDENUM COATINGS—A process for coating metals such as stainless, Inconel, and Croloy with molybdenum has these basic steps: 1. Preparing a dispersion of finely divided moly in a nonaqueous solvent, such as isopropanol. 2. Electrophoretic depositing on the base which is made an electrode in the dispersion. 3. Densifying to achieve close packing of the metal particles. 4. Sintering in a reducing atmosphere to coalesce the particles into a coherent film. The process, developed by Vitro Corp. of America, New York, also offers a new approach in applying lubricating films, corrosion resistant and special ceramic coatings.

IMPROVED ALUMINUM CONDUCTORS—Reynolds Metals Co., Louisville, is silver plating aluminum bus conductors to simplify soldered, brazed, and bolted connections. A new manufacturing process allows the company to sell the conductors for less than equivalent copper bus.

AUTOMATES RESISTANCE WELDER—Newest contribution to Detroit automation is a flash welder which joins worm gears to steering shafts. Built by Federal Machine & Welder Co., Warren, Ohio, it automatically marks the correct shaft and radial positioner for the worm.

TRANSPARENT VCI FILM—A new transparent film, treated with volatile corrosion inhibitor, heat seals at 200° F. Called MY-V-1 (it's based on Mylar), the packaging material offers greater product sales appeal and allows ready examination. Daubert Chemical Co., Chicago, says the film can be used to protect iron, steel, and aluminum products, and provides rust prevention for several years.

Metalworking Outlook—Page 47

Market Outlook—Page 135

How a Short Run Die Is Made

It Costs . . .

Material	**$ 64**
Labor (63 hr)	**$416**
Total	**$480**



1. Scribe to template.

Short Run Dies Offer Long Life

They add a new dimension to the thinking of shopmen under pressure to use shortcuts. The information in this article will give you an idea of how they fit into your operation

THE TYPE of die illustrated is being used as a double edged competitive weapon by alert stampers. It combines long tool life and tool economy.

The cost of the example is less than one-fourth that of a permanent tool. (It's made by Scottish Tool, Die & Metal Products Co., Cleveland.) With resharpening, it will produce several hundred thousand blanks made from 0.001 to 0.187 in. mild steel.

Problem—Die designers and shop foremen are under constant pressure from management to make use of more shortcuts like the steel rule die (STEEL, July 22, p. 100). Makers of short run dies have come up with many improvements. A few of their dies are the equivalent of a permanent tool on some jobs.

Formula — Johan M. Andersen, Duplicon Co. Inc., Westboro, Mass., heads one of the thirty-odd firms which specialize in short run dies. A member of the Small Lot Stamping Institute (write HPL Mfg. Co., 15210 Miles Ave., Cleveland, Ohio), he uses a rule of thumb to choose between the standard short run and the steel rule types:

- Standard short run tooling is more economical: 1. When the blank is smaller than 12 in. square and 0.005 to 0.375 in. thick. 2. When tolerances are less than 0.015 in.
- Steel rule dies are more economical: 1. When the blank is larger than 12 in. square (the larger it is, the greater the advantage). 2. When material thickness is less than 0.125 in. (That figure will probably be increased, says Mr. Andersen.) 3. When tolerances are not tighter than 0.030 in.

"In general, the steel rule die is another tool in the short run diemakers' bag of tricks. It shouldn't replace standard types any more than ceramic cutting tools should obsolete carbides," thinks Mr. Andersen.

Another Avenue—The tool shown in the illustrations at the beginning of this article demonstrates another approach to longer die life. The Scottish Company feels that such dies are the equal of permanent tools on many blanking and piercing jobs. Some have already run more than a million pieces.

The material is a 4130 or 4140 steel plate. Holes are drilled to



2. Drill and cut out on bandsaw.

3. Mill and finish file to size.



4. Flame harden cutting edges to Rc 55.



5. Broach female with punch; finish to size.

within plus or minus 0.005 in.; blank dimensions are held within plus or minus 0.010 in. Cutting edges are flame hardened to Rockwell 53-55.

After the punch plate is scribed, clearance holes are drilled and the shape cut with a bandsaw. The shape is finished by milling and hand filing.

The female die is laid out, clearance holes are drilled and the shape bandsawed.

Shortcut — The punch is flame hardened and matched with the female. Both are placed in a hydraulic press. It forces the punch through the female, broaching it to size. The female is then milled



6. Here's the assembled die with strippers and guides.



Here are the basic parts of Dayton Rogers' blanking die. Punch is stationary. Ram contacts female forcing it against punch. Strippers are operated by pneumatic die cushion



Dayton Rogers hole punchers operate from the bottom up. Magnetism holds template and part (top). Ram moves female die up. Punches come in sizes up to 1.5 in.

and smoothed by hand filing.

Following flame hardening of the female, the die is ready for assembly. Clearances are checked, and guides are drilled and reamed. Stripper plate and springs are attached, and the die is checked in a tryout press.

Mounting holes in all dies are drilled to fit a preset pattern. Dies are interchangeable on a standard die set. The same pattern can be drilled in upper and lower bolsters and the die used without shoes.

Added Feature—Leo Ward, president of Scottish, developed a flame hardening torch for his shop. It's a standard oxyacetylene torch with a built-in water spray and guard. The torch heats the cutting edge of the die. As it moves along, the spray (separated from the hot tip by the guard) quenches the heated section, imparting exceptional hardness (Rc 55) to the metal.

The exceptionally tough, shock resistant alloys increase die life.

Another Avenue—Here's a die method based on the idea that the fastest way isn't always the cheapest. It was recently introduced by Dayton Rogers Mfg. Co., Minneapolis.

Parts are blanked first. Holes are punched one at a time on separate punch presses. Die costs are said to be less than 20 per cent of those for conventional dies. The method is ideal when only a few thousand pieces a year are required.

Blanking—The company recommends an open bed inclinable press for its blanking die, which consists of a punch holder and sub-bolster. A pneumatic die cushion is used for stripper pins and blank ejector.

The female die is held loosely over the stationary punch in a die stop which replaces the upper bolster in conventional dies. The die stop and sub-bolster are tied together.

Strip stock is fed through the blanking die against an adjustable stop. When the press is tripped the ram block forces the female against the strip and punch. On the upstroke, the pneumatic stripper forces the stripping plate against the strip, removing it from the punch. A longer stripper in the center holds the completed blank against the ram until it clears the female.

Cycling—A full universal material stop picks up the blanked position in the scrap strip. The press then cycles for another blank. Maximum speed is 100 to 250 parts a minute.

Piercing—Holes are pierced one at a time. Small presses can be arranged in a semicircle around the operator.

Dayton Rogers presses hold interchangeable round punches and dies which progress from the smallest size to 1.5 in. in steps of 0.0005 in.

A piece of scrap fastened to the upper part of the press serves to locate the blank correctly for piercing. Tripping the work cycle magnetizes a stripping plate. The combination of magnetism and a mechanical stripper pulls the blank off the piercing punch. The magnet also holds both piercing fixture and part during the work cycle.

The press is automatic. As the work reaches the correct position, the trip operates. Prevention against double cycling is built into the electrical system.

Summation — H. A. Daschner, managing director, Pressed Metal Institute, Cleveland, echoes the sentiments of small lot diemen: "Such dies are adequate for more jobs than formerly thought possible. Frequently, the cost of several is less than that of one permanent tool."

You can choose from an increasingly wide variety: Plug, sandwich, mugget, put and take, steel rule, and the types described in this article. Some manufacturers (like Dayton Rogers) offer presses designed only for short runs.

• *An extra copy of this article is available until supply is exhausted. Write Editorial Service,* STEEL, *Penton Bldg., Cleveland 13, Ohio.*



Operator loads tray of parts. Controlled atmosphere furnaces are placed at each side of martempering bath (foreground). Monorail connects furnaces with quenching bath

Modified Martemp Cuts Warping

The system also permits a better structure stabilization during deepfreezing, reduces stock allowance for grinding, and cuts rejects to 1 per cent, says maker of aircraft pumps

By EDGAR C. WALLACE,
Chief Metallurgist
and HOWARD E. CROUSE,
Supervisor
Watertown Div.,
New York Air Brake Co.,
Watertown, N. Y.

MODIFIED martempering is a good way to heat treat intricate and expensive parts.

Its advantages over conventional methods: It costs less to operate, reduces grinding costs, lowers rejects due to grinding cracks, and improves tolerances on finished parts.

Example—The Watertown, N. Y., division of New York Air Brake Co. produces air brake equipment and aircraft hydraulic pumps. It previously heat treated pump cylinder blocks in salt or in atmosphere furnaces with a conventional oil quench.

Pump blocks are normally made from 52100 steel, oil hardening tool steel, or one of several stainless grades.

The blocks are 2 to 5½ in. in diameter (some experimental models are larger). Each contains 30 to 100 drilled holes. Hole sizes are 1/32 to 1 in. They often have a center boring 4 in. in diameter.

Problems—Warpage was excessive. Grinding cracks caused a high percentage of rejections. After grinding to a millionth of an inch, final size was not stable.

Switching to controlled atmosphere furnaces and martempering at 260 to 275° F, eliminated most of the difficulties.

Equipment—The setup uses a martempering bath; two horizontal, controlled atmosphere furnaces



Equipment takes floor area of less than 9 by 18 ft. Layout permits one man to heat treat 400 lb an hour. Carbon potential is easily adjusted at generator

with alloy muffles; an RX gas generator; an Autocarb signaling controller; and an Autocarb dew point recorder. The equipment was installed by Surface Combustion Corp., Toledo, Ohio.

Floor Space—Heating furnaces have 18 by 30 in. nickel-chromium alloy muffles, placed behind and at either side of the martempering bath (see illustration at left). They are heated with over-and-under multiple burners that are piloted. A small monorail, leading to each furnace door, passes over the center of the martempering bath.

The bath is 30 in. deep, 36 in. wide, and 40 in. long. It is heated by two suction immersion burners. They can also cool to prevent overheating of the bath. A variable speed agitator circulates the oil.

Procedure—Parts are tray loaded and put in the furnace. Heating time varies with cross section and load—it averages 1¼ hours.

After heating, the operator opens the door and puts the tray on a table above the bath. The table is on an air piston controlled by a foot pedal. Parts are lowered rapidly into the marquenching oil.

The parts reach bath temperature in about 5 minutes and are removed in 10. Short immersion prevents excessive stabilization of retained austenite.

Stabilizing — After cooling to room temperature, parts get a series of tempering and deepfreeze treatments to complete austenite transformation.

As-hardened, parts are 64 to 65 Rockwell C. Work is usually tempered to below the as-quenched hardness. New York Air Brake feels that freezing is good insurance for maintaining tolerances which prolong service life. (Pumps often work at 4500 psi. Tolerances are held to a millionth of an inch.)

Atmosphere—Treated parts cost $25 to $500. Spoilage from surface changes is expensive.

An 800 cfh, RX generator is used to manufacture protective atmospheres. A signaling carbon controller controls the dew point, and a two-point recorder charts the dew points of the two furnaces. Dew points of 30° F and up are used.

Natural gas is added to raise carbon potential since the company prefers a slight carburization for small parts.

Flexibility—A valve system in the atmosphere generating equipment improves control. RX generator gas is piped directly to the furnaces, and passes to the two-point recording instrument.

During quenching, the gas from the furnaces doesn't go through the recording equipment. (The operation is automatic.) During the loading and subsequent purging, time clocks control valves automatically. Purging of the furnace is completed before atmosphere again enters the recording equipment.

Atmosphere can be varied in each furnace. Each is manifolded and controlled from the same generator.

Summing Up—New York Air Brake finds that the system greatly increases oil life. Grinding stock has been reduced due to better warpage control. Rejects have been cut from 6 per cent to less than 1 per cent. Cleaning problems also have been eliminated, improving housekeeping.



Operator steps on pedal which controls air lift for trays. In burner exhaust stacks, blowers provide a venturi action which aids combustion and provides cooling when needed



This cogging mill will be used in large scale production of superalloy and high speed steels. It uses diamond grooved rolls

New Mill Will Roll Tough Steels

Latrobe has $3-million mill to roll superalloys and high speed steels. "It'll solve crucial problems in coming missile era," predicts J. E. Workman, executive vice president

A 32-IN. COGGING mill has replaced hammer and press forging for superalloys and high speed steels at Latrobe Steel Co., Latrobe, Pa.

A common blooming mill can't roll these alloys without damage to their metallurgical structure, expains Dr. S. G. Fletcher, Latrobe's vice president-metallurgy.

"The most important departure from tradition which makes it possible for our mill to handle these tough ingots is the use of diamond grooved rolls instead of the usual box or flat rolls of the conventional blooming mill," he added.

Difference—This type of rolling action tends to distribute the hot deformation more uniformly, particularly in the center of the ingot. It gives the kneading required to compact and refine the internal porous cast structure.

Standard box passes on conventional mills will often rupture the centers because of unrestricted lateral flow. On soft steels, lateral flow is not harmful because they have the ductility to absorb the action. Harder alloys tend to break up internally.

Latrobe says that kneading action produced by its type of rolling has beneficial effects on the internal structure—in many cases, the technique is superior to hammering or pressing.

Alloys Vary—Some tough steels are easier to handle than others. Heavy reductions at low speeds are best for some, while others require light reductions at relatively high speed. (Reductions are 2 to 8 per cent per pass—a great deal lower than what is possible with carbon steels.) To take care of this, a great deal of versatility was designed into the mill. Variations in speed of rolling and rate of reduction can be accurately controlled at the pulpit.

The mill can handle ingots as large as 18 in. square that weigh 4000 lb. It will turn out billets as small as 3 in. square, or slabs up to 12 in. wide. One product, termed sheet-bars, consists of slabs 8 to 10 in. wide, about 1½ in. thick. They are used as starting stock for rolling superalloy sheets.

Six men operate the mill. Rolling is controlled from an air con-

ditioned pulpit. The installation can roll 100 to 150 tons of tough alloys in an 8-hour shift.

Products — A number of steels and superalloys have already been rolled on the mill. It has handled ingots of the common high speed tool steels, such as 18-4-1, M-2, M-3, T-15, including their sulfurized modifications. High carbon, high chromium die steels, some with as much as 2.5 per cent carbon have been rolled. The mill has processed vacuum melted, nickel base superalloys, such as Waspaloy, M-252 and Udimet 500, for jet engines and missiles.

Latrobe is operating a vacuum, consumable electrode furnace and is processing a wide variety of alloys supplied by companies operating induction vacuum furnaces.

Studies on rolling tool steels started almost ten years ago as part of a planned program "to find a better way of handling high speed steels and superalloys," as company officials put it.

Future—The mill brightens prospects for a much broader product line, especially for materials with structural applications in missiles and aircraft. Mr. Workman predicts: "Five years from now, 50 per cent of our business may be in materials we aren't even making now."



The diamond groove rolls (top) give more uniform deformation (especially in center of the ingot), contrasted with pressure from conventional flat rolls, illustrated in bottom drawing

Lockheed Tries the Unusual

Five still-uncommon production techniques are used to build supersonic F-104A Starfighter. They help cut assembly time to that of a trainer that's been in production eight years

STRIVING FOR producibility, engineers at Lockheed Aircraft Corp., Burbank, Calif., designed their sleek F-104A to take advantage of several unusual, but profitable, production techniques.

Five stand out: Compression forming, zero-draft forgings, chemical milling, steel extrusions, and extruded, integrally stiffened aluminum panels.

Here is a Lockheed report on what's being done with these methods.

Compression Forming — Developed by Lockheed engineers, it achieves tolerances unusual in sheet metal parts.

The part first is formed to broad tolerances on a Hydropress. Next it's heat treated and placed in the cavity of a compression die. A high-pressure ram compresses both the surface and edges of the part—forcing metal to flow against the face of the die.

Finished by this method, the sheet metal part is three times as precise as those produced by standard forming. In addition, much sharper flange radiuses can be produced in a channel section. This enables flange rivets to be placed closer to the web of the channel, reducing the thickness required in the web to carry a given load.

Where loads are light, wing spars and ribs in the F-104A are being made from sheet metal, using the compression forming method. Forgings are used in heavy load carrying areas.

Zero-Draft Forgings — Until recently, forgings were made with a taper in the ribs so the forging could be withdrawn from the die cavity. In most forgings, this taper had to be machined off to permit attachment to other parts or, simply, to remove the unneeded material.

Using higher forging pressures and precision dies, forgings are being made to close tolerances with thin, untapered ribs. This eliminates most of the previously required machining operations and is about 20 per cent less costly than a conventional machined forging.

The F-104A uses about 40 zero-draft forgings.

Chemical Milling—Recently the aircraft industry has been removing unneeded material by immersing aluminum sheets and plates in a caustic soda solution. By masking certain areas to prevent etching, lands or plateaus of varying heights can be produced. This process, similar to that used in making photographic plates for printing, cuts machining costs considerably.

The F-104A engine air intake ducts are exclusively chemical milled.

Steel Extrusions—Prior to this development, complex steel shapes had to be machined from solid bars. The F-104A uses approximately a dozen steel extrusions in such applications as piano-type hinges for attaching ailerons to the wing.

Extruded Aluminum Panels—To produce lighter, more efficient and smoother surfaces for engine air intake ducts on the F-104A, Lockheed uses extruded, integrally stiffened aluminum panels this way: The extrusion, in tubular form, is slit lengthwise and unwrapped into a flat sheet. This sheet is then contoured into desired shape through the stretch-forming process.

Master Key...

TO POWER'S LOW COST FUTURE

BITUMINOUS COALS
FOR EVERY PURPOSE

• Bituminous coal contributes to plant operating profits by its *productivity* and *stability*. Virtually limitless supply, plus most modern mining methods, gears production to *any volume demand*.

Accessibility and increasingly efficient burning equipment mean economical, constant-cost for today and tomorrow.

B&O

Ask our man! BALTIMORE & OHIO RAILROAD, BALTIMORE 1, MD., Phone: LExington 9-0400



Vacuum crane in foreground has just lifted a sheet from pile. Crane will traverse to next roller conveyor which is entry end of Sendzimir. Crane in background picks them up on exit side

Vacuum Crane Speeds Mill Output

Manual sheet handling took longer, produced too many rejects. This automatic device lifts stainless sheets vertically to avoid scratches. Operator controls cycling time

FEEDING a Sendzimir finishing mill is made easier with vacuum handling equipment, says Atlas Steels Ltd., Welland, Ont.

A new vacuum crane automatically handles the firm's stainless sheets, replacing a manual operation. Output has been increased through the elimination of downtime for rest periods. Quality is better. (There are no scratches caused by dragging one sheet over another.)

Operation—The mill finishes austenitic stainless sheets. Sizes are 25 by 72 in. to 50 by 156 in., gages 0.020 in. to 0.188 in.

Sheets come directly from the hot mill after annealing and pickling. Partly finished sheets used to be stacked by crane near the entry end of the mill. They were lifted by hand to the feed end and from a conveyor at the exit end.

The mill is nonreversing, so piles at the exit were returned to the feed end by overhead crane. Sheets sometimes were handled 14 times during finish rolling.

On the feed end, some always got dragged over the sheet next in the pack. Even slight scratches, when rolled into a sheet, result in



Here is close-up of exit crane. Note that cups automatically adjust to waviness in sheet. Crane stacks on either side. Conveyor on right returns pile for another pass

flaws which don't show up until the metal is polished.

Replacement — Two vacuum cranes, made by Production Machinery Corp., Mentor, Ohio, eliminate the hand operations. (Vacuum is used because austenitic stainless is nonmagnetic.) One positions sheets on the feed table. The mill operator controls the cycle.

After the sheet is rolled, it is automatically picked up by the exit crane, stacked on either side, or returned for another pass.

The exit crane works automatically. It is actuated by sheets when they reach the end of the conveyor. The entry crane automatically picks up a sheet and holds it until the operator pushes a button.

No Scratches—The crane touches the sheets with rubber cups. It lifts and lowers the sheets vertically to prevent scratching. Quality is improved, and the number of rejects is sharply reduced.

Cranes are designed for rapid handling of a wide range of sizes and gages. Hydraulic drive permits quick traverses. It operates at 6 fps during most of the travel, decelerating to ¼ fps before stopping.

Source of Power—Vacuum for lifting comes from a pump mounted on the crane. It eliminates dragging hoses from the support. A trolley duct provides electric power.

Cups are mounted on a universal joint, allowing a 35-degree tilt. Six are used. They function satisfactorily even when there is a 12 in. variation in the level of the sheet. (Hot-rolled sheets, stacked one on another, have a wavy surface.) One cup will lift the sheet even if the other five aren't engaged.

Practice—Atlas rolls sheets of varying length in one pack. When short sheets leave one or more cups open, the operator lets them run through without bothering to cut out the extra cups. Each will lift about 300 lb. Sheets are laid down before the vacuum is cut to avoid dropping.

A pushbutton controls the depiler crane at the entry side. The other end is controlled from a panel on that side of the mill. The operator can start, stop, or repeat any operation. Normally, cycling is automatic, and the de-piler at the entry end goes through these steps:

1. Solenoid valve starts hydraulic traverse mechanism.
2. Crane accelerates to 6 fps.
3. Crane decelerates to ¼ fps and stops.
4. Air cylinders lower sheet to entry conveyor.
5. Sheet is deposited.
6. Air cylinders raise cups.
7. Crane returns to initial position.
8. Air cylinders lower cups, which touch top sheet on pack.
9. After a time delay, cylinders raise cups and sheet. Sheet is held until cycle button is pressed.

ALCOA'S NEW COLOR MOVIE



2011-T3

Here's the "Lightweight Champion of the Machining World." Watch this free-machining aluminum alloy perform amazing feats of economy and versatility through a blizzard of fine, crisp chips. It's just the ticket for most screw machine products.

6061-T6

The fabulous alloy that's unequaled where service calls fo exceptional resistance to corrosion, suitability for weldin or brazing. It's the most finishable of the aluminum scre machine stock alloys.

FREE SHOWING

Be sure to see these amazing alloys perform thei spectacular feats of strength, economy, machin ability, finishability and corrosion resistance. De termine a date for a showing to your group an contact your nearest Alcoa sales office. They' confirm a show date for you and send the film t reach you in time for your meeting. No charge Aluminum Company of America, 874-M Alco Building, Pittsburgh 19, Pennsylvania.

"THE FOUR AMAZING ALLOYS"
DEMONSTRATES THE VERSATILITY OF
ALCOA ALUMINUM SCREW MACHINE STOCK



024-T4

he daring "Aircraft Alloy." Noted for its strength. Tops here tight, vibration-, strain- and wear-proof assemblies e a must.

2017-T4

The startling alloy that's priced lowest of the aluminum screw machine stock alloys. Handles tough service jobs with a high degree of machinability.

Your Guide the Best in uminum Value

ALCOA ALUMINUM
SCREW MACHINE STOCK
ALUMINUM COMPANY OF AMERICA

NEW! "ALCOA THEATRE"
EXCITING ADVENTURE
ALTERNATE MONDAY EVENINGS

Learn why leading companies have switched to Alcoa Aluminum Screw Machine Stock

ALUMINUM COMPANY OF AMERICA
874-M ALCOA BUILDING, PITTSBURGH 19, PENNSYLVANIA

Please send booklet with direct quotes from industry leaders on why they buy from Alcoa.

NAME..... TITLE .....

COMPANY.....

ADDRESS..... CITY..... STATE .....



Plating line (top) readies two racks every 72 seconds. Transfer (center) removes them and places two others on plating conveyor. Monorail (below) is on lower level

Loader Speeds Plating Line

Automatic handling of plating racks permits joining service monorail and plating line. Firm says one machine does work of five men, cuts manpower, and improves quality

AUTOMOBILE bumpers and grille guards are being plated at twice the former rate by Eaton Mfg. Co.'s Cleveland Stamping Div.

The reason: A conveyor which features an automatic transfer device. It eliminates manual lifting of heavy plating racks, and combines chrome and nickel plating lines, which were separated.

Ralph Everstine, chief electrochemist, says that the installation has cut manpower and turns out better parts.

Preparation — Before plating, parts are polished and buffed to eliminate die and welding marks. Parts are 10 to 34 in. long, and weigh ½ to 8 lb.

The plating conveyor uses a double file system. Either lane can be operated independently. (It permits closing down one for servicing solution tanks.) Each can also be operated at a different current density, permitting segregation of shapes for improved deposition.

Two Lines—The electroplating conveyor handles 50 carrier loads of parts every hour. Parallel to it is a monorail at floor level. It carries racks with unplated parts to the loader and returns with racks carrying plated parts. The loader is a mechanical connection between the two lines.

Every 72 seconds, two racks of plated parts are ready to be unloaded. When in position, the automatic transfer lifts them into the unloader.

At the same time, two racks of raw parts are placed in empty carriers on the plating machine. The transfer mechanism shuttles racks with the plated parts to the monorail conveyor for unloading and picks up a new load of raw parts. The monorail carries racks after unloading through manual emptying, stripping, rinsing, and reloading.

Co-ordinated—All controls for the monorail, loader, and electroplating machine are centralized for co-ordination. Manual controls are

JONES & LAMSON MACHINE COMPANY

the man who needs a new machine tool is already paying for it



Still useful, yes . . . but is it still Profitable?

When the purchase of new machine tools comes up for discussion, it's not at all unusual for someone to comment — "but our present machines still seem to be doing a good job".

On the surface, this objection seems to make good sense. It doesn't stand up, however, because it isn't good economics.

While surveying a number of metalworking plants recently, a prominent industrial publisher discovered this startling fact: — *In every plant with machinery more than ten years old, profit margins were steadily falling!*

Why should this be the case, especially when sales were at an all-time high?

The answer, of course, is that older, still "useful" machines cannot produce enough goods at a low enough cost to compete favorably with new machines on a profit basis.

Write for J & L's Replacement Information Kit, which contains much valuable information. Jones & Lamson Machine Company, 517 Clinton St., Springfield, Vermont.

Turret Lathes • Fay Automatic Lathes • Precision Boring Machines • Thread & Form Grinders • Optical Comparators • Threading Dies, Taps & Chasers

Transfer unit in loading position. Raw parts (right) are about to be elevated to start of plating line. Finished parts at left are being removed. View is from monorail line

provided for forward or reverse jogging. The lines can be restarted from any position.

The automatic loader has two double stations, one for loading and one for unloading. All control and drive mechanisms are exposed for accessibility.

Racks of raw parts move into position at the plating machine, following a conventional flow pattern. Finished racks move away on the same hooks—there is no mixing of raw and finished stock on alternate hooks.

The loader also permits the synchronization of two plating operations using a common monorail. It can serve for intermediate operations like degreasing, drying, or rack stripping.

Plating—Eaton's plating operation takes parts through 30 immersions. Raw parts pass through several washes, acids, and cleaners. They remain at nickel plating for 55 minutes before further rinsing.

Chrome immersion takes 5 minutes. Electroplating is complete after several additional rinses. Any tank can be bypassed.

Maker—The transfer machine was made by Hanson-Van Winkle-Munning Co., Matawan. N. J.

Beryllium Expands

New plant points up future of the metal. Structural applications are forecast

PRODUCTION uses and continuing research into the techniques of manufacturing beryllium parts were emphasized at the dedication of Brush Beryllium Co.'s plant at Elmore, Ohio, on Nov. 17.

Production—The new plant will produce 10,000 lb of vacuum cast beryllium a month—enough to supply half the Atomic Energy Commission's requirements, plus some for private industry. (For details of the AEC's use of metal and its properties see STEEL, Aug. 19, p. 152.) The vacuum cast ingots are made into a fine powder at Brush's Cleveland plant, then pressed and sintered into large blocks from which wrought products are made or parts are machined.

The $4.5-million plant will also produce 20,000 lb of beryllium hydroxide a month. This material will be used at the Elmore plant in making master alloys, such as beryllium-copper ingots, and in continuously cast billets of beryllium-copper. Other uses include beryllium oxide refractories.

Research—A pilot rolling mill at the Elmore plant will develop techniques for the production of wrought products. Basic research in fabricating techniques is carried on at Cleveland.

The process development laboratory at Elmore will produce pilot-plant quantities of special beryllium compounds.

Predictions—Beryllium's nuclear, mechanical, and thermal properties, says Brush, indicate continued large scale use in nuclear reactors—particularly portable ones like those being designed for aircraft.

The company says the metal is being studied and flight tested for aircraft construction. Its high strength and lightness will permit design of structural assemblies much lighter than those now used.

Rockets—The re-entry of high speed missiles or spacecraft generates high frictional heat. Such sudden heat loads can be absorbed by beryllium, says Brush. Its melting point, thermal conductivity, and heat capacity are high.

JONES & LAMSON MACHINE TOOLS

the man who needs a new machine tool is already paying for it

The Turret Lathe with a fully automatic thread-chasing cycle!

Here is full turret lathe versatility and a threading attachment with a fully automatic cycle — all in one machine. Now you can be sure of concentricity of threading with other lathe work, *all done in one chucking*, with the time saving of the Auto-Threader!

This Auto-Threader will chase straight or taper threads — or a combination — internal or external, from the front of the machine.

Other features include: uniform thread length, by means of positive stop and follower nut disengagement together with rapid tool withdrawal; precision lead control by full depth follower nut engagement on a hardened and ground leader.

Write for descriptive folder No. 5440. Jones & Lamson Machine Company, 517 Clinton Street, Springfield, Vermont.

Turret Lathes • Fay Automatic Lathes • Precision Boring Machines • Thread & Form Grinders • Optical Comparators • Threading Dies, Taps & Chasers



A jet engine compressor housing with 248 holes is machined automatically in about 5½ hours. Numerical controls govern the cycle

Tape Guides Jet Engine Boring

User expects to cut setup and machining time by nearly 75 per cent. The machine will do the work of three standard boring mills and should turn out more consistent work

WITH TAPES guiding it through intricate cycles, a horizontal boring machine will process 248 holes in jet engine compressor casings at General Electric's Evendale, Ohio, plant.

The cycle time will be about 5½ hours. Setup and machining time are expected to be cut 74 per cent.

Cycle—Four spindles will bore and generate a front face and back counterbore at each of the hole locations. The same job now takes three standard boring mills, say GE officials.

The operator locates the part in the fixture with an alignment telescope. After the cycle is started, a punched paper tape guides the tools to complete the part. Since there are four controlled spindles, as many as four operations can be done on any hole.

All positioning of the spindles and table rotation come from the tape. The machine has a heavy duty boring head mounted on a compound slide. The head holds a precision boring spindle and three hydraulically actuated, feed-out quill and spindle assemblies. They are individually controlled for three different feed ratios. The spindle will locate vertically over a maximum range of 40 in.

The 55-in. rotary table indexes through 360 degrees from a reference point at a speed of about 5/6 rpm. (Engineers point out that this speed of rotation could be used as a feed for milling the periphery of the part.) The table has a lifting mechanism for rotation and a clamp for locking the table in position.

Built by Barnes Drill Co., Rockford, Ill., the machine maintains an accuracy of 0.005 in. true position and repeatability of ±0.001 in. All feed screws, including the spindle feed-out screws, are precision engineered ball screws.

Control — A GE-designed electronic control actuates the machining cycle and performs seven programmed functions: It picks the motions to be actuated and sets spindle advance, spindle speed, spindle feed, depth of feed; then it tells whether to position only, or position and drill, and decides on dwell, no-dwell, and backfeed combinations.

The control unit gets its information from standard eight-channel Flexowriter tape.

JONES & LAMSON "AUTOMATION"



J&L's Unique Approach to "Automation"

"Automation" is a tricky word — one that has many definitions. However, at Jones & Lamson its basic meaning is always the same . . . "the solution to a cost reduction problem".

In some cases, this could involve automatic in-process gaging, size adjustment feed back, self-resetting of tools, and automatic handling for long runs on single machines. Other problems might call for an articulated, sequential *line* of machines, complete with automatic handling, inter-machine transfer and automatic control of speeds, feeds, etc.

Through numerical control, using punched tapes, J&L "automation" *also greatly increases small-lot flexibility*. In this case, machine set-up and change-over become primarily an office procedure.

We would be pleased to show you how J&L's approach to "Automation" can be put to good use in *your* operations. Write for literature — Jones & Lamson Machine Company, 517 Clinton St., Springfield, Vermont.

Turret Lathes • Fay Automatic Lathes • Precision Boring Machines • Thread & Form Grinders • Optical Comparators • Threading Dies, Taps & Chasers

Chem-Milling Handles Tough Job

It takes place of nine parts which were riveted or bonded. Stiffening is built in. Method is gaining wide acceptance in production of replacements for complicated subassemblies

THE PART above is said to be one of the most outstanding examples of complex chemical milling.

It illustrates the design possibilities of the method: Nine parts formerly riveted or bonded are replaced by a single piece. Stiffening is built in.

Production—The milling is done at the U. S. Chemical Milling Corp., Manhattan Beach, Calif. Each piece has three taper angles. The final shape takes nine operations.

After the plate passes through staging and cleaning, a masking coating is applied to restrict metal removal. The area to be cut is scribed and the masking removed.

Immersion—The first cut, a taper, is made by controlling the rate of immersion in and withdrawal from the chemical solution. Afterward, the exposed section is again masked and three additional areas scribed, stripped, and tapered.

As soon as the three tapers are finished, the part is completely masked, and the deepest cut scribed, stripped, and milled.

The final five steps are comparatively shallow, and the part requires no further masking. As each area is scribed, stripped, and milled, the additional metal removed brings all six cuts to their final dimensions.

Weight Saving—Airplanemakers are the biggest boosters of chemical milling. Here are some of its advantages:

1. The method gives designers greater latitude in part shapes. Complex forms, broad or narrow cuts, and sharp corners are possible in one operation. Parts can be formed before or after chemical milling.

2. Parts are lighter. The process eliminates riveting, welding, and brazing.

3. The designer can count on closer tolerances: 0.002 in. plus half the sheet tolerance is usual. Machine milling tolerances are 0.010 in.

4. Tooling is simpler than that for machining.

5. No final sanding or polishing is needed.

6. No special equipment is needed. The process uses conventional cleaning tanks and paint spray booths.

7. Labor cost is comparatively low. Highly skilled operators are not needed.

JONES & LAMSON OPTICAL COMPARATORS

the man who needs a new machine tool is already paying for it



Simulated machining operations give production control as well as absolute inspection

At J&L we answer an inspection problem by asking, "How was the piece made?"

Take, for instance, this inspection of broached slots in turbine discs. Holding fixtures are similar to those used in the actual broaching operation. Measurements are taken, right and left, as on the broaching machine. During inspection, the part moves in the same planes as it does while it is being machined. And the combination of light, optics and chart act as the cutting tool.

Through this visualization of the machining operation, it is a simple matter for the operator to take measurements on the comparator and then go back to the broaching machine to make any necessary adjustments.

Thus, with J&L, you not only inspect end products but, more importantly, you find out *where* and *when* to adjust the manufacturing process. Write to Jones & Lamson Machine Company, 517 Clinton Street, Springfield, Vermont, for literature.

Turret Lathes • Fay Automatic Lathes • Precision Boring Machines • Thread & Form Grinders • Optical Comparators • Threading Dies, Taps & Chasers



Workman is installing forging die on holder. Wire thread inserts greatly reduce stripping, seizing, galling, and corrosion

Inserts Up Die Holder Life

They eliminate thread failures. Spring qualities provide up to 90 per cent thread engagement, improve load distribution. They are said to lengthen holder life seven times

WIRE thread inserts have cut maintenance costs and increased the life of holders for hot forging dies at the Forging & Screw Machine Div., Scovill Mfg. Co., Waterbury, Conn.

The installation eliminated thread failure, one of the most frequent sources of failure. Holder life has been increased seven times.

Problem—Steady vibration of heavy forging presses loosened hold-down bolts. Threads were damaged, and dies moved out of alignment. Billet scale also fell into unused holes and prevented tightening the bolts on a larger die.

Sometimes, an operator inadvertently placed a cold billet in the die when starting a new run. The die halves would stick together and hold-down bolts usually pulled out, stripping the threads.

Old Solution — Each time a thread was stripped or became worn, the die holder was returned to the machine shop. It was welded, drilled, and retapped.

Unless another die holder was available, the press was down for at least 4 hours.

New Way—All die holders are now fitted with wire thread inserts made by Heli-Coil Corp., a division of Topp Industries Inc., Danbury, Conn. Here's how they are installed (standard bolts are ¾ in. in diameter):

Drill 25/32-in. hole; tap threads with a ¾-10 Heli-Coil tap; install ¾-10 inserts.

Insert liners are said to increase the safe load carrying capacity by as much as 30 per cent, compared with unprotected tap holes. Load distribution is better; threads are practically free from wear by vibration, assembly, and disassembly.

Saving Drill Time

You can shorten cycle on larger machines by doing one operation on a small drill press

COMBINING drilling and chamfering of flanged hubs cut the cost of the operations almost in half at the Automotive Div., Clark Equipment Co., Jackson, Mich.

The move also reduced handling and machine time on a larger drill.

Auxiliary — An operator drills flanged hubs for automatic converter transmissions. He loads a part on the drilling machine table and presses the start button. Holes are drilled, tools retracted, and stopped automatically.

During the automatic cycle time the operator chamfers the holes of a previously drilled flange. He uses a Walker-Turner 15 in. drill press which is next to the automatic drilling machine.

Previously, the operator had idle time during the drilling cycle.



SMALLER PRESS
. . . saves time for big one

Other Examples—Clark uses several small drill presses. They can be easily moved for short runs.

In addition to direct labor savings, the firm feels that cycle time reductions on a larger machine are worth its investment in smaller drill presses.

Standby — Engineers point out that several drill presses operated in tandem can be put into emergency service when production machines are down. Such setups can include coolants and cutting fluids.

With suitable fixturing, drill presses can counterbore, spotface, undercut, and even mill. On one occasion, the machine was used to grind a small radius.

JONES & LAMSON
THREAD TOOLS

the man who needs
a new machine tool is
already paying for it



Wholesale Hollow Milling with J&L Die Heads

This is part of a transfer machine set-up that uses 48 J & L Die Heads on hollow milling operations. Rough and finish turning is performed on both ends of automotive suspension shafts, as 1440 finished parts come off the line every hour.

Even in single spindle set-ups, hollow milling chasers in J & L Die Heads remove metal *four times faster* than single point tooling. And in many cases, J & L threading Die Heads can be adapted to hollow milling, by merely using the required turning chasers.

Chasers for multiple turning and contour forming, as well as straight or taper turning, can be used in J & L Die Heads for hollow milling on most types of turning equipment.

Write for booklets — "Hollow Milling with Die Heads", and "Let's Talk about Thread Tools". Jones & Lamson Machine Company, 517 Clinton Street, Springfield, Vermont.

Turret Lathes • Fay Automatic Lathes • Precision Boring Machines • Thread & Form Grinders • Optical Comparators • Threading Dies, Taps & Chasers



how do you measure economy?

economy is not measured by price alone!



PROVED OVER THE YEARS

When you are concerned with metal abrasives there are many yardsticks that must be applied to truly measure economy.

How long will an abrasive last? How long before it breaks down into fines and becomes inefficient?

How destructive is the abrasive to machinery and equipment?

How efficiently does it perform and what is the time cycle for good performance?

To sum it all up — the economy of using any abrasive can be measured by the **cost per ton of metal cleaned!**

On every count, Malleabrasive has proved its superiority over the years in hundreds of plants.

If you want to improve the economy of your blast cleaning operations — check Malleabrasive.

MALLEABRASIVE

THE GLOBE STEEL ABRASIVE CO., MANSFIELD, OHIO ®

1907—Fiftieth Anniversary—1957

Updating a Planer

Here's an example of how you can get the most out of your old, single purpose machines

MAINTENANCE engineers at National Supply Co., Torrance, Calif., converted an open side planer into a three dimensional, tracer controlled milling machine.

Power — All movements were changed to hydraulic power. A 25 hp, variable speed spindle replaced the planer tool mount. Speeds can be varied from 60 to 3000 rpm.

Vertical travel of the milling head is 8 in.—two hydraulic cylinders are mounted on opposite sides of the housing. The head can be swiveled. Feed rates are 0 to 25 ipm.

Control—A three-direction tracer valve is mounted above a template table. The operator stands about 48 in. from the spindle center line. Controls are on an arm which extends across the table from the spindle housing.



OLD PLANER
. . . now a tracer mill

The template table (40 by 60 in.) is an extension of the work table. Mounted outboard, it can be moved to any point along the work table.

Supply—Hydraulic power comes from a 30-hp combination unit. It delivers 20 gallons per minute to supply the spindle; a dual pump supplies 11 gpm for rapid table traverse and 11 gpm for feed movement.

Cross and vertical rapid traverse are done by opening the tracer valve. The pendant control starts and stops the spindle and table. For straight cuts, a device automatically deflects the tracer stylus at the end of each stroke.

Soldering Aluminum

You can join it and galvanized metals with a zinc-based alloy. No flux is needed

AMONG the new ways to solder aluminum is one developed by G. M. Bouton and P. R. White, metallurgists, Bell Telephone Laboratories, New York.

It's based on an inexpensive, stable, zinc-base alloy. No flux or abrasion is required. Joints are said to be stronger than the basis aluminum.

The method also works well on galvanized metals.

Refinement — Stability of the joint is insured by careful exclusion of lead, tin, bismuth, and cadmium, and the addition of magnesium and aluminum. The excluded elements are often a source of intergranular corrosion which destroys the joints.

Technique—It is not necessary to remove rolling mill oils or oxides. The joint is heated electrically or by blowtorch. One stroke of the solder stick is enough to penetrate the oxide and wet the aluminum.

Oxide film is lifted off much like paint peeling from wood. When wiped off, surfaces can be joined by adding more solder.

The method, says Bell Telephone, is equally effective on galvanized metal. No flux is needed.

The dark area around solder illustrates how the alloy loosens the oxide layer. Solder alloys with metal beneath. Wiping oxide away eliminates need for flux

HERE'S WHY FOOTE BROS.

Duti-Rated LIFETIME GEARING



GIVES BETTER PERFORMANCE ...LONGER LIFE

GEAR PERFORMANCE COMPARISON CHART



DUTI-RATED GEAR— Hardened after cutting. Precision processing permits maximum hardness while holding accuracy within extremely close tolerances.

ORDINARY HARD GEAR— Hardened after hobbing and shaving; hardness limited to maintain reasonable accuracy.

ORDINARY GEAR— Hardened before cutting; hardening limited to maintain machinability.

SOFT GEAR— Low hardness—excessive size required because of low capacity.

LINE-O-POWER Speed Reducer

AND YOU GET Duti-Rated Gearing in EVERY Line-O-Power Drive

LINE-O-POWER Right Angle Drive

Horizontal GEARMOTOR Speed Reducer

Horizontal VARI-MOUNT Variable Speed Drive

Vertical LINE-O-MOUNT Speed Reducer

Write for DUTI-RATED Gear and LINE-O-POWER Catalogs. See how you can get more for your drive dollar.

this trademark stands for the finest industrial gearing made

FOOTE BROS. Duti-Rated LIFETIME GEARING

T. M REG. U. S. PAT OFF

FOOTE BROS.

Better Power Transmission Through Better Gears

FOOTE BROS. GEAR AND MACHINE CORPORATION
4583 South Western Boulevard Chicago 9, Illinois

An important question for every steel maker:

What is Periclase?

This brief report, which uses no highly technical formulas, answers the question "What Is Periclase" in a concise discussion of (a) the mineral make-up of Periclase as compared to other magnesia materials, (b) why Periclase characteristics make it superior to other magnesias for high performance steel industry applications, and (c) how Periclase is produced by Kaiser Chemicals as the primary ingredient of basic refractories used by the steel industry.

The differences between Periclase and other magnesia materials used for basic refractories are more important to steel makers than to any other group of people.

Why?—first, because the steel industry is the nation's largest user of basic refractory products. *Second and even more important,* because the quality of refractories used has a direct effect on steel-production efficiency. Thus, the quality of the materials in the refractory products he buys is the individual concern of every steel producer.

Magnesia-Bearing Minerals Plentiful In Earth

Magnesia, (magnesium oxide), long known for its excellent physical and chemical properties in basic refractory use, is plentiful in natural forms in the earth. But in its natural form, such as found in brucite, dolomite and magnesite, it is almost always found combined with additional oxygen, lime, water and mineral impurities. These additional materials weaken or destroy many of the chemical and physical properties that make magnesia a good refractory.

On the other hand, natural forms of *pure crystalline* magnesia—known as Periclase—are rarely found in the earth. To obtain commercial quantities, it must be produced synthetically.

Periclase vs. Magnesite In Refractories

A closer comparison between Periclase and one of the commonly used natural materials—Magnesite—will show the nature of the difference in materials . . . and how these differences affect refractory performance.

A single grain of either Periclase or magnesite the size of a grain of coarse sand is composed of several thousand tiny magnesium oxide crystals. In both cases, these crystals are held together as a grain by some form of bond or bonding ingredient.

The manner in which the individual MgO crystals are bonded together into grains determines their ultimate performance in refractory service.

How Magnesite Impurities Form Grain Bond

To obtain deadburned magnesite grains, natural magnesite ore (mostly magnesium carbonate) is processed by calcining. Impurities such as lime, silica and iron act as fluxes in the sintering kiln. Burned at temperatures of about 2750°F., most of the carbon is released in the form of carbon dioxide gas, leaving a brownish residue of magnesite grains.

Although calcining raw magnesite crystallizes the MgO and releases the carbon, *it does not remove* the random impurities present in the natural ore. During the calcining process, these impurities soften or liquefy and form a coating around the MgO crystals. When the temperature is lowered at the completion of the calcining operation, these coatings harden and form a glass-like cement which bonds the crystals into grains.

The resulting magnesite grains are composed of 80-90% MgO crystals and 20-10% other minerals which have combined to form the glassy bond.

How "Impurities Bond" Affects Performance

Although MgO crystals can withstand temperatures of over 5000°F. without appreciable change, the glassy bond formed by the impurities cannot. Even at relatively low temperatures, these impurities again soften or liquefy and lose their ability to hold the MgO crystals together, permitting them to fall apart under stress (with the liquids even acting as a lubricant!).

As with the weakest link of a chain, the degree to which deadburned magnesite grains can withstand high temperature, physical stress and chemical attack *is determined by the low-melting impurities* rather than by the highly refractory MgO.

How Periclase Is Obtained From Sea Water

Of the several ways to obtain Periclase, one of the most efficient is the sea water process developed and used by Kaiser Chemicals. Because magnesium is present in sea water as magnesium chloride (a salt), magnesium hydroxide is precipitated when sea water is reacted with calcined dolomite.

This hydroxide is then thoroughly washed in fresh water to remove the calcium chloride and other soluble impurities. Finally, the pure magnesium hydroxide* is passed through filters to remove much of the excess water, and the resulting paste (known as filter-cake) is fed into high-temperature kilns for calcining.

Two Methods For Producing Periclase Grains

The fact that Periclase is synthesized allows us to control and vary the manufacturing process to produce a "custom made" product.

Standard high purity Kaiser Periclase (92% MgO) is produced by adding a small, precisely-controlled amount of very fine pure silica (SiO_2) to the filter-cake just before it is fed into the kiln. During the calcining operation the silica reacts with a portion of the MgO to form magnesium orthosilicate. This highly refractory mineral bonds the individual MgO crystals into grains.

Magnesium orthosilicate is an excellent bonding ma-

*At this hydroxide stage it is similar to the milk of magnesia used for toothpastes and medicinal purposes.

FOUR PRIMARY STEPS IN PRODUCTION OF PERICLASE FROM SEAWATER





1 When granular dolomite is added to treated seawater in this reactor, magnesium hydroxide is precipitated, washed and processed through several thickeners.

2 Next step is the vacuum filter where excess water is removed. The resulting "filter cake" is discharged on a screw conveyor for movement to kiln.

3 At the kiln, patented mineralizers are added to the filter cake. Under heat, these additives cause chemical reactions which bond MgO crystals into Periclase grains.

4 For extremely high purity Periclase, a chromium compound is added to the filter cake. This additive—under extreme heat—causes MgO crystals to lock themselves together in a "crystal bond" (no liquid phase) to form high density, low porosity Green Grain Periclase.



terial as it is similar in many respects to MgO itself. In contrast to a glassy magnesite bond, subsequent cooling or reheating does not shrink or liquefy this crystalline bond.

In addition, unusually high kiln temperatures are used in the production of Kaiser Periclase. These high temperatures cause individual crystals to combine into larger, more stable crystals. At the same time, the intense heat reduces the overall mass by shrinking the newly formed grains. In passing through the hottest point in the kiln (3300°F.) this mass is shrunk to its maximum density and minimum porosity. The result is a dense, high purity Periclase grain of very low porosity and exceptional volume stability.

Second Method Produces "Crystal Bond"

For very severe applications, Kaiser Chemicals engineers developed an even higher purity Periclase grain —96% MgO. Known as Green Grain Periclase, it is produced by adding a minute amount of chromium compound to the filter cake as it is being fed into the kiln for calcining. The effect of this patented mineralizer is to induce a phenomenal recrystallization.

Influenced by extreme heat during the calcining operation, this additive sets up stresses within each MgO crystal which cause the crystal to send out uneven projections of itself. These projections interlock with similar projections of adjacent crystals. No melting occurs, no liquids are formed. The result is a recrystallized homogeneous mass of MgO crystals tightly interlocked into a highly refractory Periclase grain of highest density and lowest porosity . . . ideal for the most severe refractory applications!

* * *

The foregoing discussion, although greatly simplified, points out the principal differences between magnesite and Kaiser Periclase. The magnesite bond, formed from impurities carried in natural ore and by added fluxing agents, is weak at use temperatures and unable to withstand the effects of high temperatures and chemical attack. Kaiser Periclase, being synthesized from high-purity MgO, permits the bond to be pre-determined and controlled. The resulting highly refractory crystalline bond is stable and can resist chemical attack almost to the same degree as the MgO crystal itself.

Kaiser Chemicals refractory specialists, backed by more than 15 years of continuous research and development, are producing special refractory compositions that assure open hearth and electric furnace operators peak performance in specific applications. These products are available for fast delivery to all parts of the United States from plants at Natividad and Moss Landing, California, and Columbiana, Ohio.

If you have a problem in your mill that might be solved by the prompt delivery of superior quality, dependable basic refractories, a Kaiser Chemicals field representative will be pleased to give you detailed information and immediate engineering assistance.

Kaiser Chemicals

Pioneers In Modern Basic Refractories

REFRACTORY BRICK & RAMMING MATERIALS • CASTABLES & MORTARS
MAGNESITE • PERICLASE • DEADBURNED DOLOMITE

Call or write Kaiser Chemicals Division, Dept. S-7261 Kaiser Aluminum & Chemical Sales, Inc., at any of the Regional Offices listed below:

PITTSBURGH 22, PA. . . . 3 Gateway Center
HAMMOND, IND. . . . 518 Calumet Building
OAKLAND 12, CALIF. . . . . 1924 Broadway

Kaiser Chemicals Basic Refractories for the Steel Industry

Kaiser PERICLASE (D-S) — Kaiser PERICLASE-CHROME Brick
Kaiser CHROME-PERICLASE Brick — Permanente 165 Ramming Mix
Permanente 84 Ramming Mix

Pontiac's Automated Foundry Line



Casts 150 Engine Blocks an Hour

Automated line at Pontiac's foundry is built around two indexable molding machines. Twenty men are doing the work that took 68 on block molding operations

INDEXABLE machines mold, close flasks, and shake out 2400 V-8 engine block castings a day in the foundry at GM's Pontiac Motor Div., Pontiac, Mich. Manual handling of flasks is passe.

Observers maintain constant control of all phases of the system through a master panel. Maintenance men check and correct reasons for minor stoppages. Workers are needed only to set chaplets and cores, and to pour, spray the drags, and hang blocks on the cooling conveyor.

Operations are interlocked by electrical and pneumatic controls that may be preset for cycle time and production. Pusher cylinders and conveyors move the heavy flasks (they weigh about 2100 lb each when filled).

Equipment—The system has two four-station molding machines, one for making copes and a similar one for making drags. Built by Osborn Mfg. Co., Cleveland, they operate alike, but require slightly different setups and auxiliary equipment; the cope is deeper than the drag, and the drag has to be rolled over to bring it face up.

Each machine has an indexing mechanism that carries the patterns and molds from station to station.

Sequence of Operation — Work begins at the drag molding machine. The metal pattern is blown off by an air jet and sprayed with a parting lubricant at the make-ready station. It is done while the conveyor moves the drag flask into the filling station.

When indexing is complete, the pattern is elevated. In moving upward inside the drag flask, the pattern picks up the flask and makes it ready for filling. A slight upward motion opens the sand hopper gates and releases a predetermined amount of sand. The pattern (with the flask still in place) is lowered to the indexing mechanism.

Stripping Station—Jolting and squeezing take place at the third station, with the mold and floating pattern plates free of the indexing mechanism. The flask is indexed to the draw station, while

he No. 4921 Osborn molding machine, a four-station indexing unit, fills the flask nd jolts, squeezes, and draws the mold



he pattern is removed at the fourth station



Core setting fixture is manually brought into position over drag mold. Guide pins insure perfect setting of cores

another flask is being filled and another pattern prepared at stations one and two.

At the stripping station, the mold and pattern are raised. The mold is drawn on rollers; the draw piston descends; and the pattern is returned to rest on the indexing cradle arms.

The drag mold is ejected onto a conveyor and moved to a turnover station. Rotated through 180 degrees, bringing it face up, the mold is moved off onto a conveyor for the next operation, which is spraying with a quick drying graphite solution.

Cores Are Added—After spraying, the drag molds are pushed onto the coring conveyor. The seven cores which are to be set are preassembled and set into a fixture on a conveyor which carries them to the setting station.

They are removed from the conveyor manually in a core setting fixture which lifts the cores as a unit and positions them in the drag. The entire core assembly is set accurately in a few seconds.

Cope Molds — Meanwhile, the cope is being processed on a similar molding machine. Copes are made in the same way as the drags. At the fourth station, withdrawal of the pattern leaves

Completed molds (about 2100 lb each) are poured on a conveyor



Hot V-8 blocks are carried to cooling tower by overhead conveyor



Flasks move through a jolt-shakeout system and return to molding machine after the sand and casting have been removed

the cope in a raised position. Th cope is moved into the closing ma chine and positioned directly abov the drag. The closed mold i moved onto a conveyor which car ries it to the pouring area.

After pouring, the molds con tinue on the conveyor for a re quired cooling time before they ar rive at the mold shakeout area Castings are removed, flasks emp tied, and the cope and drag halve conveyed back to the two moldin machines.

Automatic Handling—The han dling equipment, although not part of the molding machines, i integrated and synchronized s that flasks approach and enter th machines at proper intervals, an mold halves are handled out c the machines when ready fo transfer.

Indexing and transfers ar done pneumatically and hydraul cally in response to solenoi valves, most of which are actu ated by the master timer.

The sand supply also is handle automatically. Sand from th shakeout is checked by probes, an the correct amounts of water an bonding material are added auto matically in the muller. After mulling, conveyors deliver the san to the molding machine hopper

Maintenance—A preventive main tenance program for the automati foundry unit has been one of th principal reasons for its success A four-man crew is available dur ing each of the two shifts the un operates.

During the third shift, when th unit is closed down, a crew clean checks, and repairs all key op erations and machinery units.

Coremaking—Pontiac has rea ized additional economies in core making. Eleven Osborn coremak ing machines handle the load. On can turn out 360 barrel and crank shaft cores an hour.

The five-station machines blo and draw the core boxes on a pre set time cycle. Cores are bakee assembled, and loaded on con veyors for delivery to the moldin line.

• *An extra copy of this article is ava able until supply is exhausted. Wri Editorial Service,* STEEL, *Penton Bld Cleveland 13, Ohio.*



JUST OFF THE PRESS!

A new Kodak Catalogue of Industrial Radiographic materials and accessories

A gold mine of information on the choice of x-ray films for today's radiographic inspection procedures.

This 16-page booklet is far more than an ordinary catalogue. It lists and describes the latest Kodak X-ray Films and accessories. It goes much further. It gives the characteristics of these fast films and provides charts that aid you in selecting the correct film for various applications and sources of radiation.

You may have this informative catalogue without charge. Just mail a card or the coupon with your request. Or ask your Kodak Technical Representative or your Kodak X-ray dealer.

EASTMAN KODAK COMPANY—*X-ray Division*—Rochester 4, N.Y.

Get your free copy of this new book

MAIL THIS COUPON

Eastman Kodak Company
X-ray Division
Rochester 4, N.Y.

Gentlemen: Please send your free new catalogue "Kodak Materials and Accessories for Industrial Radiography." 23-12

Name_____

Street_____

City_____

State_____

Kodak
TRADEMARK

Regina Reports 50% Paint Saving with RANSBURG NO. 2 PROCESS

Electrostatic Spray Painting

That's because Ransburg No. 2 Process puts the paint on the product instead of up the stack



Aluminum housings, hung four to a fixture, are uniformly painted electrostatically as the conveyor makes a loop around the Ransburg reciprocating disk unit. Eight hand sprayers formerly were required to handle this work in Regina's finishing department.



The Regina Corporation, Rahway, N. J., replaced hand spray with Ransburg No. 2 Process to paint their twin-brush Floor Polisher and Scrubber, and their Electrikbroom.

Now, a single reciprocating disk unit automatically handles the work which formerly required eight hand sprayers. Even with increased production, Regina is using 50% less paint. Quality of the work is improved with maximum uniformity on all parts.

NO REASON WHY YOU CAN'T DO IT, TOO!
Want to know what Ransburg No. 2 Process will do for you in your finishing department? If your present production justifies conveyorized painting, let us prove the many cost-saving benefits which can be yours. Write for our No. 2 Process brochure which pictures many on-the-line examples of electro-coating on a wide variety of products, and describes our free survey service.

Ransburg ELECTRO-COATING CORP.
Indianapolis 7, Indiana

RANSBURG

Foundry Tool Mixes Ore

Taconite plants use conveyor belt mixer to process sticky, abrasive concentrates

A COMPANY doing business with one industry does well to search for markets in entirely different fields. A case in point is the Pekay Machine & Engineering Co., Inc., Chicago.

Pekay makes what it calls a Mixer-Muller, widely used in the foundry industry for conditioning molding sand. The infant taconite industry has opened a new future for the machine.

Concentrate Mixing — Late in 1955, the Erie Mining Co., setting up its preliminary taconite plant at Aurora, Minn., found itself with no successful way of mixing bentonite and sea coal with the ore concentrate. After a year of experimentation, the Mixer-Muller has become standard equipment for mixing ore, coal, and bentonite for balling drums at Erie Mining Co.'s Hoyt Lake, Minn., plant. Taconite processing plants of Bethlehem Cornwall Corp., Hilton Mines Co., and Cleveland-Cliffs Iron Co. also are using the machine.

The taconite concentrate, which weighs 125 lb per cu ft, is tacky and abrasive. The mixers handle it in a continuous operation, receiving it from and discharging it to a conveyor belt. The units cost $4000 to $8000.



Pekay Mixer-Muller installed in conveyor line at Erie Mining Co.'s Hoyt Lake, Minn., taconite beneficiating plant

Low Voltage Power Equipment Has Quick-Make Manual Closure

The K line of circuit breakers consists of 600-volt units in 225, 600 and 1600 ampere frame sizes. Life of contacts and of the breaker is extended by eliminating arcing damage resulting from careless closure by hand.

The K line switchgear uses closed door drawout for the circuit breakers. They can be moved from operating to test and disconnect positions within their enclosure without opening switchgear cabinet doors.

Unitized construction reduces the switchgear to three basic components—the breaker, the enclosure, and a cradle assembly on which the breaker slides for drawout. *Write*: Switchgear Div., I-T-E Circuit Breaker Co., Philadelphia, Pa. *Phone*: Locust 7-1420



Batteries for Electric Trucks Have High Capacities



Type HC and CMS batteries provide increased power within standard battery dimensions. Battery sediment space is reduced to a minimum (allowing the use of long plates) by wrapping positive plates for maximum insulation and minimum shedding.

The HC battery has a rated capacity of 72 ampere hours per positive plate, yet has the same outside dimensions as the industry's former standard of 60 ampere hours per positive plate. Discharge rate is 6 hours. Positive plates are 0.255 in. thick and 16 7/16 in. long.

The CMS battery has a rated capacity of 55 ampere hours per positive plate at the 6-hour rate. It is used with low sit-down fork trucks (center control types) with collapsed mast heights of about 72 in. *Write*: C & D Batteries Inc., Washington and Cherry Streets, Conshohocken, Pa. *Phone*: Taylor 8-1140

High-Speed Tube Machine Produces Double Flares

A motor driven mechanical press and a mechanical punch-shifting and tube-clamping mechanism make up this machine. It produces a double flare on steel or nonferrous tubing at a single tube position. Tube capacity of the machine is ½ in. OD x 0.035 in. for steel and up to ⅝ in. OD for copper, brass, or aluminum tubing. Maximum output: 90 flares a minute.

Operation cycle: When the clutch is engaged, the tubing is gripped by two steel dies. There are two punches. The bulging punch first strikes at the end of the tubing. The punches automatically retract and shift position laterally. Next, the flaring punch strikes the end of the tubing. The two dies then reopen, completing the cycle, and the clutch is disengaged by the antirepeat mechanism. *Write*: Automation Associates Inc., 1444 E. 11 Mile Rd., Madison Heights, Mich. *Phone*: Lincoln 1-8013





DENTROL WIRE—submerged in gasoline, oil, water—proves resistant to all 3.

New Dentrol thermoplastic wire RESISTS ALL 3—GASOLINE, OIL, WATER

Dentrol wire affords *new safety* wherever wiring is exposed to gasoline or oil—*new economy* over the lead-covered cable you're now using in these areas.

Made with a clear nylon jacket over-all, Dentrol not only beats gasoline, oil and moisture—but is exceptionally resistant to abrasion. It is easily installed (hard, smooth finish makes pulling through conduit simple), easily stripped, lightweight for easy handling.

Suggested uses: for 600 volt wiring for lighting, power and control in and around service stations, refineries, tank farms, and industrial plants.

Dentrol is Underwriters' Laboratories approved as TW and "gasoline-resistant" wire for use in open raceway where exposed to gasoline or gasoline vapors. Thus it meets the provisions of section 5023 of the 1956 National Electrical Code, concerned with installations in hazardous locations.

Available in colors, and in 500′ cartons. See your Anaconda distributor. For information write: Anaconda Wire & Cable Company, 25 Broadway, N. Y. 4, N. Y.

LIVE BETTER ELECTRICALLY

SEE THE MAN FROM **ANACONDA®** FOR **DENTROL WIRE**

NEW PRODUCTS and equipment

Welding Machine

This twin arc welding machine performs controlled welding operations on both sides of large production parts. It is a submerged arc machine that welds at the rate of 80 ipm.

The machine illustrated makes four reinforcement welds along the edges of both sides of a beam 12 ft long. Its cross section is 8 x 8 in.



The part is squared by a mechanism located in the center of the machine. Fixtures on each end of the bed both center and clamp the part in position. They also turn the part over. *Write*: Expert Welding Machine Co., 17144 Mt. Elliott Ave., Detroit 12 Mich. *Phone*: Twinbrook 1-4327

Granite Riser Blocks

These riser blocks provide an accurate surface parallel to the working surface plate at an elevation that allows the use of standard height gages. This eliminates erroneous readings caused by vibration or chatter often encountered with extralength height gages.

The touch of a finger will guide the block into position. The block floats on a cushion of air. There is no wear on the surface plate or the block itself while it is being moved.

Air at about 40 psi is piped into a hole in the back of the block and led to a series of grooves on the bottom surface. The grooves

Furnace Cars

FOR MECHANICAL or ELECTRIC OPERATION



Above: 60-ton furnace car for mechanically operated system.

CUSTOM-BUILT and quality-built for dependable service. Easton experience includes all types of furnace and transfer cars for modern heat treating systems. Built to any desired capacity.

Write or telephone for technical information.

CUSTOM BUILT

A-1052 TRADE MARK

EASTON®

EASTON CAR & CONSTRUCTION COMPANY • EASTON, PA.

Keep Plant Air CLEAR of Welding Fumes

Welding shops equipped with Ruemelin Fume Collectors are assured of a clean, healthful atmosphere. Harmful fumes, heat and smoke are eliminated *at their source*, before they have a chance to spread throughout the shop. This lessens fatigue . . . improves working conditions . . . paves the way for increased plant production. Ruemelin Fume Collectors are approved by Industrial Commissions and insurance companies. Thousands in service. Available with 9 ft., 15 ft., 17 ft. and 20 ft. reach. Write for Bulletin No. 37-E.

RUEMELIN MFG. CO.

MFRS. & ENGRS. • SAND BLAST & DUST COLLECTING EQUIPMENT
3882 NORTH PALMER STREET • MILWAUKEE 12, WISCONSIN, U. S. A.

A 8755-½P

are cut to within two inches of the edges, so that if the block is moved too close to the side of the surface plate the air will escape. This safety feature prevents the block from "floating off" the surface plate.

When the block has been positioned, the operator shuts off the air supply.

Blocks are also available in square and cylindrical shapes. Top and bottom surfaces are flat to a maximum reading of 0.000050 in. and parallel within 0.000075 in. *Write*: Herman Stone Co., 1860 N. Gettysburg Ave., Dayton, Ohio.

Switch Plugs In

The Plug-In Limit is a precision limit switch which can be replaced almost immediately should the need arise.

The unit consists of two parts—a terminal block enclosure containing the wiring connections to the outside line, and a switch enclosure that includes all moving mechanical and electrical parts.



The switch enclosure is fitted with four current-carrying spring plugs integrally molded to the basic switching element, and the terminal block with four corresponding receptacles. When plugged together, they form a complete switching unit.

Wiring connections are made to the sealed terminal block enclosure which is permanently mounted on the machine.

The switch enclosure is plugged onto this block, precisely positioned by dowel pins, and held by two screws.

Actuating arms may be preset to eliminate on-the-job adjustment.

The switch also offers complete adjustability of actuation and versatility of mounting. *Write*: Micro Switch, division of Minneapolis-Honeywell Regulator Co., Freeport, Ill.

Press Automation

The Press Pacer is a transfer unit which can convert standard stamping presses into fully automated transfer lines up to 60 ft long.



The transfer unit can be used with both straight-side and gap-frame presses. It is portable, easy to install, and can be disassembled in minutes.

The unit is situated between presses. Aluminum transfer rails with retractable pickup fingers move back and forth to carry stampings from one press to another. Transfer distance can be adjusted from 8 in. to 3 ft or more.

Pickup fingers are interchangeable to accommodate a wide range of stampings in different shapes and sizes. Presses are tripped by the pickup fingers as they are retracted.

Two cams driven by an electri motor in the unit's base produc the reciprocating motion of th transfer rails. *Write*: Contrac Mfg. Div., Sheffield Corp., Dayto 1, Ohio. *Phone*: Kenmore 3131

Refractory Cutter

This portable masonry splitte saves time in shaping refractorie to size. It makes a sharp, sawlik break.



The hand-operated splitter eli inates the hazards of flying dus and fragments.

The splitter has a breaking pres sure of over 50,000 lb. *Write* E & R Mfg. Co., Rochester, Ind.

Index Table

Model GEM-26 will index part weighing up to 2000 lb. The tabl has a diameter of 26 in. and ma be equipped with as many as 1 stations.

The table will index to ± 0.00 in. on a 24-in. diameter work cir cle, with true Geneva motion Workpieces are positioned smoothly and quickly, in as little as 2/3 sec ond.

The table is used to automat drilling, tapping, chamfering, and welding machines, gaging devices and other high volume operations

Standard equipment: Rotary air motor, solenoid valve, limit switch *Write*: Gray Equipment Co., 13600 Ford Rd., Dearborn, Mich. *Phone*: Tiffany 6-7573

call KE for plant expansion or new facilities





1,250,000 barrel cement plant addition recently completed by KE for Marquette Cement, one of world's largest cement producers.

has made KE a major engineer-contractor serving the Minerals Industry

Placing of four fully-lined mills in a few hours instead of days—a unique center pier kiln drive —a 2,700′ cement transport "airway." With these and many more planned innovations and short-cuts, Kaiser Engineers completed Marquette Cement's Cape Girardeau plant expansion quickly and economically. Construction cost and time were well below industry average.

Mining, transportation, beneficiation, materials handling, processing in cement, gypsum, coal, ferrous and non-ferrous metals facilities—these are but a few of the fields wherein KE serves the Minerals Industries—from economic analysis through start-up.

KE ingenuity—multi-industry experience, keenly applied—can benefit your next facility. Let us show you how.

KAISER ENGINEERS

engineers—contractors
Contracting since 1914

Division of Henry J. Kaiser Company • Oakland 12, California • New York, Pittsburgh, Washington, D.C., Buenos Aires, Calcutta, Dusseldorf, Montreal, Rio de Janeiro, Sydney, Tokyo

NEW literature

Write directly to the company for a copy

Clutches

Bulletin 501, 4 pages, describes electromagnetic disc clutches for use on ball mills, rod mills, and kilns. Stearns Electric Corp., 120 N. Broadway, Milwaukee 2, Wis.

Aircraft Fasteners

Bulletin 8-411, 16 pages, describes the line of Huckbolt fasteners and stumps, their properties, installation, and inspection. Huck Mfg. Co., 2480 Bellevue Ave., Detroit 7, Mich.

Dust Collectors

Long cone collectors are dimensioned and described in Bulletin 150-A, 4 pages. Sprout, Waldron & Co. Inc., Muncy, Pa.

Fork Truck

This 4-page bulletin describes an electric-powered fork truck with a capacity of 2000 lb. Elwell-Parker Electric Co., 4205 St. Clair Ave., Cleveland 3, Ohio.

Taps

This 20-page booklet tells how specific taps for tough steels, cast iron, aluminum, zinc, or brass give better performance. Detroit Tap & Tool Co., 8615 E. Eight Mile Rd., Warren, Mich.

Alloy Temperature Chart

This chart indicates the temperature range of alloys and their usefulness in carburizing and nitriding, reducing atmospheres, and oxidation. Rolled Alloys Inc., 4815 Bellevue Ave., Detroit 7, Mich.

Refractories

Bulletin 324, 24 pages, gives detailed information on castables, cements, ramming mixes, and patches. Chas. Taylor Sons Co., Cincinnati, Ohio.

Corrosion Prevention

This chart presents data on 20 military-specification corrosion preventives, including solvent cutbacks, petrolatum barriers, general purpose preservatives, and engine preservation lubricants. Pennsylvania Refining Co., Butler, Pa.

Nuclear Stainless

This 4-page bulletin discusses the use of stainless steel and special purpose alloy tubing and pipe in nuclear energy applications. Alloy Tube Div., Carpenter Steel Co., Union, N. J.

Recording Systems

This 16-page bulletin contains descriptions and specifications of oscillographic recording systems and a line of accessories and unit instruments. Industrial Div., Sanborn Co., 175 Wyman St., Waltham 54, Mass.

Industrial Flooring

Bulletin 655, 4 pages, tells how to use emery aggregate in new floors and in resurfacing or patching old ones. Walter Maguire Co. Inc., 60 E. 42nd St., New York, N. Y.

Iron and Steel Castings

Physical properties and chemical compositions of iron and steel castings are covered in this 16-page bulletin. Howard Foundry Co., 1700 N. Kostner Ave., Chicago 39, Ill.

Grinding Spindles

This 8-page bulletin describes a line of spindles for grinders and boring machines. Ex-Cell-O Corp., 1200 Oakman Blvd., Detroit 32, Mich.

High Strength Steels

Structural steels with yield strengths over 200,000 psi are described in this 16-page bulletin. Composition, properties, and technical data are presented for all grades. End uses are described. Climax Molybdenum Co., 500 Fifth Ave., New York 36, N. Y.

Dispersions

Uses and properties of colloidal graphite, molybdenum disulfide, mica, glass, copper, and custom dispersions are described in a 4-page bulletin. Acheson Colloids Co., Port Huron, Mich.

Flexible Couplings

Shaft couplings used where units are spaced far apart and one bearing is provided for only one of the units are covered in Bulletin 99, 4 pages. Thomas Flexible Coupling Co., Warren, Pa.

Adjustable Ramps

A line of adjustable ramps (with capacities from 10,000 to 20,000 lb) for loading docks is described in this 8-page bulletin. Rowe Methods Inc., 2534 Detroit Ave., Cleveland 13, Ohio.

Filter Powder

Bulletin 28, 3 pages, describes an insoluble cellulose fiber that is compatible with brighteners and never causes roughness in copper, other cyanide-type, or bright nickel solutions. MacDermid Inc., Waterbury, Conn.

Cold Friction Saw

This 4-page bulletin describes a saw for cutting beams, columns, and angles. Wilmington Plant, United Engineering & Foundry Co., Wilmington 99, Del.

Seam Welding

Bulletin SP-7A, 16 pages, details seam welding from material preparation to weld testing. Taylor-Winfield Corp., Warren, Ohio.

Curtain Walls

Porcelain enamel on steel and aluminum curtain walls and veneer panels are described in this 8-page bulletin. Ingram-Richardson Mfg. Co., Beaver Falls, Pa.

Aluminum Sheet

Properties and uses of each of the aluminum sheet alloys are discussed in this 28-page bulletin. Revere Copper & Brass Inc., 230 Park Ave., New York 17, N. Y.

Adjustable Speed Drives

Bulletin GEA-6643, 16 pages, describes a line of direct current drives from 3 to 150 hp. A slide rule is included which calculates case dimensions, horsepower, speed range, power unit weight, and motor frame size. General Electric Co., Schenectady 5, N. Y.

Stainless Pipe

This chart, TDC-188, lists the analysis and comparative price ratios of 33 seamless stainless grades. Tubular Products Div., Babcock & Wilcox Co., Beaver Falls, Pa.

Instrument Switches

Advantages and construction of instrument and control switches rated for 20-ampere continuous capacity with 600-volt insulation are described in Bulletin 14B8112A, 8 pages. Allis-Chalmers Mfg. Co., Milwaukee 1, Wis.

Stainless Steel Fasteners

This 12-page bulletin covers aircraft bolts, slotted and Phillips machine screws, flat and round rivets and washers. Allmetal Screw Products Co. Inc., 821 Stewart Ave., Garden City, N. Y.

FILMS AVAILABLE

"Steel Valley" is an 18-minute movie showing how the lighter, tougher superalloy steels and reactive metals are made and used. Public Relations Dept., Sharon Steel Corp., Sharon, Pa.

STEEL

December 2, 1957

Market Outlook

RESIGNED to sluggish buying during the remaining weeks of this year, leading steelmakers are sizing up market prospects for 1958. What they see is mildly encouraging, especially in light of the slow markets of recent weeks.

They expect the current economic adjustment to continue. But they think finished steel use will hold close to 1957 volume, around 85 million tons. They expect ingot output to slip no more than 5 per cent below this year's estimated 114 million tons.

SIDEWISE MOVEMENT—Current steel business continues on a plateau. Buying for December delivery is hand to mouth, and the pace of specifying is likely to slow down as the holidays approach.

As a result, this month's volume will likely fall appreciably under that of November—and business that month certainly wasn't up to seasonal expectations.

FORWARD BUYING—Despite current dullness, sellers are encouraged by a slight improvement in consumer interest in first quarter (1958) requirements. It is particularly noticeable in sheets and strip.

Many users that have been ordering sparingly the last several months, now appear to be more concerned about their early first quarter needs.

RISING ACTIVITY—Growing production of automobiles continues to spark hope of an early pickup in orders for steel. So far, the improvement in autos has not meant much.

Latest reports show auto output running about 30 per cent better than it did a year ago. Figures for the latest week place output above 154,000 cars for the first time since late in December last year.

INVENTORIES SHRINKING—Consumers' stocks of steel products are being reduced steadily. But evidence is accumulating to indicate some users have reduced inventories about as far as they can; they are depending more and more on prompt mill shipments. Automotive inventories are estimated at around 18 days and are believed rising.

Extension of the short position on stocks could catch some consumers off base in some products should demand take a sudden spurt—a possibility in light of rising agitation for stepped up production of missiles and other defense items.

PRODUCTION—Reflecting continued sluggish demand, steelmaking operations dropped sharply last week, falling 3 percentage points to 73.5 per cent of ingot capacity. It was the slowest production pace, except for strike and holiday periods, since 1954.

Output for the week is estimated at about 1,880,000 net tons. That compares with the all-time high of 2,525,000 tons in the week ended Dec. 23 last year.

PRICES—The decline in scrap prices was resumed last week, following a week of relative stability. STEEL's composite on No. 1 heavy melting steel slipped another 17 cents, and at $33 is at a new low since December, 1954.

Other price indexes are unchanged, with STEEL's arithmetical average on finished steel products holding at $146.03.

NATIONAL STEELWORKS OPERATIONS



DISTRICT INGOT RATES

(Percentage of Capacity Engaged)

	Week Ended Dec. 1	Change	Same 1956	Week 1955
Pittsburgh	74.5	— 5.5*	96.5	99
Chicago	76	— 1.5*	100.5	97.5
Mid-Atlantic	82	— 0.5	101	99
Youngstown	71	+ 1	101	100
Wheeling	61	— 3	102	102
Cleveland	71	— 0.5*	106.5	96
Buffalo	78	— 5	107.5	80
Birmingham	63.5	+ 3	94.5	94
New England	53	0	80	88
Cincinnati	81.5	— 4.5	95.5	92.5
St. Louis	87.5	— 1.5	102.5	101.5
Detroit	88.5	— 3.5*	102	100.5
Western	86	0	105	103
National Rate	73.5	— 3	100	100

INGOT PRODUCTION‡

	Week Ended Dec. 1	Week Ago	Month Ago	Year Ago
INDEX (1947-1949=100)	117.3†	121.1	127.1	154.9
NET TONS (In thousands)	1,884†	1,945	2,041	2,489

*Change from preceding week's revised rate. †Estimated. ‡Amer. Iron & Steel Institute. Weekly capacity (net tons): 2,559,490 in 1957; 2,461,893 in 1956; 2,413,278 in 1955.

Metalworking Outlook—Page 47

Technical Outlook—Page 93

Do you need HIGH STRENGTH - MACHINABILITY - MINIMUM DISTORTION?

Specify B&L

Strain-TEMPERED STEEL

Bliss & Laughlin Strain-Tempered* Cold Finished Bar Steels provide any or all of these material characteristics with suitable modifications to best meet your specific requirements.

Designed to speed up your production, save heat treating operations and reduce fabricating difficulties, Strain-Tempered Steel also offers you opportunity for an improvement in part service quality, and a saving in material costs.

Perhaps you are now paying a price premium for extra properties which you may not need or want. When you buy B&L Strain-Tempered Steel you get a product tailored to your job. By eliminating extra charges for unneeded qualities you ensure lowest unit part costs.

Complete modern facilities for handling Strain Tempered Steel Bars & Coil Stock.



ADDED ECONOMIES

are now available to you in ordering Strain-Tempered Bar Steels. Get in touch with us at once, and let B&L sales engineers show you these new savings.

Our latest Bulletin gives further details on Strain-Tempered Bars. Ask for Bulletin #55.

*Trade Mark Registered

BLISS & LAUGHLIN, INC.

GENERAL OFFICES: HARVEY, ILLINOIS

SALES OFFICES IN ALL PRINCIPAL CITIES

FOUR PLANTS:—

HARVEY, ILL.



DETROIT, MICH.

BUFFALO, N. Y.

MANSFIELD, MASS

Nonferrous Casting Shipments

(Tons)

	BRASS-BRONZE	ALUMINUM	MAGNESIUM
1957*	425,000	390,000	16,700
1956	483,153	397,291	18,084
1955	504,449	413,581	13,927
1954	417,965	312,486	12,889
1953	495,248	329,011	17,259
1952	504,955	259,489	17,429
1951	588,771	275,216	16,567
1950	528,486	271,541	7,612

Source: Bureau of the Census.
*Estimated by STEEL.

Foundries Feel the Pinch

NONFERROUS foundries seem to be in the same boat as producers of gray iron, malleable, and steel castings. They're shipping smaller tonnages than they did last year and watching backlogs decline.

At the end of August, shipments of brass and bronze castings were 13 per cent behind last year's level; backlogs were down 30 per cent. Magnesium castings showed a 6.5 per cent decline in shipments and a 25 per cent drop in unfilled orders. For aluminum castings, shipments were off 2 per cent, backlogs 20 per cent.

Less Consumption — Reduced shipments of brass and bronze castings can be attributed to smaller consumption by manufacturing and construction industries and slow inventory replacement. Orders from shipbuilders, industrial valvemakers, and pump manufacturers have been relatively good. Shipbuilders, having one of their best peacetime years, are ordering more manganese bronze propellers than ever before.

Volume has slipped in bearings, bushings, plumbing fixtures, valves, and fittings. The drop in shipments of magnesium castings is due mainly to defense cutbacks.

Higher Costs—Fluctuating costs of raw materials, red brass ingots, and scrap confuse the price picture. While ingot and scrap prices fall, the costs of labor, overhead, and freight continue to mount. Result: Foundries hold the line, despite falling metal prices.

Outlook for 1958—Automakers will increase their use of aluminum castings by 8 per cent in 1958, predicts Kaiser Aluminum Co. Greater tonnages will also be used in business machines and home appliances. Magnesium castings seem destined for better sales now that the government is pushing missile research.

Next year's consumption of aluminum diecastings will be about 205,000 tons, surpassing sand and permanent mold castings combined. Diecastings offer a wider range of applications than other types, particularly when large production runs are involved.

In the heavier aluminum alloy castings, the trend is toward the permanent mold process. Motor vehicles provide a market for 60 per cent of permanent mold castings. Home appliances take 10 per cent of the output, industrial-commercial equipment 8 per cent.

Of 3127 U. S. foundries that produce nonferrous castings exclusively, 2363 cast brass and bronze, 3111 cast aluminum, and 218 magnesium. There were 2895 exclusive nonferrous foundries in 1955.

More Expansion—Although capital expenditures for nonferrous foundry expansion have slowed, large investments are still being made. In the brass industry, Walworth Co. is building a $5-million-plus engineering and research center at Braintree, Mass. Ford Motor Co.'s Sheffield, Ala., plant is

They, Too, Produce Stainless . . .

Here are two additions to the list of stainless steel producers published on Pages 108 and 109 of the Nov. 4 STEEL.

Claymont plant, Wickwire Spencer Steel Div., Colorado Fuel & Iron Corp. (Wilmington, Del.) is a producer of stainless clad plates.

Summerill Stainless Tube Div., Columbia Steel & Shafting Co. (Pittsburgh) is a producer of seamless pipe and tubing, mechanical and pressure pipe and tubing.

For an extra copy of the 16-page article containing the table of stainless steel producers, write Editorial Service, STEEL, Penton Bldg., Cleveland 13, Ohio.

working up to a daily output of 140 tons of permanent mold and diecast aluminum parts for engines and automatic transmissions. Chevrolet is building an aluminum foundry at Massena, N. Y.

Blast Furnace Output Up

Blast furnace production (pig iron, ferromanganese, and spiegeleisen) totaled 6,519,478 net tons in October, reports the American Iron & Steel Institute. This compares with 6,627,911 tons in September, and 7,315,559 in October last year.

Of total output in October, 6,454,450 tons were pig iron (September—6,569,074; October, 1956—7,245,650) and 65,028 tons ferromanganese and spiegeleisen (September—58,837; October, 1956—69,909).

Output in the first ten months this year was 68,280,112 net tons (67,632,845 pig iron and 647,267 ferromanganese and spiegeleisen). In the like period last year, it was 61,581,491 tons (61,041,605 pig iron and 539,886 ferromanganese).

BLAST FURNACE PRODUCTION—October, 1957
(Net Tons)
(Pig Iron, Ferromanganese & Spiegeleisen)

Districts	October 1957	October 1956	First Ten Months 1957	First Ten Months 1956
Eastern	1,524,799	1,574,265	14,796,591	12,942,686
Pittsburgh-Youngstown	2,069,052	2,550,197	22,871,063	21,521,926
Cleveland-Detroit	831,984	843,679	8,259,267	7,301,913
Chicago	1,280,670	1,457,557	13,702,797	12,429,827
Southern	474,739	521,576	5,294,449	4,176,778
Western	338,234	368,285	3,355,945	3,208,361
Totals	6,519,478	7,315,559	68,280,112	61,581,491

This tile is called a dog bone!



It's a husky supporting tile—used instead of an expensive alloy casting in a double suspended arch designed by B-L for high temperature aluminum, steel and glass furnaces. It can stand extremely high temperatures—can be used with or without insulation.

The dog bone supports the arch tile. Bottom lugs are sloped so that the weight of the arch tile will draw the two together. Filler tile space out the arch.

Naturally the completed arch will possess all of the inherent characteristics of Bigelow-Liptak suspended construction. Burned out or damaged tile can be removed without disturbing large areas. Expansion is confined to individual tile—will not accumulate over the entire width of the arch. It all adds up to more production—less down time through keeping heat from raising the roof.



We'd like to tell you more about it. Just write.

BIGELOW-LIPTAK Corporation
AND BIGELOW-LIPTAK EXPORT CORPORATION
13300 PURITAN AVENUE, DETROIT 27, MICHIGAN

UNIT-SUSPENDED WALLS AND ARCHES

In Canada: BIGELOW-LIPTAK OF CANADA, LTD., *Toronto, Ontario*

ATLANTA • BOSTON • BUFFALO • CHICAGO • CLEVELAND • DENVER • HOUSTON • KANSAS CITY, MO. • LOS ANGELES • MIAMI • MINNEAPOLIS • NEW YORK • PHILADELPHIA • PITTSBURGH • PORTLAND, ORE. • ST. LOUIS • ST. PAUL • SALT LAKE CITY • SAN FRANCISCO • SEATTLE • TULSA • MONTREAL • SAULT STE. MARIE, ONT. • VANCOUVER • WINNIPEG

Tin Plate . . .

Tin Plate Prices, Page 149

American Can Co. has opened a facility at Milwaukee for processing tin plate for canmaking from 15,000-pound coils. The plant addition is the first of its kind in the North Central states, and is part of Canco's $27 million program to set up facilities for handling coils in strategic canning areas.

Plates . . .

Plate Prices, Page 147

Plate orders (excepting shipbuilding requirements) are off an estimated 15 per cent this quarter in the East. Several eastern Pennsylvania producers will become current on schedules by year-end, but at least two will have carryovers.

More fabricating shops are placing orders on 30-day leadtime, compared with 45 recently.

Tank and weldment volume is lower; consumers' steel inventories are larger. Electrical equipment demand is holding up, and substantial stainless clad volume is being estimated.

In general, plate fabricating shops are getting steel tonnage in the volume required, and deliveries are not too far extended.

The New York Shipbuilding Corp., Camden, N. J., has a contract for the first nuclear-powered merchant ship to be built. Its cost: $21 million. The keel will be laid next year. Babcock & Wilcox Co. has a contract ($9 million) to build the atomic-powered propulsion plant.

Steel Bars . . .

Bar Prices, Page 147

Incoming orders for hot-rolled bars dipped slightly during November, largely due to disappointing automobile requirements. December order volume is difficult to measure because there have been few advance orders, but expectations are that the month's volume will fall below that of November, if for no other reason than the normal holiday lull at the end of the month.

Shops producing heavier steel forgings in the East are reported to have relatively better backlogs than those turning out smaller items. The strength is accounted for by propeller shafts, press cylinders, and heavy power equipment.

Reinforcing Bars . . .

Reinforcing Bar Prices, Page 147

Demand for concrete reinforcing bars is slower. Price competition among distributor-fabricators is increasing. Deliveries are prompt, and bar mills' backlogs are off noticeably.

In the East, slower demand for bridges and foundation work leaves less volume to be estimated. Schools and educational buildings lead current inquiry. The Social Security Building in Baltimore will take 6000 tons of bars to be furnished by Sweet's Steel Co., Williamsport, Pa.

Ferroalloys . . .

Ferroalloy Prices, Page 154

Ferroalloy production increased 9.31 per cent last year, reaching a new high of 2,639,681 net tons, reports the U. S. Bureau of Mines. In the preceding year it was 2,414,789 tons.

Shipments in 1956 amounted to 2,859,573 tons, against 2,541,489 in 1955. Shipments were up 1.89 per cent from 1955, but their value increased 20.8 per cent, due to higher prices.

Consumption of ferroalloying elements by the steel industry in 1956, as reported by the American Iron & Steel Institute was: Chromium, 166,118 tons; nickel, 58,929; aluminum, 26,958; molybdenum, 13,764; copper, 4379; titanium, 2820; tungsten, 1973; vanadium, 1433; lead, 1419; zirconium, 994; cobalt, 726; columbium-tantalum, 199; boron, 21.

Ferromanganese imports (excluding silicomanganese) last year amounted to 123,953 net tons valued at $28,511,690. In the preceding year, the total was 52,236 tons valued at $11,898,383.

FERROALLOY PRODUCTION & SHIPMENTS

(Net Tons)

	1956		1955	
	Production	Shipments	Production	Shipments
Ferromanganese[1]	1,062,171	1,052,432	974,902	1,013,619
Ferrosilicon	460,193	434,213	382,699	424,744
Silvery iron	438,694	413,953	459,291	488,292
Ferrochromium[2]	498,855	480,169	407,703	421,867
Ferrotitanium	7,762	7,228	6,565	6,881
Ferrophosphorus	73,175	94,545	77,115	75,862
Other[3]	98,831	107,033	106,514	110,224
Totals	2,639,681	2,859,573	2,414,789	2,541,489

[1]Including manganese briquets and silicomanganese.
[2]Including ferrochrome silicon, Chrom-X, chrom sil-X, and other chromium alloys.
[3]Including alsifer, ferroboron, ferrocolumbium, ferrotantalum-columbium, ferronickel, ferrotungsten, ferromolybdenum, simanal, spiegeleisen, zirconium-ferrosilicon, ferrovanadium, and miscellaneous.

THE 479 DAY TEST:

it's a RECORD!

We knew they were good . . . the trade knew they were good . . . welding engineers knew they were good. But nobody was prepared to forecast that the new Miller line of GOLD STAR welders would erect a startling milestone in welding history . . . in welder performance!

In August, 1956, Miller began production on a new completely sealed semi-metallic rectifier. The date proved to be significant in welding circles. For 479 days later NOT A SINGLE FAILURE HAD BEEN REPORTED FROM THE FIELD!

A new transformer design teamed with the revolutionary completely sealed semi-metallic rectifier led to the introduction of the Miller GOLD STAR series of rectifier type dc and combination ac-dc machines.

Today, weldors everywhere agree that Miller GOLD STAR machines give you:

a. The best welding current ever produced,
b. Record-making dependability.

The 479 day test was made on thousands of Miller GOLD STAR welders working under every conceivable condition—indoors—outdoors—in hundreds of industries.

Here indeed is an all-time record for welder and rectifier reliability.

miller ELECTRIC MANUFACTURING CO., INC.
APPLETON, WISCONSIN
distributed in Canada by CANADIAN LIQUID AIR CO., LTD. Montreal



Ingot Manipulator built for a west coast steel company

Thomas builds machinery to your drawings and specifications

*We will be glad to figure your inquiries

THOMAS
MACHINE MANUFACTURING CO.
PITTSBURGH 23, PA.

57

GRIPHOIST TIRFOR Saves Man-hours for You in Plant Installation and Maintenance

One man using a GRIPHOIST places heavy tank in 5 minutes

One man using GRIPHOIST TIRFOR often Does the job of a crew of 4 to 6 men

- Factory — one man using GRIPHOIST placed 3 sections of 40,000 lb. machine in minutes
- Maintenance—overhead lift jobs handled when power machinery unavailable
- Rigger — 2 men moved 40-ton load from truck to foundation — in lieu of costly set-up
- Construction — 6 GRIPHOISTS saved 1000 man-hours removing false-work on 12-span overpass
- Vans — Trucks — GRIPHOIST loads and unloads girders, angles and plates

Manually operated, GRIPHOIST weighs 42 lbs; rated for 3300 lbs. single line to 6 tons 4-part line; unlimited travel 1/2" cable.

Ask your dealer or write

Princeton Griphoist, Inc. 32 GEORGE STREET • BOSTON 19, MASS.

Griphoist, Inc. 424 BRYANT STREET • SAN FRANCISCO 7, CALIF.

Sheets, Strip . . .

Sheet & Strip Prices, Pages 148 & 149

Sheet sellers are out beating the bushes for orders. Failure of automotive buying to develop in expected volume has put the mills in an uncomfortable backlog position, since buyers generally, following the automotive pattern, have been trimming inventories and ordering only requirements in sight.

This absence of heavy forward buying is resulting in stepped up competition among the mills for orders. Reports are more frequently heard of freight absorption as sellers seek business in areas distant from their producing mills.

There is a little more optimism for first quarter. Meanhile, December volume is expected to fall under that of November, largely because of the holidays at year-end.

Auto inventories are still estimated around 18 days, but they are reporting starting to edge up slightly as makers aim for high December car output.

Tubular Goods . . .

Tubular Goods Prices, Page 151

Specialty tubing sales are slowing down, chiefly because of sluggish automotive demand and generally slow warehouse ordering.

Oil country tubular goods sales are falling as inventory reduction gains momentum among well drillers. Unfilled order backlogs at tube mills are off substantially. Rapid deliveries will be required in first quarter next year.

Foreign sales of pipe and tubing are down. A moderate inventory reduction program among foreign users is beginning. A Pittsburgh tubular goods producer thinks sales will be up sharply in second quarter next year, both on foreign and domestic account.

Wire . . .

Wire Prices, Pages 149 & 150

Pressure for prompt shipments is accompanying wire orders for December. Volume is light. Fourth quarter bookings for all grades of carbon wire (manufacturers, heading, and spring) will fall below earlier estimates, running not over

10 to 12 per cent, compared with third quarter.

Consumers are reducing inventories for yearend, but some are placing orders for January in slightly better volume. The wire mills are able to meet most delivery demands with skeleton crews, but any material increase in demands would soon be reflected in more extended shipments. Rod buying is slow.

Warehouse . . .

Warehouse Prices, Page 152

Demand for steel products from warehouses in the East is slow. In most instances, November volume was off slightly from October's and a further decline is expected this month. However, one important distributor of sheets and strip in the Pittsburgh area reports a 10 per cent increase in sales during November, compared with the previous month. The sales gain there was due to slightly improved automotive business and general completion of inventory reductions among customers.

Price weakness has developed in flat-rolled products and buttweld pipe in several districts.

Pig Iron . . .

Pig Iron Prices, Page 152

Prospects for an immediate improvement in demand for merchant iron are not bright. Foundries are receiving a relatively light flow of orders and are buying iron hand to mouth to cover needs. Automotive foundries are a little more active, and farm implement shops in the Chicago area are doing fairly well.

A big distributor of pig iron in the Cleveland district estimates that business for 1957 will be 8 to 10 per cent below that booked in 1956. "However," says a sales manager, "the business we are doing this year was considered mighty good five years ago, both in dollars and in tonnage."

Structural Shapes . . .

Structural Shape Prices, Page 147

Except for schools, less structural steel tonnage is being estimated in the East. (And many schools are designed to use more

Magnetic-Core Coil Classifier Inspects Tin Plate Continuously, Automatically

Beckman coil classifiers are measuring and recording characteristics and defects of tin plate around-the-clock, in continuous on-line operation. Linear travel, pinhole footage, over- and under-gage tolerances, coatings, quenching strain, slivers, abrasions, damaged edges are all detected and recorded while coils are rolling and shears flying.

Data from detectors is supplemented by manual entries showing date, purchase order, coil, line, and turn numbers. All information is then delayed for correct relationship to shear position. Upon shear activation, the appropriate totalized data is recorded on preprinted formats, with separate records for quality control and customer information. This in-process correlation of upstream detection with shear control and data printout permits accurate profiling of product with no lag in production – increases profit margins.

No vacuum tubes are used – all electronic circuitry consists of extremely reliable, toroidal magnetic cores and other passive elements. Without modification, Beckman coil classifiers are compatible with data reduction systems and in-process control.

Coil classifiers are typical of the many reliable system applications of Beckman counters and timers, proved in thousands of field installations. For more information on counting and timing system applications, write for Data File 2D-13-67.

Beckman®

Systems Division

325 N. Muller Ave., Anaheim, Calif.

a division of Beckman Instruments, Inc.

Responsible new positions in engineering, manufacturing, technical marketing. Write for Career File 10.



EXACT TEMPERATURE FOR ALCO FORGINGS

New furnaces for ALCO open-die and circular forgings use automatic heat-zone control for better quality of end product

New furnaces are part of ALCO's drive for top quality in open-die and circular forgings. The furnaces, like the car-bottom furnace above, are zoned, and each zone is automatically controlled to the proper heat level. This means that each ingot or billet reaches the forging press at the right temperature for planned reduction, and it also means that ALCO heat treatment is exact and thorough, assuring the best physical properties for the intended application.

Quality and leadership like this are in every step of production of an ALCO forging. They save you money. If you do extensive machining on open-die or circular forgings, Hi-Qua-Led Steel®, which only ALCO offers, can cut your costs up to 50 per cent.

ALCO forgings are available to 40 ft and 30,000 lb in the open-die type, and from 15 to 145 in. OD for circular forgings. For specific information contact the nearest ALCO sales office, or for new full-color brochure write Spring & Forge Division, Dept. OCF-6, P. O. Box 1065, Schenectady 1, New York.

ALCO

ALCO PRODUCTS, INC.

NEW YORK

Sales Offices in Principal Cities

Locomotives • Diesel Engines • Nuclear Reactors • Springs • Steel Pipe • Forgings • Oil-Field Equipment

bars and bar shapes than structurals.)

Most fabricating shops are shipping tonnage in excess of bookings. In trying to maintain backlogs, they are estimating the bulk of the volume brought out that will fit into shop facilities.

The price for steel in place and deliveries are dominant factors in the placement of contracts.

Pittsburgh area fabricators report demand from the construction industry continues to decline, and only spotty demand is seen over the winter months.

Structural Shortage Over

Structural steel is now readily available for the entire construction industry, John G. Hotchkiss, district engineer, American Institute of Steel Construction, told a meeting of the Structural Steel & Ornamental Association of New Jersey.

Output of heavy structurals this year will be 25 per cent above 1956 levels to a record 6,700,000 tons, he said.

STRUCTURAL SHAPES . . .

STRUCTURAL STEEL PLACED

800 tons, high school, Butler, Pa., to Pittsburgh-Des Moines Steel Co., Pittsburgh; William F. Sutter, Nescopeck, Pa., general contractor.

455 tons, girder bridge, near Aldridge, Ill., to Vincennes Steel Corp., Vincennes, Ind.

380 tons, WF beam bridges, Effingham County, Ill., to Mississippi Valley Structural Steel Co., Decatur, Ill.

350 tons, four-span deck bridge on U. S. Route 24, Ripley, Ill., to Illinois Steel Bridge Co., Jacksonville, Ill.

300 tons, dormitory and dining hall, Pennsylvania State University, University Park, Pa.; to Bethlehem Steel Co., Bethlehem, Pa.; John McShain Inc., Philadelphia, general contractor.

270 tons, high school, Portage, Pa., to Griffith-Custer Steel Co., Johnstown, Pa.; Gamble & Gamble Construction Co., Bolivar, Pa., general contractor.

100 tons, high school, Fairfax, Va., to the Southern Iron Works, Norfolk, Va.; Banks & Lee Inc., Washington, general contractor; reinforcing bars to Ceco Steel Products Inc.

STRUCTURAL STEEL PENDING

5000 tons, superstructure, contract No. 3, suspension bridge, Ogdensburg project, St. Lawrence County, New York-Granville, Canada; American Bridge Div., U. S. Steel Corp., Pittsburgh, is low bidder at $5,742,755. Bethlehem Steel Co. bid $5,960,830. Bids were taken Nov. 21 at Albany.

5000 tons, 2150-ft suspension bridge, Ogdensburg project, St. Lawrence River, N. Y.; postponed for second time; Albany, N. Y.

4760 tons, reservoir project, intake substructures and tunnels, power project, near Pierre, S. Dak.; bids Dec. 18, tentative, to Corps of Engineers, Omaha, Nebr.

3500 tons, addition to Exchange Bldg., Seattle; plans completed; bids soon.

1200 tons, New York state educational building, Albany, N. Y.; bids Nov. 26.

MEET "LITTLE STEVE"

NEW SPACE SAVING, LOW COST UNIT WITH AUTOMATIC LOAD AND UNLOAD



Here's What "LITTLE STEVE" can do Automatically

- ELECTROPLATING
- ANODIZING
- BLACK JAPANNING
- ENAMELING
- ELECTROTYPE PLATING
- PLASTIC COATINGS
- BRIGHT DIPPING
- PHOSPHATE COATINGS

UP TO 40,000 PIECES PER DAY
540 RACKS OR ARMS PER HOUR

Yes, this new immersion processing machine by Stevens can process up to 40,000 pieces per day — and it has a variety of other uses too.

Ruggedly built, "Little Steve" can be obtained at a surprisingly low initial cost. It is ideal for large or small companies for it will fit many production cycles. It uses an arm as a rack or will take racks for small parts.

Being of small size it offers no floor space or load problems; involves low solution expense and means a small capital investment. It can be used easily as a laboratory testing machine.

For further information about "Little Steve" write for illustrated folder or call your local Stevens sales engineer.

FREDERIC B. STEVENS INCORPORATED
YOUR METAL FINISHING SUPERMARKET
DETROIT 16, MICHIGAN

STEVENS 75 YEARS OF SERVICE

WAREHOUSES AND OFFICES IN PRINCIPAL CITIES

960 tons, I-beam bridge, Jenkintown, Montgomery County, Pa.; bids Dec. 13, Harrisburg, Pa.

570 tons, I-beam bridge, Connellsville, Pa.; bids Dec. 13, Harrisburg, Pa., also 45 tons of reinforcing bars.

430 tons, five-span composite girder bridge, Farmington River, Farmington, Conn.; Oneglia & Gervasini, Torrington, Conn., low on general contract; also 165 tons of deformed steel bars, and 85 tons of steel piles.

275 tons, Public School No. 279, Brooklyn, N. Y.; pending.

270 tons, Public School No. 284, Brooklyn, N. Y.; bids closed.

230 tons, Mercer Island High School, Seattle; Dahlgren Construction Co., Seattle, general contractor.

Unstated, Geiger Air Field, aircraft shelter, Spokane; general contract to H. Halvorson Inc., Spokane, low at $219,319; steel to be furnished by government.

REINFORCING BARS . . .

REINFORCING BARS PLACED

6000 tons, Social Security Building, Baltimore, to Sweet's Steel Co., Williamsport, Pa.; McCloskey & Co., Philadelphia, general contractor.

1000 tons, dormitory and dining hall, Pennsylvania State University, University Park, Pa., to Bethlehem Steel Co., Bethlehem, Pa.; John McShain Inc., Philadelphia, general contractor.

960 tons, state highway structures, Onondaga-Wayne counties, New York, to the Bethlehem Steel Co., Bethlehem, Pa.; Bero Construction Corp., Waterloo, N. Y., general contractor; 1900 tons, structurals, to the Phoenix Bridge Co., Phoenixville, Pa.

895 tons, office building, State Department of Health, Atlanta, to Atlantic Steel Co., Atlanta; George A. Fuller Co., Atlanta, general contractor.

560 tons, dormitories, University of Miami, Coral Gables, Fla., to Joseph H. Fox Co., Birmingham; M. R. Harrison Construction Corp., Miami, Fla., general contractor.

255 tons, school, Philadelphia, to the Concrete Steel Co., Philadelphia.

250 tons, high school, Butler, Pa., to Copperweld Steel Co., Warren, Ohio; William F. Sutter, Nescopeck, Pa., general contractor.

140 tons, dormitory, Hamilton College, Clinton, N. Y. (70 tons of bars) to the Buffalo Steel Corp., Tonawanda, N. Y., and (70 tons, structurals) to the Utica Steam Engine & Boiler Works, Utica, N. Y.; R. S. Noonan Inc., York, Pa., general contractor.

190 tons, five state highway structures, Bow-Concord, N. H., to Scherer Steel Co., East Hartford, Conn.; Lane Construction Corp., Meriden, Conn., general contractor.

170 tons, addition, Roger Williams Hospital, Providence, R. I., Plantations Steel Co., Providence; Dimeo Construction Co., Providence, general contractor; 50 tons of structural steel to Tower Iron Works, Providence.

100 tons, high school, Somerville, N. J., to U. S. Steel Supply Div., U. S. Steel Corp., New York; Dean Construction Co., New York, general contractor.

67 tons, Washington state highway bridges, Yakima County, to Bethlehem Pacific Coast Steel Corp., Seattle; Lockyear & White, Longview, Wash., general contractor.

REINFORCING BARS PENDING

8965 tons, tunnels and intake substructures, power project, near Pierre, S. Dak.; bids Dec. 18, Corps of Engineers, Omaha, Nebr.; also 100 tons of wire mesh.

3000 tons, steel sheet piling; bids Nov. 26, U. S. Engineer, Louisville.

1025 tons, steel sheet piling; bids in to U. S. Engineer, Detroit.

1000 tons, retaining walls and underpass, Southwest Freeway, Second to Fourth Streets, Washington; bids Dec. 2, District of Columbia Highway Department.

455 tons overpass and grade separation, Seattle; S. S. Mullen Inc., Seattle, low at $755,636.

305 tons, state highway structures, including I-beam bridge, Jenkintown, Montgomery County, Pa.; bids Dec. 13, Harrisburg, Pa.; also 5118 linear feet of steel beam piles.

235 tons, deformed bars, two contracts; bids Nov. 27, General Stores Supply Office, Navy, Philadelphia.

180 tons, three flat slab bridges, Whatcom County, Wash.; bids to Olympia, Wash., Nov. 19.

157 tons, Washington state highway bridges, Kittitas and Spokane counties; bids to Olympia, Wash., Nov. 19.

156 tons, three Washington state spans, Grant County; bids to Olympia, Wash., Nov. 19.

114 tons, Washington state underpass, Pierce County; bids to Olympia, Wash., Dec. 3.

100 tons plus, three-level parking garage, for State of Washington, Olympia; bids to general administration director, Olympia, Wash., Dec. 17.

100 tons, Washington state, Yakima County four slab bridges; bids to Olympia, Wash., Dec. 3.

100 tons, two Washington state highway bridges, Yakima County; general contract to Lockyear & White, Longview, Wash., low at $86,990.

100 tons, Oregon highway overpass, Marion County; Tom Lillebo, Reedsport, Oreg., low at $93,442.

90 tons, Washington state underpass, King County; bids to Olympia, Wash., Dec. 3.

PIPE . . .

STEEL PIPE PLACED

Unstated, system improvement, Ketchikan, Alaska; general contract to Macri Construction Co., Anchorage, Alaska, low at $216,034 to the Alaska Public Works.

PLATES . . .

PLATES PENDING

500 tons or more, penstocks, tunnel lines, and surge tanks, expansion of Ft. Peck, Mont., powerhouse and facilities; bids to U. S. Engineer, Garrison District, Riverdale, N. Dak., Jan. 7.

500 tons, water storage tank, West Linn, Oreg.; tank project postponed; new bids may be called.

150 tons, three tanks, storage capacity 280,000 gal.; Atomic Energy Commission, Las Vegas, Nev.

100 tons plus, storage tank, King County District No. 75, Seattle; Pittsburgh-Des Moines Steel Co., Seattle, low at $56,606.

Unstated, reactor building shell, 80 ft in diameter by 139 ft high, carbon steel plate, 1 in. thick; also water tank, 200,000-gal. capacity; bids to Atomic Energy Commission, Idaho Falls, Idaho, soon; project AT (10-1) 927.

Unstated tonnage, 100,000-gal water storage tank, naval auxiliary air station, Mayport, Fla.; bids Dec. 19, district public works office, Navy, Charleston, S. C.

RAILS, CARS . . .

LOCOMOTIVES PLACED

Nickel Plate, 40 diesel units, including twenty 1750-hp road switchers to the Electro-Motive Div., General Motors Corp., La Grange, Ill.; ten 1800-hp road switchers to Alco Products Inc., New York; ten 1200-hp yard switchers to Fairbanks, Morse & Co., Chicago.

RAILROAD CARS PLACED

Canadian Pacific, 300 gondolas and 200 stock cars, to Canadian Car & Foundry Co., Montreal, Que.

Handling Coil Stock?

CHECK THESE

C-F LIFTER ADVANTAGES

- 1 Lifter handles wide range of coil sizes
- Requires minimum of only 10" to 12" between piles —saves storage room
- 1 man operation — eliminates hookers
- Positive grip on coil — no damage to material

• C-F Coil Lifters are saving time and labor in many plants and warehouses because they can pick up, carry and set down a coil of steel faster and safer than any other method. Infinite jaw openings permit handling a very wide range of coil widths . . . carrying legs open fast, stay open until operator closes them on coil. Narrow legs require minimum space between piles — a space saving advantage. Made in motorized models for crane cab or pendant operation as well as manual types with chain wheel, in capacities from 3 tons up. Powered Rotating Heads available. Opening ranges to suit your requirements. Write for illustrated Bulletin.



CULLEN-FRIESTEDT CO.

1308 South Kilbourn Avenue • Chicago 23, Illinois

Price Indexes and Composites



Nov. 26, 1957	Week Ago	Month Ago	Nov. Avg.	Year Ago
181.7	181.7	181.7	181.7	168.8

AVERAGE PRICES OF STEEL (Bureau of Labor Statistics)

Week Ended Nov. 26

Prices include mill base prices and typical extras and deductions. Units are 100 lb except where otherwise noted in parentheses. For complete description of the following products and extras and deductions applicable to them, write to STEEL.

Rails, Standard No. 1	$5.600	Bars, Reinforcing	6.210
Rails, Light, 40 lb	7.067	Bars, C.F., Carbon	10.360
Tie Plates	6.600	Bars, C.F., Alloy	13.875
Axles, Railway	9.825	Bars, C.F., Stainless, 302 (lb)	0.553
Wheels, Freight Car, 33 in. (per wheel)	60.000	Sheets, H.R., Carbon	6.192
Plates, Carbon	6.150	Sheets, C.R., Carbon	7.089
Structural Shapes	5.942	Sheets, Galvanized	8.220
Bars, Tool Steel, Carbon (lb)	0.535	Sheets, C.R., Stainless, 302 (lb)	0.688
Bars, Tool Steel, Alloy, Oil Hardening Die (lb)	0.650	Sheets, Electrical	12.025
Bars, Tool Steel, H.R., Alloy, High Speed, W 6.75, Cr 4.5, V 2.1, Mo 5.5, C 0.60 (lb)	1.355	Strip, C.R., Carbon	9.243
Bars, Tool Steel, H.R., Alloy, High Speed, W18, Cr 4, V 1 (lb)	1.850	Strip, C.R., Stainless, 430 (lb)	0.493
Bars, H.R., Alloy	10.525	Strip, H.R., Carbon	6.245
Bars, H.R., Stainless, 303 (lb)	0.525	Pipe, Black, Buttweld (100 ft)	19.814
Bars, H.R., Carbon	6.425	Pipe, Galv., Buttweld (100 ft)	23.264
		Pipe, Line (100 ft)	199.023
		Casing, Oil Well, Carbon (100 ft)	194.499
		Casing, Oil Well, Alloy (100 ft)	304.610
		Tubes, Boiler (100 ft)	49.130
		Tubing, Mechanical, Carbon (100 ft)	24.953
		Tubing, Mechanical, Stainless, 304 (100 ft)	205.608
		Tin Plate, Hot-dipped, 1.25 lb (95 lb base box)	9.783
		Tin Plate, Electrolytic, 0.25 lb (95 lb base box)	8.483
		Black Plate, Canmaking Quality (95 lb base box)	7.583
		Wire, Drawn, Carbon	10.225
		Wire, Drawn, Stainless, 430 (lb)	0.653
		Bale Ties (bundles)	7.967
		Nails, Wire, 8d Common	9.828
		Wire, Barbed (80-rod spool)	8.719
		Woven Wire Fence (20-rod roll)	21.737

STEEL's FINISHED STEEL PRICE INDEX*

	Nov. 27 1957	Week Ago	Month Ago	Year Ago	5 Yr Ago
Index (1935-39 avg=100)	239.15	239.15	239.15	225.92	181.31
Index in cents per lb	6.479	6.479	6.479	6.111	4.912

STEEL's ARITHMETICAL PRICE COMPOSITES*

Finished Steel, NT	$146.03	$146.03	$146.03	$137.66	$110.98
No. 2 Fdry Pig Iron, GT	66.49	66.49	66.49	62.63	55.04
Basic Pig Iron, GT	65.99	65.99	65.99	62.18	54.66
Malleable Pig Iron, GT	67.27	67.27	67.27	63.41	55.77
Steelmaking Scrap, GT	33.00	33.17	35.33	64.67	43.00

*For explanation of weighted index see STEEL, Sept. 19, 1949, p. 54; of arithmetical price composite, STEEL, Sept. 1, 1952, p. 130.

Comparison of Prices

Comparative prices by districts, in cents per pound except as otherwise noted. Delivered prices based on nearest production point.

FINISHED STEEL	Nov. 27 1957	Week Ago	Month Ago	Year Ago	5 Yr Ago
Bars, H.R., Pittsburgh	5.425	5.425	5.425	5.075	3.95
Bars, H.R., Chicago	5.425	5.425	5.425	5.075	3.95
Bars, H.R., deld., Philadelphia	5.725	5.725	5.725	5.35	4.502
Bars, C.F., Pittsburgh	7.30*	7.30*	7.30*	6.85*	4.925
Shapes, Std., Pittsburgh	5.275	5.275	5.275	5.00	3.85
Shapes, Std., Chicago	5.275	5.275	5.275	5.00	3.85
Shapes, deld., Philadelphia	5.545	5.545	5.545	5.40	4.13
Plates, Pittsburgh	5.10	5.10	5.10	4.85	3.90
Plates, Chicago	5.10	5.10	5.10	4.85	3.90
Plates, Coatesville, Pa.	5.10	5.10	5.10	5.25	4.35
Plates, Sparrows Point, Md.	5.10	5.10	5.10	4.85	3.90
Plates, Claymont, Del.	5.70	5.70	5.70	5.35	4.35
Sheets, H.R., Pittsburgh	4.925	4.925	4.925	4.675	3.775
Sheets, H.R., Chicago	4.925	4.925	4.925	4.675	3.775
Sheets, C.R., Pittsburgh	6.05	6.05	6.05	5.75	4.575
Sheets, C.R., Chicago	6.05	6.05	6.05	5.75	4.575
Sheets, C.R., Detroit	6.05-6.15	6.05-6.15	6.05-6.15	5.75-5.85	4.775
Sheets, Galv., Pittsburgh	6.60	6.60	6.60	6.30	5.075
Strip, H.R., Pittsburgh	4.925	4.925	4.925	4.675	3.75-4.225
Strip, H.R., Chicago	4.925	4.925	4.925	4.675	3.725
Strip, C.R., Pittsburgh	7.15	7.15	7.15	6.85	5.10-5.80
Strip, C.R., Chicago	7.15	7.15	7.15	6.85	5.35
Strip, C.R., Detroit	7.25	7.25	7.25	6.95	5.30-6.05
Wire, Basic, Pittsburgh	7.65	7.65	7.65	7.20	5.10-5.225
Nails, Wire, Pittsburgh	8.95	8.95	8.95	8.20	6.20-6.35
Tin plate (1.50 lb) box, Pitts.	$10.30	$10.30	$10.30	$9.95	$8.95

*Including 0.35c for special quality.

SEMIFINISHED STEEL

Billets, forging, Pitts. (NT)	$96.00	$96.00	$96.00	$91.50	$70.50
Wire rods, 7/32-5/8" Pitts.	6.15	6.15	6.15	5.80	4.425

PIG IRON, Gross Ton	Nov. 27 1957	Week Ago	Month Ago	Year Ago	5 Yr Ago
Bessemer, Pitts.	$67.00	$67.00	$67.00	$63.50	$55.50
Basic, Valley	66.00	66.00	66.00	62.50	54.50
Basic, deld., Phila.	70.01	70.01	70.01	66.26	59.25
No. 2 Fdry, Neville Island, Pa.	66.50	66.50	66.50	63.00	55.00
No. 2 Fdry, Chicago	66.50	66.50	66.50	63.00	55.00
No. 2 Fdry, deld., Phila.	70.51	70.51	70.51	66.76	59.75
No. 2 Fdry, Birm.	62.50	62.50	62.50	59.00	51.38
No. 2 Fdry (Birm.) deld. Cin.	70.20	70.20	70.20	66.70	58.93
Malleable, Valley	66.50	66.50	66.50	63.00	55.00
Malleable, Chicago	66.50	66.50	66.50	63.00	55.00
Ferromanganese, Duquesne	245.00†	245.00†	245.00†	235.00†	228.00*

†74-76% Mn, net ton. *75-82% Mn, gross ton, Etna, Pa.

SCRAP, Gross Ton (Including broker's commission)

No. 1 Heavy Melt, Pittsburgh	$33.50	$33.50	$35.50	$66.50	$44.00
No. 1 Heavy Melt, E. Pa.	33.50	33.50	36.50	62.50	41.50
No. 1 Heavy Melt, Chicago	32.00	32.50	34.00	65.00	42.50
No. 1 Heavy Melt, Valley	31.50	31.50	33.50	66.50	44.00
No. 1 Heavy Melt, Cleve.	28.50	28.50	30.50	65.00	43.00
No. 1 Heavy Melt, Buffalo	32.50	32.50	36.50	59.50	43.00
Rails, Rerolling, Chicago	48.00	48.50	49.50	89.00	52.50
No. 1 Cast, Chicago	35.50	35.50	35.50	50.50	50.00

COKE, Net Ton

Beehive, Furn., Connlsvl.	$15.25	$15.25	$15.25	$14.50	$14.75
Beehive, Fdry., Connlsvl.	18.25	18.25	18.25	17.50	17.00

4 OF THESE ECONOMICAL CLEVELAND PRESSES

newly installed— now on FULL TIME production of 1958 automobile parts!

One of the leading automobile manufacturers recently added *four* of these Cleveland Single Crank Presses to boost production of parts for their 1958 line of cars.

Designed for uninterrupted production with every important cost-reducing and safety feature, these new 350-ton-capacity presses have a stroke of 3″, a shut height of 22″, a bed area of 42 x 42″, and operate at 60 rpm.

If production and economy are your problem, let us send you complete details on the improved performance of Cleveland Presses. You have eleven different types of presses to choose from, each of which can be furnished in a wide range of sizes and capacities to suit your particular requirements.



THE CLEVELAND PUNCH & SHEAR WORKS CO. U.S.A.
Established 1880

Power Presses
Fabricating Tools
Punching Tools & Dies

E. 40th and St. Clair Avenue, Cleveland 14, Ohio

Offices: NEW YORK, DETROIT, CHICAGO, PHILADELPHIA, EAST LANSING, CINCINNATI

AA-6535

Steel Prices

Mill prices as reported to STEEL, Nov. 27, cents per pound except as otherwise noted. *Changes shown in italics.* Code numbers following mill points indicate producing company. Key to producers, page 148; to footnotes, page 150.

SEMIFINISHED

INGOTS, Carbon, Forging (NT)
Munhall,Pa. U5 ....$73.50

INGOTS, Alloy (NT)
Detroit S41 .....$77.00
Farrell, Pa. S3 .....77.00
Lowellville,O. S3 .....77.00
Midland,Pa. C18 .....77.00
Munhall,Pa. U5 .....77.00
Sharon,Pa. S3 .....77.00

BILLETS, BLOOMS & SLABS
Carbon, Rerolling (NT)
Bessemer,Pa. U5 ....$77.50
Bridgeport,Conn. C32 ..80.50
Buffalo R2 .....77.50
Clairton,Pa. U5 .....77.50
Ensley,Ala. T2 .....77.50
Fairfield,Ala. T2 ....77.50
Fontana,Calif. K1 ....88.00
Gary,Ind. U5 .....77.50
Johnstown,Pa. B2 ....77.50
Lackawanna,N.Y. B2...77.50
Munhall,Pa. U5 .....77.50
S.Chicago,Ill. R2, U5..77.50
S.Duquesne,Pa. U5 ....77.50
Sterling,Ill. N15 .....77.50
Youngstown R2 .....77.50

Carbon, Forging (NT)
Bessemer,Pa. U5 ....$96.00
Bridgeport,Conn. C32..101.00
Buffalo R2 .....96.00
Canton,O. R2 .....98.50
Clairton,Pa. U5 .....96.00
Conshohocken,Pa. A3.101.00
Ensley,Ala. T2 .....96.00
Fairfield,Ala. T2 ....96.00
Fontana,Calif. K1 ...105.50
Gary,Ind. U5 .....96.00
Geneva,Utah C11 ....96.00
Houston S5 .....101.00
Johnstown,Pa. B2 ....96.00
Lackawanna,N.Y. B2...96.00
LosAngeles B3 .....105.50
Midland,Pa. C18 .....96.00
Munhall,Pa. U5 .....96.00
Seattle B3 .....109.50
Sharon,Pa. S3 .....96.00
S.Chicago R2, U5, W14..96.00
S.Duquesne,Pa. U5 ...96.00
S.SanFrancisco B3 ...105.50
Warren,O. C17 .....96.00

Alloy, Forging (NT)
Bethlehem,Pa. B2 ..$114.00
Bridgeport,Conn. C32..114.00
Buffalo R2 .....114.00
Canton,O. R2, T7 ....114.00
Conshohocken,Pa. A3..121.00
Detroit S41 .....114.00
Economy,Pa. B14 ....114.00
Farrell,Pa. S3 .....114.00
Fontana,Calif. K1 ....135.00
Gary,Ind. U5 .....114.00
Houston S5 .....119.00
Ind.Harbor, Ind. Y1 ..114.00
Johnstown,Pa. B2 ...114.00
Lackawanna,N.Y. B2.114.00
Los Angeles B3 .....134.00
Lowellville,O. S3 ....114.00
Massillon,O. R2 .....114.00
Midland,Pa. C18 .....114.00
Munhall,Pa. U5 .....114.00
Sharon,Pa. S3 .....114.00
S.Chicago R2, U5, W14.114.00
S.Duquesne,Pa. U5 ...114.00
Struthers,O. Y1 .....114.00
Warren,O. C17 .....114.00

ROUNDS, SEAMLESS TUBE (NT)
Bridgeport,Conn. C32.$122.50
Buffalo R2 .....117.50
Canton,O. R2 .....120.00
Cleveland R2 .....117.50
Gary,Ind. U5 .....117.50
S.Chicago,Ill. R2, W14 117.50
S.Duquesne,Pa. U5 ...117.50
Warren,O. C17 .....117.50

SKELP
Aliquippa,Pa. J5 .....5.075
Munhall,Pa. U5 .....4.875
Warren,O. R2 .....4.875
Youngstown R2, U5 ..4.875

WIRE RODS
AlabamaCity,Ala. R2 ..6.15
Aliquippa,Pa. J5 .....6.15
Alton,Ill. L1 .....6.35
Buffalo W12 .....6.15
Cleveland A7 .....6.15
Donora,Pa. A7 .....6.15
Fairfield,Ala. T2 .....6.15
Houston S5 .....6.40
IndianaHarbor,Ind. Y1..6.15
Johnstown,Pa. B2 .....6.15
Joliet,Ill. A7 .....6.15
KansasCity,Mo. S5 ....6.40
Kokomo,Ind. C16 .....6.25
LosAngeles B3 .....6.95
Minnequa,Colo. C10 ....6.40
Monessen,Pa. P17 ....6.15
N.Tonawanda,N.Y. B11..6.15
Pittsburg,Calif. C11 ....6.95
Portsmouth,O. P12 ....6.15
Roebling,N.J. R5 .....6.25
S.Chicago,Ill. R2 .....6.15
SparrowsPoint,Md. B2 ..6.25
Sterling,Ill. (1) N15 ....6.15
Sterling,Ill. N15 .....6.25
Struthers,O. Y1 .....6.15
Worcester,Mass. A7 ....6.45

STRUCTURALS

Carbon Steel Std. Shapes
Ala.City,Ala. R2 ....5.275
Atlanta A11 .....5.475
Aliquippa,Pa. J5 .....5.275
Bessemer,Ala. T2 .....5.275
Bethlehem,Pa. B2 ....5.325
Birmingham C15 .....5.275
Clairton,Pa. U5 .....5.275
Fairfield,Ala. T2 .....5.275
Fontana,Calif. K1 ....6.075
Gary,Ind. U5 .....5.275
Geneva,Utah C11 .....5.275
Houston S5 .....5.375
Ind.Harbor,Ind. I-2 ...5.275
Johnstown,Pa. B2 ....5.325
Joliet,Ill. P22 .....5.275
KansasCity,Mo. S5 ....5.375
Lackawanna,N.Y. B2..5.325
LosAngeles B3 .....5.975
Minnequa,Colo. C10 ...5.575
Munhall,Pa. U5 .....5.275
Niles,Calif. P1 .....5.925
Phoenixville,Pa. P4 ...5.325
Portland,Oreg. O4 ....6.025
Seattle B3 .....6.025
S.Chicago,Ill. U5, W14.5.275
S.SanFrancisco B3 ....5.925
Sterling,Ill. N15 .....5.275
Torrance,Calif. C11 ..5.975
Weirton,W.Va. W6 ....5.275

Wide Flange
Bethlehem,Pa. B2 ....5.325
Clairton,Pa. U5 .....5.275
Fontana,Calif. K1 ....6.225
IndianaHarbor,Ind. I-2.5.275
Lackawanna,N.Y. B2 ..5.325
Munhall,Pa. U5 .....5.275
Phoenixville,Pa. P4 ...5.325
S.Chicago,Ill. U5 .....5.275

Alloy Std. Shapes
Aliquippa,Pa. J5 .....6.55
Clairton,Pa. U5 .....6.55
Gary,Ind. U5 .....6.55
Houston S5 .....6.65
KansasCity, Mo. S5 ....6.65
Munhall,Pa. U5 .....6.55
S.Chicago,Ill. U5 .....6.55

H.S., L.A. Std. Shapes
Aliquippa,Pa. J5 .....7.75
Bessemer,Ala. T2 .....7.75
Bethlehem,Pa. B2 .....7.80
Clairton,Pa. U5 .....7.75
Fairfield,Ala. T2 .....7.75
Fontana,Calif. K1 .....8.55
Gary,Ind. U5 .....7.75
Geneva,Utah C11 .....7.75
Houston S5 .....7.85
Ind.Harbor,Ind. I-2, Y1 7.75
Johnstown,Pa. B2 .....7.80
KansasCity,Mo. S5 ....7.85
Lackawanna,N.Y. B2 ..7.80
LosAngeles B3 .....8.45
Munhall,Pa. U5 .....7.75
Seattle B3 .....8.50
S.Chicago,Ill. U5, W14..7.75
S.SanFrancisco B3 .....8.40
Struthers,O. Y1 .....7.75

H.S., L.A. Wide Flange
Bethlehem,Pa. B2 .....7.80
Lackawanna,N.Y. B2 ..7.80
Munhall,Pa. U5 .....7.75
S.Chicago,Ill. U5 .....7.75

PILING

BEARING PILES
Bethlehem,Pa. B2 ....5.325
Lackawanna,N.Y. B2..5.325
Munhall,Pa. U5 .....5.275
S.Chicago,Ill. U5 .....5.275

STEEL SHEET PILING
Lackawanna,N.Y. B2 ..6.225
Munhall,Pa. U5 .....6.225
S.Chicago,Ill. U5 .....6.225
Weirton,W.Va. W6 ....6.225

PLATES

PLATES, Carbon Steel
Ala.City, Ala. R2 .....5.10
Aliquippa,Pa. J5 .....5.10
Ashland,Ky. (15) A10..5.10
Bessemer,Ala. T2 .....5.10
Clairton,Pa. U5 .....5.10
Claymont,Del. C22 .....5.10
Cleveland J5, R2 .....5.20
Coatesville,Pa. L7 .....5.10
Conshohocken,Pa. A3 ..5.20
Ecorse,Mich. G5 .....5.20
Fairfield,Ala. T2 .....5.10
Fontana,Calif.(30) K1 ..5.90
Gary,Ind. U5 .....5.10
Geneva,Utah C11 .....5.10
GraniteCity,Ill. G4 .....5.30
Harrisburg,Pa. P4 ....5.80
Houston S5 .....5.20
Ind.Harbor,Ind. I-2, Y1.5.10
Johnstown, Pa. B2 .....5.10
Lackawanna,N.Y. B2 ..5.10
LoneStar,Tex. L6 .....5.45
Mansfield,O. E6 .....5.10
Minnequa,Colo. C10 ....5.95
Munhall,Pa. U5 .....5.10
Newport,Ky. A2 .....5.10
Pittsburgh J5 .....5.10
Riverdale,Ill. A1 .....5.10
Seattle B3 .....6.00
Sharon,Pa. S3 .....5.10
S.Chicago,Ill. U5, W14 5.10
SparrowsPoint,Md. B2 ..5.10
Sterling,Ill. N15 .....5.10
Steubenville,O. W10 ....5.10
Warren,O. R2 .....5.10
Youngstown R2, U5, Y1.5.10

PLATES, Carbon Abras. Resist.
Claymont,Del. C22 .....6.75
Fontana,Calif. K1 .....7.55
Geneva,Utah C11 .....6.75
Houston S5 .....6.85
Johnstown,Pa. B2 .....6.75
SparrowsPoint,Md. B2 ..6.75

PLATES, Wrought Iron
Economy,Pa. B14 .....13.15

PLATES, H.S., L.A.
Aliquippa,Pa. J5 .....7.625
Bessemer,Ala. T2 .....7.625
Clairton,Pa. U5 .....7.625
Claymont,Del. C22 ....7.625
Cleveland J5, R2 .....7.625
Coatesville,Pa. L7 ....7.925
Conshohocken,Pa. A3 ..7.625
Economy,Pa. B14 ....7.625
Ecorse,Mich. G5 .....7.725
Fairfield,Ala. T2 .....7.625
Farrell,Pa. S3 .....7.625
Fontana,Calif.(30) K1 .8.425
Gary,Ind. U5 .....7.625
Geneva,Utah C11 .....7.625
Houston S5 .....7.725
Ind.Harbor,Ind. I-2, Y1 7.625
Johnstown,Pa. B2 .....7.625
Munhall,Pa. U5 .....7.625
Pittsburgh J5 .....7.625
Seattle B3 .....8.525
Sharon,Pa. S3 .....7.625
S.Chicago,Ill. U5, W14 7.625
SparrowsPoint,Md. B2..7.625
Warren,O. R2 .....7.625
Youngstown U5 .....7.625

PLATES, ALLOY
Aliquippa,Pa. J5 .....7.20
Claymont,Del. C22 .....7.20
Coatesville,Pa. L7 .....7.20
Economy,Pa. B14 .....7.20
Farrell,Pa. S3 .....7.20
Fontana,Calif.(30) K1 ..8.00
Gary,Ind. U5 .....7.20
Houston S5 .....7.30
Ind.Harbor,Ind. Y1 ....7.20
Johnstown,Pa. B2 .....7.20
Lowellville,O. S3 .....7.20
Munhall,Pa. U5 .....7.20
Newport,Ky. A2 .....7.20
Pittsburgh J5 .....7.20
Seattle B3 .....8.10
Sharon,Pa. S3 .....7.20
S.Chicago,Ill. U5, W14..7.20
SparrowsPoint,Md. B2 ..7.20
Youngstown Y1 .....7.20

FLOOR PLATES
Cleveland J5 .....6.175
Conshohocken,Pa. A3 ..6.175
Ind.Harbor,Ind. I-2 ...6.175
Munhall,Pa. U5 .....6.175
S.Chicago,Ill. U5 .....6.175

PLATES, Ingot Iron
Ashland c.l. (15) A10..5.35
Ashland l.c.l. (15) A10..5.85
Cleveland c.l. R2 .....5.85
Warren,O. c.l. R2 .....5.85

BARS

BARS, Hot-Rolled Carbon (Merchant Quality)
Ala.City,Ala.(9) R2 ..5.425
Aliquippa,Pa.(9) J5 ...5.425
Alton,Ill. L1 .....5.625
Atlanta(9) A11 .....5.625
Bessemer,Ala.(9) T2 ..5.425
Birmingham(9) C15 ..5.425
Bridgeport,Conn.(9) C32.5.65
Buffalo(9) R2 .....5.425
Clairton,Pa. (9) U5 ....5.425
Cleveland(9) R2 .....5.425
Ecorse,Mich.(9) G5....5.525
Emeryville,Calif. J7 ..6.175
Fairfield,Ala(9) T2 ..5.425
Fairless,Pa. (9) U5 ..5.575
Fontana,Calif.(9) K1 ..6.125
Gary,Ind.(9) U5 .....5.425
Houston (9) S5 .....5.675
Ind.Harbor(9) I-2, Y1 5.425
Johnstown,Pa.(9) B2 ..5.425
Joliet,Ill. P22 .....5.425
KansasCity,Mo.(9) S5..5.675
Lackawanna(9) B2 ....5.425
LosAngeles(9) B3 ....6.125
Milton,Pa. M18 .....5.575
Minnequa,Colo. C10 ..5.875
Niles,Calif. P1 .....6.125
N.T'wanda,N.Y.(46)B11 5.775
Pittsburg,Calif.(9) C11.6.125
Pittsburgh(9) J5 .....5.425
Portland,Oreg. O4 ....6.175
Seattle B3, N14 .....6.175
S.Ch'c'go(9)R2,U5,W14 5.425
S.Duquesne,Pa.(9) U5..5.425
S.SanFran.,Calif.(9)B3 6.175
Sterling,Ill.(1)(9) N15..5.425
Sterling,Ill.(9) N15 ....5.525
Struthers,O. Y1 .....5.425
Tonawanda,N.Y. B12 ..5.425
Torrance,Calif.(9) C11.6.125
Youngstown(9) R2, U5.5.425

BARS, H.R. Leaded Alloy
(Including leaded extra)
Warren,O. C17 .....7.475

BARS, Hot-Rolled Alloy
Aliquippa,Pa. J5 .....6.475
Bethlehem,Pa. B2 ....6.475
Bridgeport,Conn. C32 ..6.55
Buffalo R2 .....6.475
Canton,O. R2, T7 ....6.475
Clairton,Pa. U5 .....6.475
Detroit S41 .....6.475
Economy,Pa. B14 ....6.475
Ecorse,Mich. G5 .....6.575
Fairless,Pa. U5 .....6.625
Farrell,Pa. S3 .....6.475
Fontana,Calif. K1 ....7.525
Gary,Ind. U5 .....6.475
Houston S5 .....6.725
Ind.Harbor,Ind. I-2, Y1 6.475
Johnstown,Pa. B2 ....6.475
KansasCity,Mo. S5 ....6.725
Lackawanna,N.Y. B2 ..6.475
Lowellville,O. S3 .....6.475
LosAngeles B3 .....7.525
Massillon,O. R2 .....6.475
Midland,Pa. C18 .....6.475
Pittsburgh J5 .....6.475
Sharon,Pa. S3 .....6.475
S.Chicago R2, U5, W14 6.475
S.Duquesne,Pa. U5 ....6.475
Struthers,O. Y1 .....6.475
Warren,O. C17 .....6.475
Youngstown U5 .....6.475

BARS & SMALL SHAPES, H.R. High-Strength, Low-Alloy
Aliquippa,Pa. J5 .....7.925
Bessemer,Ala. T2 .....7.925
Bethlehem,Pa. B2 .....7.925
Bridgeport,Conn. C32 ..7.95
Clairton,Pa. U5 .....7.925
Cleveland R2 .....7.925
Ecorse,Mich. G5 .....8.025
Fairfield,Ala. T2 .....7.925
Fontana,Calif. K1 ....8.625
Gary,Ind. U5 .....7.925
Houston S5 .....8.175
Ind.Harbor,Ind. Y1 ...7.925
Johnstown,Pa. B2 ....7.925
KansasCity,Mo. S5 ....8.175
Lackawanna,N.Y. B2..7.925
LosAngeles B3 .....8.625
Pittsburgh J5 .....7.925
Seattle B3 .....8.675
S.Chicago,Ill. U5, W14 7.925
S.Duquesne,Pa. U5 ....7.925
S.San Francisco B3 ...8.675
Struthers,O. Y1 .....7.925
Youngstown U5 .....7.925

BAR SIZE ANGLES; H.R. Carbon
Bethlehem,Pa.(9) B2 ..5.575
Houston(9) S5 .....5.675
KansasCity,Mo.(9) S5..5.675
Lackawanna(9) B2 ...5.425
Sterling,Ill. N15 .....5.525
Sterling,Ill.(1) N15 ...5.425
Tonawanda,N.Y. B12 ..5.425

BAR SIZE ANGLES; S. Shapes
Aliquippa,Pa. J5 .....5.425
Atlanta A11 .....5.625
Joliet,Ill. P22 .....5.425
Niles,Calif. P1 .....6.125
Pittsburgh J5 .....5.425
Portland,Oreg. O4 ....6.175
SanFrancisco S7 .....6.275
Seattle B3 .....6.175

BAR SHAPES, Hot-Rolled Alloy
Aliquippa,Pa. J5 .....6.55
Clairton,Pa. U5 .....6.55
Gary,Ind. U5 .....6.55
Houston S5 .....6.80
KansasCity,Mo. S5 ....6.80
Pittsburgh J5 .....6.55
Youngstown U5 .....6.55

BARS, C.F., Leaded Alloy (Including leaded extra)
Ambridge,Pa. W18 ...9.925
BeaverFalls,Pa. M12 ..9.925
Camden,N.J. P13 ....10.10
Chicago W18 .....9.925
Cleveland C20 .....9.925
Elyria,O. W8 .....9.925
LosAngeles P2, S30
(Grade A) 11.30
(Grade B) 11.80
Monaca,Pa. S17 .....9.925
Newark,N.J. W18 ....10.10
SpringCity,Pa. K3 ....10.10
Warren,O. C17 .....9.925

BARS, Cold-Finished Carbon
Ambridge,Pa. W18 .....7.30
BeaverFalls,Pa. M12,R2 7.30
Birmingham C15 .....7.90
Bridgeport,Conn. C32 ..7.65
Buffalo B5 .....7.35
Camden,N.J. P13 .....7.75
Carnegie,Pa. C12 .....7.30
Chicago W18 .....7.30
Cleveland A7, C20 ....7.30
Detroit B5, P17 .....7.50
Detroit S41 .....7.30
Donora,Pa. A7 .....7.30
Elyria,O. W8 .....7.30
FranklinPark,Ill. N5 ...7.30
Gary,Ind. R2 .....7.30
GreenBay,Wis. F7 .....7.30
Hammond,Ind. J5, L2 ..7.30
Hartford,Conn. R2 .....7.80
Harvey,Ill. B5 .....7.30
LosAngeles (49), S30 ..8.75
LosAngeles P2, R2 ...8.75
Mansfield,Mass. B5 ....7.85
Massillon,O. R2, R8 ....7.30
Midland,Pa. C18 .....7.30
Monaca,Pa. S17 .....7.30
Newark,N.J. W18 .....7.75
NewCastle,Pa.(17) B4 ..7.30
Pittsburgh J5 .....7.30
Plymouth,Mich. P5 ....7.55
Putnam,Conn. W18 ....7.85
Readville,Mass. C14 ....7.85
S.Chicago,Ill. W14 .....7.30
SpringCity,Pa. K3 .....7.75
Struthers,O. Y1 .....7.30
Warren,O. C17 .....7.30
Willimantic,Conn. J5 ..7.80
Waukegan,Ill. A7 .....7.30
Youngstown F3, Y1 ....7.30

BARS, Cold-Finished Carbon (Turned and Ground)
Cumberland,Md.(5) C19.6.55

BARS, Cold-Finished Alloy
Ambridge,Pa. W18 ....8.775
BeaverFalls,Pa.M12,R2 8.775
Bethlehem,Pa. B2 .....8.775
Bridgeport,Conn. C32 ..8.925
Buffalo B5 .....8.775
Camden,N.J. P13 .....8.95
Canton,O. T7 .....8.775
Carnegie,Pa. C12 .....8.775
Chicago W18 .....8.775
Cleveland A7, C20 ....8.775
Detroit B5, P17 .....8.975
Detroit S41 .....8.775
Donora,Pa. A7 .....8.775
Elyria,O. W8 .....8.775
FranklinPark,Ill. N5 ..8.775
Gary,Ind. R2 .....8.775
GreenBay,Wis. F7 .....8.775
Hammond,Ind. J5, L2..8.775
Hartford,Conn. R2 ....9.075
Harvey,Ill. B5 .....8.775
Lackawanna,N.Y. B2 ..8.775
LosAngeles P2 .....10.65
LosAngeles S30 .....10.75
Mansfield,Mass. B5 ....9.075
Massillon,O. R2, R8 ..8.775
Midland,Pa. C18 .....8.775
Monaca,Pa. S17 .....8.775
Newark,N.J. W18 .....8.95
Plymouth,Mich. P5 ....8.975
S.Chicago,Ill. W14 ....8.775
SpringCity,Pa. K3 ....8.95
Struthers,O. Y1 .....8.775
Warren,O. C17 .....8.775
Waukegan,Ill. A7 .....8.775
Worcester,Mass. A7 ....9.075
Youngstown F3, Y1 ..8.775

BARS, Reinforcing (To Fabricators)

Ala.City,Ala. R2 ....5.425
Atlanta A11 .....5.625
Birmingham C15, S42 .5.425
Bridgeport,Conn. C32 ..5.65
Buffalo R2 .....5.425
Cleveland R2 .....5.425
Ecorse,Mich. G5 .....5.775
Emeryville,Calif. J7 ..6.175
Fairfield,Ala. T2 ....5.425
Fairless,Pa. U5 .....5.575
Fontana,Calif. K1 ....6.125
Ft.Worth,Tex.(4)(26)T4 5.875
Gary,Ind. U5 .....5.425
Houston S5 .....5.675
Ind.Harbor,Ind. I-2,Y1 5.425
Johnstown,Pa. B2 ....5.425
Joliet,Ill. P22 .....5.425
KansasCity,Mo. S5 ...5.675
Lackawanna,N.Y. B2..5.425
LosAngeles B3 .....6.125
Milton,Pa. M18 .....5.575
Minnequa,Colo. C10 ..5.875
Niles,Calif. P1 .....6.125
Pittsburg,Calif. C11 ..6.125
Pittsburgh J5 .....5.425
Portland,Oreg. O4 ....6.175
SandSprings,Okla. S5 ..5.925
Seattle B3, N14 .....6.175
S.Chicago,Ill. R2 .....5.425
S.Duquesne,Pa. U5 ....5.425
S.SanFrancisco B3 ....6.175
SparrowsPoint,Md. B2.5.425
Sterling,Ill.(1) N15 ..5.425
Sterling,Ill. N15 .....5.525
Struthers,O. Y1 .....5.425
Tonawanda,N.Y. B12 ..6.00
Torrance,Calif. C11....6.125
Youngstown R2, U5 ..5.425

BARS, Reinforcing (Fabricated; to Consumers)

Boston B2 .....7.65
Chicago U8 .....6.91
Cleveland U8 .....6.89
Johnstown,Pa. B2 ....7.08
KansasCity,Mo. S5 ....7.35
Lackawanna,N.Y. B2 ..6.85
Marion,O. P11 .....6.70
Newark,N.J. U8 .....7.55
Philadelphia U8 .....7.38
Pittsburgh J5, U8 ....7.10
Seattle B3, N14 .....7.70
SparrowsPt.,Md. B2 ....7.08
St.Paul U8 .....7.92
Williamsport,Pa. S19 ..7.00

BARS, Wrought Iron

Economy,Pa.(S.R.)B14 14.45
Economy,Pa.(D.R.)B14 18.00
Economy,(Staybolt)B14 18.45

RAIL STEEL BARS

ChicagoHts.(3) C2, I-2.5.325
ChicagoHts.(4)(44) I-2,..5.425
ChicagoHts.(4) C2 ....5.425
Ft.Worth,Tex.(26) T4..5.875
Franklin,Pa. (3) F5 ..5.325
Franklin,Pa. (4) F5 ..5.425
JerseyShore,Pa.(3) J8 ..5.30
Marion,O.(3) P11 ....5.325
Tonawanda(3) R12 ...5.325
Tonawanda(4) B12 ....6.00
Williamsport,Pa. (3)S19 5.50

SHEETS

SHEETS, Hot-Rolled Steel (18 Gage and Heavier)

Ala.City,Ala. R2 ....4.925
Allenport,Pa. P7 .....4.925
Ashland,Ky.(8) A10 ..4.925
Cleveland J5, R2 ....4.925
Conshohocken,Pa. A3 ..4.975
Detroit(8) M1 .....5.025
Ecorse,Mich. G5 .....5.025
Fairfield,Ala. T2 ....4.925
Fairless,Pa. U5 .....4.975
Fontana,Calif. K1 ....5.825
Gary,Ind. U5 .....4.925
Geneva,Utah C11 ....5.025
GraniteCity,Ill.(8) G4..5.125
Ind.Harbor,Ind. I-2, Y1 4.925
Irvin,Pa. U5 .....4.925
Lackawanna,N.Y. B2 .4.925
Mansfield,O. E6 .....4.925
Munhall,Pa. U5 .....4.925
Newport,Ky.(8) A2 ..4.925
Niles,O. M21, S3 .....4.925
Pittsburg,Calif. C11 ..5.625
Pittsburgh J5 .....4.925
Portsmouth,O. P12 ....4.925
Riverdale,Ill. A1 ....4.925
Sharon,Pa. S3 .....4.925
S.Chicago,Ill. W14 ....4.925
SparrowsPoint,Md. B2 .4.925
Steubenville,O. W10 ..4.925
Warren,O. R2 .....4.925
Weirton,W.Va. W6 ..4.925
Youngstown U5, Y1 ..4.925

SHEETS, H.R.,(19 Ga. & Lighter)

Niles,O. M21 .....6.05

SHEETS, H.R. Alloy

Gary,Ind. U5 .....8.10
Ind.Harbor,Ind. Y1 ....8.10
Irvin,Pa. U5 .....8.10
Munhall,Pa. U5 .....8.10
Newport,Ky. A2 .....8.10
Youngstown U5, Y1 ...8.10

SHEETS, H.R.(14 Ga. & Heavier) High-Strength, Low-Alloy

Cleveland J5, R2 ....7.275
Conshohocken,Pa. A3..7.325
Ecorse,Mich. G5 .....7.375
Fairfield,Ala. T2 .....7.275
Fairless,Pa. U5 .....7.325
Farrell,Pa. S3 .....7.275
Fontana,Calif. K1 ....8.175
Gary,Ind. U5 .....7.275
Ind.Harbor,Ind. I-2, Y1 7.275
Irvin,Pa. U5 .....7.275
Lackawanna (35) B2 ..7.275
Munhall,Pa. U5 .....7.275
Pittsburgh J5 .....7.275
S.Chicago,Ill. U5, W14 7.275
Sharon,Pa. S3 .....7.275
SparrowsPoint(36) B2 .7.275
Warren,O. R2 .....7.275
Weirton,W.Va. W6 ...7.275
Youngstown U5, Y1 ..7.275

SHEETS, Hot-Rolled Ingot Iron (18 Gage and Heavier)

Ashland,Ky.(8) A10 ..5.175
Cleveland R2 .....5.675
Warren,O. R2 .....5.675

SHEETS, Cold-Rolled Ingot Iron

Cleveland R2 .....6.80
Middletown,O. A10 ....6.55
Warren,O. R2 .....6.80

SHEETS, Cold-Rolled Steel (Commercial Quality)

AlabamaCity,Ala. R2 ..6.05
Allenport,Pa. P7 .....6.05
Cleveland J5, R2 .....6.05
Conshohocken,Pa. A3 ..6.10
Detroit M1 .....6.05
Ecorse,Mich. G5 .....6.15
Fairfield,Ala. T2 .....6.05
Fairless,Pa. U5 .....6.10
Follansbee,W.Va. F4 ..6.05
Fontana,Calif. K1 ....7.30
Gary,Ind. U5 .....6.05
GraniteCity,Ill. G4 ....6.25
Ind.Harbor,Ind. I-2, Y1 6.05
Irvin,Pa. U5 .....6.05
Lackawanna,N.Y. B2 ..6.05
Mansfield,O. E6 .....6.05
Middletown,O. A10 ....6.05
Newport,Ky. A2 .....6.05
Pittsburg,Calif. C11 ...7.00
Pittsburgh J5 .....6.05
Portsmouth,O. P12 ....6.05
SparrowsPoint,Md. B2 ..6.05
Steubenville,O. W10 ...6.05
Warren,O. R2 .....6.05
Weirton,W.Va. W6 ....6.05
Yorkville,O. W10 .....6.05
Youngstown Y1 .....6.05

SHEETS, Cold-Rolled High-Strength, Low-Alloy

Cleveland J5, R2 ....8.975
Ecorse,Mich. G5 .....9.075
Fairless,Pa. U5 .....9.025
Fontana,Calif. K1....10.275
Gary,Ind. U5 .....8.975
IndianaHarbor,Ind. Y1 8.975
Irvin,Pa. U5 .....8.975
Lackawanna (37) B2 ..8.975
Pittsburgh J5 .....8.975
SparrowsPoint (38) B2 8.975
Warren,O. R2 .....8.975
Weirton,W.Va. W6 ....8.975
Youngstown Y1 .....8.975

SHEETS, Culvert

	Cu Steel	Cu Fe
Ashland,Ky. A10	.6.95	7.20
Canton,O. R2	....6.95	7.45
Fairfield T2	....6.95	7.20
Gary,Ind. U5	....6.95	7.20
GraniteCity,Ill. G4	7.15	...
Ind.Harbor I-2	..6.95	7.20
Irvin,Pa. U5	....6.95	7.20
Kokomo,Ind. C16	7.05	...
MartinsFry. W10	.6.95	7.20
Pitts.,Calif. C11	..7.70	...
Pittsburgh J5	....6.95	...
SparrowsPt. B2	..6.95	...

SHEETS, Culvert—Pure Iron

Ind.Harbor,Ind. I-2 .. 7.20

SHEETS, Galvanized Steel Hot-Dipped

Ala.City,Ala. R2 ....6.60‡
Ashland,Ky. A10 ....6.60†
Canton,O. R2 .....6.60‡
Dover,O. R1 .....6.60†
Fairfield,Ala. T2 ....6.60†
Gary,Ind. U5 .....6.60•
GraniteCity,Ill. G4 ....6.80•
Ind.Harbor,Ind. I-2 ...6.60†
Irvin,Pa. U5 .....6.60•
Kokomo,Ind. C16 ....6.70‡
MartinsFerry,O. W10 ..6.60•
Middletown,O. A10 ..6.60†
Pittsburg,Calif. C11 ...7.35•
Pittsburgh J5 .....6.60†
SparrowsPt.,Md. B2 ..6.60†
Warren,O. R2 .....6.60†
Weirton,W.Va. W6 ....6.60•

•Continuous and noncontinuous. †Continuous. ‡Noncontinuous.

SHEETS, Well Casing

Fontana,Calif. K1 ....7.32

SHEETS, Galvanized High-Strength, Low-Alloy

Irvin,Pa. U5 .....9.72
SparrowsPt.(39) B2 ..9.72

SHEETS, Galvannealed Steel

Canton,O. R2 .....7.0
Irvin,Pa. U5 .....7.0

SHEETS, Galvanized Ingot Iro (Hot-Dipped Continuous)

Ashland,Ky. A10 .....6.8
Middletown,O. A10 ....6.8

SHEETS, Electrogalvanized

Cleveland (28) R2 ...7.42
Niles,O. (28) R2 ....7.42
Weirton,W.Va. W6 ..7.27

SHEETS, Aluminum Coated

Butler,Pa. A10 (type 1).9.22
Butler,Pa. A10 (type 2).9.33

SHEETS, Enameling Iron

Ashland,Ky. A10 .....6.622
Cleveland R2 .....6.622
Gary,Ind. U5 .....6.622
GraniteCity,Ill. G4 ....6.822
Ind.Harbor,Ind. I-2,Y1 6.622
Irvin,Pa. U5 .....6.622
Middletown,O. A10 ....6.622
Niles,O. M21, S3 ....6.622
Youngstown Y1 .....6.622

BLUED STOCK, 29 Gage

Follansbee,W.Va. F4 ..8.65
Ind.Harbor,Ind. I-2 ..8.475
Yorkville,O. W10 ....8.475

SHEETS, Long Terne Steel (Commercial Quality)

BeechBottom,W.Va.W10 7.00
Gary,Ind. U5 .....7.00
Mansfield,O. E6 .....7.00
Middletown,O. A10 ....7.00
Niles,O. M21, S3 .....7.00
Warren,O. R2 .....7.00
Weirton,W.Va. W6 ....7.00

SHEETS, Long Terne, Ingot Iron

Middletown,O. A10 ....7.40

Key to Producers

A1 Acme Steel Co.
A2 Acme-Newport Steel Co.
A3 Alan Wood Steel Co.
A4 Allegheny Ludlum Steel
A5 Alloy Metal Wire Div., H. K. Porter Co. Inc.
A6 American Shim Steel Co.
A7 American Steel & Wire Div., U. S. Steel Corp.
A8 Anchor Drawn Steel Co.
A9 Angell Nail & Chaplet
A10 Armco Steel Corp.
A11 Atlantic Steel Co.

B1 Babcock & Wilcox Co.
B2 Bethlehem Steel Co.
B3 Beth. Pac. Coast Steel
B4 Blair Strip Steel Co.
B5 Bliss & Laughlin Inc.
B8 Braeburn Alloy Steel
B9 Brainard Steel Div., Sharon Steel Corp.
B10 E. & G. Brooke, Wickwire Spencer Steel Div., Colo. Fuel & Iron
B11 Buffalo Bolt Co., Div., Buffalo-Eclipse Corp.
B12 Buffalo Steel Corp.
B14 A. M. Byers Co.
B15 J. Bishop & Co.

C1 Calstrip Steel Corp.
C2 Calumet Steel Div., Borg-Warner Corp.
C4 Carpenter Steel Co.
C7 Cleve.Cold Rolling Mills
C9 Colonial Steel Co.
C10 Colorado Fuel & Iron
C11 Columbia-Geneva Steel
C12 Columbia Steel & Shaft.
C13 Columbia Tool Steel Co.
C14 Compressed Steel Shaft.
C15 Connors Steel Div., H. K. Porter Co. Inc.
C16 Continental Steel Corp.
C17 Copperweld Steel Co.
C18 Crucible Steel Co.
C19 Cumberland Steel Co.
C20 Cuyahoga Steel & Wire
C22 Claymont Plant, Wickwire Spencer Steel Div., Colo. Fuel & Iron
C23 Charter Wire Inc.
C24 G. O. Carlson Inc.
C32 Carpenter Steel of N.Eng.

D2 Detroit Steel Corp.
D3 Dearborn Div., Sharon Steel Corp.
D4 Disston Div., H. K. Porter Co. Inc.
D6 Driver-Harris Co.
D7 Dickson Weatherproof Nail Co.
D8 Damascus Tube Co.
D9 Wilbur B. Driver Co.

E1 EasternGas&FuelAssoc.
E2 Eastern Stainless Steel
E4 Electro Metallurgical Co.
E5 Elliott Bros. Steel Co.
E6 Empire Steel Corp.

F2 Firth Sterling Inc.
F3 Fitzsimmons Steel Co.
F4 Follansbee Steel Corp.
F5 Franklin Steel Div., Borg-Warner Corp.
F6 Fretz-Moon Tube Co.
F7 Ft. Howard Steel & Wire
F8 Ft. Wayne Metals Inc.

G4 Granite City Steel Co.
G5 Great Lakes Steel Corp.
G6 Greer Steel Co.
G8 Green River Steel Corp.

H1 Hanna Furnace Corp.
H7 Helical Tube Co.

I-1 Igoe Bros. Inc.
I-2 Inland Steel Co.
I-3 Interlake Iron Corp.
I-4 Ingersoll Steel Div., Borg-Warner Corp.
I-6 Ivins, E., Steel Tube
I-7 Indiana Steel & Wire Co.

J1 Jackson Iron & Steel Co.
J3 Jessop Steel Co.
J4 Johnson Steel & Wire Co.
J5 Jones & Laughlin Steel
J6 Joslyn Mfg. & Supply
J7 Judson Steel Corp.
J8 Jersey Shore Steel Co.

K1 Kaiser Steel Corp.
K2 Keokuk Electro-Metals
K3 Keystone Drawn Steel
K4 Keystone Steel & Wire
K7 Kenmore Metals Corp.

L1 Laclede Steel Co.
L2 LaSalle Steel Co.
L3 Latrobe Steel Co.
L6 Lone Star Steel Co.
L7 Lukens Steel Co.

M1 McLouth Steel Corp.
M4 Mahoning Valley Steel
M6 Mercer Pipe Div., Sawhill Tubular Products
M8 Mid-States Steel & Wire
M12 Moltrup Steel Products
M14 McInnes Steel Co.
M16 Md.Fine & Special. Wire
M17 Metal Forming Corp.
M18 Milton Steel Div., Merritt-Chapman&Scott
M21 Mallory-Sharon Titanium Corp.
M22 Mill Strip Products Co.

N1 National Standard Co.
N2 National Supply Co.
N3 National Tube Div., U. S. Steel Corp.
N5 Nelson Steel & Wire Co.
N6 New England High Carbon Wire Co.
N8 Newman-Crosby Steel
N9 Newport Steel Corp.
N14 Northwest.SteelRoll.Mill
N15 Northwestern S.&W. Co.

O4 Oregon Steel Mills

P1 Pacific States Steel Corp.
P2 Pacific Tube Co.
P4 Phoenix Iron & Steel Co., Sub. of Barium Steel Corp.
P5 Pilgrim Drawn Steel
P6 Pittsburgh Coke & Chem.
P7 Pittsburgh Steel Co.
P11 Pollak Steel Co.
P12 Portsmouth Div., Detroit Steel Corp.
P13 Precision Drawn Steel
P14 Pitts. Screw & Bolt Co.
P15 Pittsburgh Metallurgical
P16 Page Steel & Wire Div., Amer. Chain & Cable
P17 Plymouth Steel Co.
P19 Pitts. Rolling Mills
P20 Prod. Steel Strip Corp.
P22 Phoenix Mfg. Co.
P24 Phil. Steel & Wire Corp.

R1 Reeves Steel & Mfg. Co.
R2 Republic Steel Corp.
R3 Rhode Island Steel Corp.
R5 Roebling's Sons, John A.
R6 Rome Strip Steel Co.
R8 Reliance Div.,EatonMfg.
R9 Rome Mfg. Co.
R10 Rodney Metals Inc.

S1 Seneca Wire & Mfg. Co.
S3 Sharon Steel Corp.
S4 Sharon Tube Co.
S5 Sheffield Steel Div., Armco Steel Corp.
S6 Shenango Furnace Co.
S7 Simmons Co.
S8 Simonds Saw & Steel Co.
S12 Spencer Wire Corp.
S13 Standard Forgings Corp.
S14 Standard Tube Co.
S15 Stanley Works
S17 Superior Drawn Steel Co.
S18 Superior Steel Corp.
S19 Sweet's Steel Co.
S20 Southern States Steel
S23 Superior Tube Co.
S25 Stainless Welded Prod.
S26 Specialty Wire Co. Inc.
S30 Sierra Drawn Steel Corp.
S40 Seneca Steel Service
S41 Stainless Steel Div., J&L Steel Corp.
S42 Southern Elec. Steel Co.

T2 Tenn. Coal & Iron Div., U. S. Steel Corp.
T3 Tenn. Prod. & Chem.
T4 Texas Steel Co.
T5 Thomas Strip Div. Pittsburgh Steel Co.
T6 Thompson Wire Co.
T7 Timken Roller Bearing
T9 Tonawanda Iron Div., Am. Rad. & Stan. San.
T13 Tube Methods Inc.
T19 Techalloy Co. Inc.

U4 Universal-Cyclops Steel
U5 United States Steel Corp.
U6 U. S. Pipe & Foundry
U7 Ulbrich Stainless Steels
U8 U. S. Steel Supply Div., U. S. Steel Corp.

V2 Vanadium-Alloys Steel
V3 Vulcan Crucible Div., H. K. Porter Co. Inc.

W1 Wallace Barnes Co.
W2 Wallingford Steel Co.
W3 Washburn Wire Co.
W4 Washington Steel Corp.
W6 Weirton Steel Co.
W8 Western Automatic Machine Screw Co.
W9 Wheatland Tube Co.
W10 Wheeling Steel Corp.
W12 Wickwire Spencer Steel Div., Colo. Fuel & Iron
W13 Wilson Steel & Wire Co.
W14 Wisconsin Steel Div., International Harvester
W15 Woodward Iron Co.
W18 Wyckoff Steel Co.

Y1 Youngstown Sheet&Tube

STRIP

STRIP, Hot-Rolled Carbon

Ala.City,Ala.(27) R2 ..4.925
Allenport,Pa. P7 .....4.925
Alton,Ill. L1 .....5.125
Ashland,Ky.(8) A10 ..4.925
Atlanta A11 .....5.125
Bessemer,Ala. T2 ....4.925
Birmingham C15 .....4.925
Buffalo (27) R2 .....4.925
Conshohocken,Pa. A3 ..4.975
Detroit M1 .....5.025
Ecorse,Mich. G5 .....5.025
Fairfield,Ala. T2 .....4.925
Fontana, Calif. K1 ...5.825
Gary,Ind. U5 .....4.925
Ind.Harbor,Ind. I-2, Y1 4.925
Johnstown,Pa. (25) B2 .4.925
Lackaw'na,N.Y.(25) B2 4.925
LosAngeles(25) B3 ....5.675
Minnequa,Colo. C10 ..6.025
Pittsburg,Calif. C11 ..5.675
Riverdale,Ill. A1 .....4.925
SanFrancisco S7 .....6.35
Seattle(25) B3 .....6.35
Seattle N14 .....6.35
Sharon,Pa. S3 .....4.925
S.SanFrancisco(25) B3 5.675
SparrowsPoint,Md. B2 4.925
Sterling,Ill. (1) N15 ..4.925
Sterling,Ill. N15 .....5.025
Torrance,Calif. C11 ..5.675
Warren,O. R2 .....4.925
Weirton,W.Va. W6 ...4.925
Youngstown U5 .....4.925

STRIP, Hot-Rolled Alloy

Carnegie,Pa. S18 .....8.10
Farrell,Pa. S3 .....8.10
Gary,Ind. U5 .....8.10
Houston S5 .....8.35
Ind.Harbor,Ind. Y1 ....8.10
KansasCity,Mo. S5 ....8.35
LosAngeles B3 .....9.30
Lowellville,O. S3 .....8.10
Newport,Ky. A2 .....8.10
Sharon, Pa. A2 .....8.10
S.Chicago,Ill. W14 ....8.10
Youngstown U5, Y1 ..8.10

STRIP, Hot-Rolled High-Strength, Low-Alloy

Bessemer,Ala. T2 ....7.325
Conshohocken,Pa. A3 ..7.325
Ecorse,Mich. G5 .....7.425
Fairfield,Ala. T2 ....7.325
Farrell,Pa. S3 .....7.325
Gary,Ind. U5 .....7.325
Ind.Harbor,Ind. I-2, Y1 7.325
Lackawanna,N.Y. B2..7.325
LosAngeles(25) B3 ....8.075
Seattle(25) B3 .....8.325
Sharon,Pa. S3 .....7.325
S.Chicago,Ill. W14 ....7.325
S.SanFrancisco(25) B3.8.075
SparrowsPoint,Md. B2..7.325
Warren,O. R2 .....7.325
Weirton,W.Va. W6 ....7.325
Youngstown U5, Y1 ..7.325

STRIP, Hot-Rolled Ingot Iron

Ashland,Ky.(8) A10 ..5.175
Warren,O. R2 .....5.675

STRIP, Cold-Rolled Carbon

Anderson,Ind. G6 .....7.15
Baltimore T6 .....7.15
Boston T6 .....7.70
Buffalo S40 .....7.15
Cleveland A7, J5 .....7.15
Conshohocken,Pa. A3 ..7.20
Dearborn,Mich. D3 ....7.25
Detroit D2, M1, P20 ...7.25
Dover,O. G6 .....7.15
Ecorse,Mich. G5 .....7.25
Evanston,Ill. M22 .....7.25
Follansbee,W.Va. F4 ..7.15
Fontana,Calif. K1 ....9.00
Franklin Park,Ill. T6 ..7.25
Ind.Harbor,Ind. Y1 ....7.15
Indianapolis J5 .....7.30
LosAngeles J5 .....9.05
LosAngeles C1 .....9.20
NewBedford,Mass. R10..7.60
NewBritain(10) S15 ....7.15
NewCastle,Pa. B4, E5 ..7.15
NewHaven,Conn. D2 ...7.60
NewKensington,Pa. A6..7.15
Pawtucket,R.I. R3 ....7.80
Pawtucket,R.I. N8 ....7.70
Philadelphia(45) P24 ...7.70
Pittsburgh J5 .....7.15
Riverdale,Ill. A1 .....7.25
Rome,N.Y. (32) R6 ....7.15
Sharon,Pa. S3 .....7.15
Trenton,N.J. (31) R5..8.60
Wallingford,Conn. W2 ..7.60
Warren,O. R2, T5 ....7.15
Weirton,W.Va. W6 ....7.15
Worcester,Mass. A7 ....7.70
Youngstown J5, Y1 ....7.15

STRIP, Cold-Rolled Alloy

Boston T6 .....15.40
Carnegie,Pa. S18 .....15.05
Cleveland A7 .....15.05
Dover,O. G6 .....15.05
Farrell,Pa. S3 .....15.05
FranklinPark,Ill. T6 ..15.05
Harrison,N.J. C18 ....15.05
Indianapolis J5 .....15.20
Lowellville,O. S3 .....15.05
Pawtucket,R.I. N8 ....15.40
Riverdale,Ill. A1 .....15.05
Sharon,Pa. S3 .....15.05
Worcester,Mass. A7 ...15.35
Youngstown J5 .....15.05

STRIP, Cold-Rolled High-Strength, Low-Alloy

Cleveland A7 .....10.45
Dearborn,Mich. D3 ....10.60
Dover,O. G6 .....10.45
Ecorse,Mich. G5 .....10.55
Farrell,Pa. S3 .....10.50
Ind.Harbor,Ind. Y1 ...10.65
Sharon,Pa. S3 .....10.50
Warren,O. R2 .....10.45

STRIP, Cold-Finished Spring Steel (Annealed)	0.26-0.40C	0.41-0.60C	0.61-0.80C	0.81-1.05C	1.06-1.35C
Baltimore T6	9.50	10.70	12.90	15.90	18.85
Boston T6	9.50	10.70	12.90	15.90	18.85
Bristol,Conn. W1	...	10.70	12.90	16.10	19.30
Carnegie,Pa. S18	8.95	10.40	12.60	15.60	....
Cleveland A7	8.95	10.40	12.60	15.60	18.55
Dearborn,Mich. D3	9.05	10.50	12.70	....	....
Detroit D2	9.05	10.50	12.70	15.70	....
Dover,O. G6	8.95	10.40	12.60	15.60	18.55
Evanston,Ill. M22	8.95	10.40	12.60	....	....
Fostoria,O. S1	10.05	11.15	13.10	16.10	....
FranklinPark,Ill. T6	9.05	10.40	12.60	15.60	18.55
Harrison,N.J. C18	...	....	12.90	16.10	19.30
Indianapolis J5	9.10	10.55	12.60	15.60	18.55
LosAngeles C1	11.15	12.60	14.80	17.80	....
LosAngeles J5	11.15	12.60	14.80	....	....
NewBritain,Conn.(10) S15.	8.95	10.40	12.60	15.60	18.55
NewCastle,Pa. B4, E5 ...	8.95	10.40	12.60	15.60	....
NewHaven,Conn. D2	9.40	10.70	12.90	15.90	....
NewKensington,Pa. A6 ...	8.95	10.40	12.60	15.60	....
NewYork W3	...	10.70	12.90	16.10	19.30
Pawtucket,R.I. N8	9.50	10.70	12.90	15.90	18.85
Riverdale,Ill. A1	9.05	10.40	12.60	15.60	18.55
Rome,N.Y.(32) R6	8.95	10.40	12.60	15.60	18.55
Sharon,Pa. S3	8.95	10.40	12.60	15.60	18.55
Trenton,N.J. R5	...	10.70	12.90	16.10	19.30
Wallingford,Conn. W2 ...	9.40	10.70	12.90	15.90	18.75
Warren,O. T5	8.95	10.40	12.60	15.60	18.55
Worcester,Mass. A7, T6..	9.50	10.70	12.90	15.90	18.85
Youngstown J5	8.95	10.40	12.60	15.60	18.55

Spring Steel (Tempered)			Up to 0.80C	0.81-1.05C	1.06-1.35C
Bristol,Conn. W1	...	...	18.10	21.95	26.30
Buffalo W12	...	...	18.10	....	....
Fostoria,O. S1	...	...	18.30	22.15	....
FranklinPark,Ill. T6	...	...	18.45	22.30	26.65
Harrison,N.J. C18	...	...	18.10	21.95	26.30
NewYork W3	...	...	18.10	21.95	26.30
Palmer,Mass. W12	...	...	18.10	....	....
Trenton,N.J. R5	...	...	18.10	21.95	26.30
Worcester,Mass. A7, T6..	...	...	18.10	21.95	26.30
Youngstown J5	...	...	18.45	22.30	26.65

STRIP, Galvanized (Continuous)

Sharon,Pa. S3 .....7.275

TIGHT COOPERAGE HOOP

Atlanta A11 .....5.65
Riverdale,Ill. A1 .....5.35
Sharon,Pa. S3 .....5.35
Youngstown U5 .....5.35

STRIP, Cold-Rolled Ingot Iron

Warren,O. R2 .....7.90

STRIP, C.R. Electrogalvanized

Cleveland A7 .....7.15*
Dover,O. G6 .....7.15*
Evanston,Ill. M22 .....7.25*
Riverdale,Ill. A1 .....7.25*
Warren,O. B9, T5 ....7.15*
Worcester,Mass. A7 ...7.70*
Youngstown J5 .....7.15*

*Plus galvanizing extras.

SILICON STEEL

H.R.SHEETS(22 Ga.,cut lengths)	Field	Armature	Electric	Motor	Dynamo
BeechBottom,W.Va. W10 .	....	....	11.80	12.90	13.95
Mansfield,O. E6	9.625	11.10	11.80	12.90	13.95
Newport,Ky. A2	9.625	11.10	11.80	12.90	13.95
Niles,O. M21, S3	9.625	11.10	11.80	12.90	....
Vandergrift,Pa. U5	....	11.10	11.80	12.90	13.95
Warren,O. R2	9.625	11.10	11.80	12.90	....
Zanesville,O. A10	....	11.10	11.80	12.90	13.95
Zanesville,O. A10 (SP Coils)	....	....	11.55	12.65	13.70

C.R. COILS & CUT LENGTHS (22 Ga.) Fully Processed (Semiprocessed ½c lower)	Field	Armature	Electric	Motor	Dynamo
BeechBottom,W.Va. W10.	....	11.35	12.05	13.15	14.20
Brackenridge,Pa. A4	....	....	12.05	13.15	14.20
GraniteCity,Ill. G4	9.825*	11.05*	11.75*	12.85*	....
IndianaHarbor,Ind. I-2 ..	9.625†	10.85*	11.55*	12.65*	....
Mansfield,O. E6	9.625*	11.35	12.05	13.15	14.20
Vandergrift,Pa. U5	9.625*	11.35	12.05	13.15	14.20
Warren,O. R2	9.625*	11.35	12.05	13.15	14.20
Zanesville,O. A10(FP Coils)	...	11.35	12.05	13.15	14.20

H.R. SHEETS (22 Ga., cut lengths)	Transformer Grades T-72	T-65	T-58	T-52
BeechBottom,W.Va. W10	15.00	15.55	16.05	17.10
Vandergrift,Pa. U5	14.75	15.55	16.05	17.10
Zanesville,O. A10	15.00	15.55	16.05	17.10

C.R. COILS & CUT LENGTHS (22 Ga.)	Grain Oriented T-100	T-90	T-80	T-73	T-66	T-72
Brackenridge,Pa. A4.	17.60	19.20	19.70	20.20	....	
Butler,Pa. A10	....	....	19.20	19.70	20.20	15.25**
Vandergrift,Pa. U5 ..	16.60	17.60	19.20	19.70	20.20	15.25‡
Warren,O. R2	....	....	....	....	....	....

*Semiprocessed. †Fully processed only. ‡Coils, annealed, semiprocessed ½c lower. **Cut lengths, ¾-cent lower.

TIN MILL PRODUCTS

TIN PLATE, Electrolytic (Base Box)	0.25 lb	0.50 lb	0.75 lb
Aliquippa,Pa. J5	$8.75	$9.00	$9.40
Fairfield,Ala. T2	8.85	9.10	9.50
Fairless,Pa. U5	8.85	9.10	9.50
Fontana,Calif. K1	9.50	9.75	10.15
Gary,Ind. U5	8.75	9.00	9.40
GraniteCity,Ill. G4	8.85	9.10	9.50
IndianaHarbor,Ind. I-2, Y1	8.75	9.00	9.40
Irvin,Pa. U5	8.75	9.00	9.40
Niles,O. R2	8.75	9.00	9.40
Pittsburg,Calif. C11	9.50	9.75	10.15
SparrowsPoint,Md. B2	8.85	9.10	9.50
Weirton,W.Va. W6	8.75	9.00	9.40
Yorkville,O. W10	8.75	9.00	9.40

ELECTROTIN (22-27 Gage; Dollars per 100 lb)			
Aliquippa,Pa. J5	7.725	7.925	....
Niles,O. R2	7.725	7.925	8.125

TIN PLATE, American	1.25 lb	1.50 lb
Aliquippa,Pa. J5	$10.05	$10.30
Fairfield,Ala. T2	10.15	10.40
Fairless,Pa. U5.	10.15	10.40
Fontana,Calif. K1	10.80	11.05
Gary,Ind. U5 ..	10.05	10.30
Irvin,Pa. U5 ..	10.05	10.30
Pitts.,Calif. C11.	10.80	11.05
Sp.Pt.,Md. B2 ..	10.15	10.40
Weirton,W.Va. W6	10.05	10.30
Yorkville,O. W10	10.05	10.30

BLACK PLATE (Base Box)

Aliquippa,Pa. J5 .....$7.85
Fairfield,Ala. T2 .....7.95
Fairless,Pa. U5 .....7.95
Fontana,Calif. K1 ....8.60
Gary,Ind. U5 .....7.85
GraniteCity,Ill. G4 ....7.95
Ind.Harbor,Ind. I-2, Y1.7.85
Irvin,Pa. U5 .....7.85
Niles,O. R2 .....7.85
Pittsburg,Calif. C11 ..8.60
SparrowsPoint,Md. B2..7.95
Weirton,W.Va. W6 ....7.85
Yorkville,O. W10 .....7.85

HOLLOWARE ENAMELING Black Plate (29 Gage)

Aliquippa,Pa. J5 ....$7.50
Gary,Ind. U5 .....7.50
GraniteCity,Ill. G4 ....7.60
Ind.Harbor,Ind. Y1 ....7.50
Irvin,Pa. U5 .....7.50
Yorkville,O. W10 .....7.50

MANUFACTURING TERNES (Special Coated, Base Box)

Gary,Ind. U5 .....$9.70
Irvin,Pa. U5 .....9.70

ROOFING SHORT TERNES (8 lb Coated, Base Box)

Gary,Ind. U5 .....$11.25

WIRE

WIRE, Manufacturers Bright, Low Carbon

AlabamaCity,Ala. R2 ..7.65
Aliquippa,Pa. J5 .....7.65
Alton,Ill. L1 .....7.85
Atlanta A11 .....7.85
Bartonville,Ill. K4 ....7.75
Buffalo W12 .....7.65
Chicago W13 .....7.65
Cleveland A7, C20 ....7.65
Crawfordsville,Ind. M8..7.75
Donora,Pa. A7 .....7.65
Duluth A7 .....7.65
Fairfield,Ala. T2 .....7.65
Fostoria,O.(24) S1 ....7.75
Houston S5 .....7.90
Jacksonville,Fla. M8 ..8.00
Johnstown,Pa. B2 ....7.65
Joliet,Ill. A7 .....7.65
KansasCity,Mo. S5 ....7.90
Kokomo,Ind. C16 .....7.75
LosAngeles B3 .....8.60
Minnequa,Colo. C10 ....7.90
Monessen,Pa. P7, P16 .7.65
N.Tonawanda,N.Y. B11 7.65
Palmer,Mass. W12 ....7.95
Pittsburg,Calif. C11 ....8.60
Portsmouth,O. P12 ....7.65
Rankin,Pa. A7 .....7.65
S.Chicago,Ill. R2 .....7.65
S.SanFrancisco C10 ....8.60
SparrowsPoint,Md. B2..7.75
Sterling,Ill.(1) N15 ....7.65
Sterling,Ill. N15 .....7.75
Struthers,O. Y1 .....7.65
Waukegan,Ill. A7 .....7.65
Worcester,Mass. A7 ....7.95

WIRE, Gal'd ACSR for Cores

Bartonville,Ill. K4 ....12.65
Buffalo W12 .....12.65
Cleveland A7 .....12.65
Donora,Pa. A7 .....12.65
Duluth A7 .....12.65
Johnstown,Pa. B2 .....12.65
Minnequa,Colo. C10 ..12.775
Monessen,Pa. P16 ....12.65
Muncie,Ind. I-7 .....12.85
NewHaven,Conn. A7 ..12.95
Palmer,Mass. W12 ...12.95
Pittsburg,Calif. C11 ..13.45
Portsmouth,O. P12 ....12.65
Roebling,N.J. R5 .....12.95
SparrowsPt.,Md. B2 ..12.75
Struthers,O. Y1 .....12.65
Trenton,N.J. A7 .....12.95
Waukegan,Ill. A7 .....12.65
Worcester,Mass. A7 ..12.95

WIRE, Upholstery Spring

Aliquippa,Pa. J5 .....9.30
Alton,Ill. L1 .....9.50
Buffalo W12 .....9.30
Cleveland A7 .....9.30
Donora,Pa. A7 .....9.30
Duluth A7 .....9.30
Johnstown,Pa. B2 .....9.30
KansasCity,Mo. S5 ....9.55
LosAngeles B3 .....10.25
Minnequa,Colo. C10 ....9.50
Monessen,Pa. P7, P16 ..9.30
NewHaven,Conn. A7 ..9.60
Palmer,Mass. W12 ....9.60
Pittsburg,Calif. C11 ..10.25
Portsmouth,O. P12 ....9.30
Roebling,N.J. R5 .....9.60
S.Chicago,Ill. R2 .....9.30
S.SanFrancisco C10 ..10.25
SparrowsPt.,Md. B2 ...9.40
Struthers,O. Y1 .....9.30
Trenton,N.J. A7 .....9.60
Waukegan,Ill. A7 .....9.60
Worcester,Mass. A7 ....9.60

WIRE, MB Spring, High Carbon

Aliquippa,Pa. J5 .....9.30
Alton,Ill. L1 .....9.50
Bartonville,Ill. K4 ....9.40
Buffalo W12 .....9.30
Cleveland A7 .....9.30
Donora,Pa. A7 .....9.30
Duluth A7 .....9.30
Fostoria,O. S1 .....9.35
Johnstown,Pa. B2 ....9.30
KansasCity,Mo. S5 ....9.55
LosAngeles B3 .....10.25
Milbury,Mass.(12) N6 ..9.60
Minnequa,Colo. C10 ...9.50
Monessen,Pa. P7, P16..9.30
Muncie,Ind. I-7 .....9.50
Palmer,Mass.(12) W12 .9.60
Pittsburg,Calif. C11 ..10.25
Portsmouth,O. P12 ....9.30
Roebling,N.J. R5 .....9.60
S.Chicago,Ill. R2 .....9.30
S.SanFrancisco C10 ..10.25
SparrowsPt.,Md. B2 ...9.40
Struthers,O. Y1 .....9.30
Trenton,N.J. A7 .....9.60
Waukegan,Ill. A7 .....9.30
Worcester,A7, J4, T6 ..9.60

WIRE, Fine & Weaving(8" Coils

Alton,Ill. L1 .....15.80
Bartonville,Ill. K4 ....15.70
Buffalo W12 .....15.60
Chicago W13 .....15.60
Cleveland A7 .....15.60
Crawfordsville,Ind. M8.15.70
Fostoria,O. S1 .....15.60
Houston S5 .....15.80
Jacksonville,Fla. M8 ..15.90
Johnstown,Pa. B2 ....15.60
KansasCity,Mo. S5 ....15.80
Kokomo,Ind. C16 .....15.60
Minnequa,Colo. C10 ...15.80
Monessen,Pa. P7, P16..15.60
Muncie,Ind. I-7 .....15.80
Palmer,Mass. W12 ....15.90
S.SanFrancisco C10 ..16.40
Waukegan,Ill. A7 .....15.60
Worcester,Mass. A7, T6 15.90

ROPE WIRE

Bartonville,Ill. K4 ....12.70
Buffalo W12 .....12.70
Fostoria,O. S1 .....12.70
Johnstown,Pa. B2 ....12.70
Monessen,Pa. P7 .....12.70
Muncie,Ind. I-7 .....12.90
Palmer,Mass. W12 ....13.00
Portsmouth,O. P12 ....12.70
Roebling,N.J. R5 .....13.00
SparrowsPt.,Md. B2 ..12.90
Struthers,O. Y1 .....12.70
Worcester,Mass. J4 ...13.00
(A) Plow and Mild Plow
add 0.25c for Improved Plo

WIRE, Tire Bead

Bartonville,Ill. K4	....16.55
Monessen,Pa. P16	....16.55
Roebling,N.J. R5	....17.05

WIRE, Cold-Rolled Flat

Anderson,Ind. G6	....11.65
Baltimore T6	.....11.95
Boston T6	.....11.95
Buffalo W12	.....11.65
Chicago W13	.....11.75
Cleveland A7	.....11.65
Crawfordsville,Ind. M8	..11.65
Dover,O. G6	.....11.65
Fostoria,O. S1	.....11.65
FranklinPark,Ill. T6	..11.75
Kokomo,Ind. C16	....11.65
Massillon,O. R8	.....11.65
Milwaukee C23	.....11.85
Monessen,Pa. P7, P16	..11.65
Palmer,Mass. W12	....11.95
Pawtucket,R.I. N8	....11.95
Philadelphia P24	.....11.95
Riverdale,Ill. A1	.....11.75
Rome,N.Y. R6	.....11.65
Sharon,Pa. S3	.....11.65
Trenton,N.J. R5	.....11.95
Warren,O. B9	.....11.65
Worcester,Mass. A7, T6	11.95

NAILS, Stock — **Col.**

AlabamaCity,Ala. R2	..173
Aliquippa,Pa. J5	173
Atlanta A11	175
Bartonville,Ill. K4	175
Chicago W13	173
Cleveland A9	173
Crawfordsville,Ind. M8	..175
Donora,Pa. A7	173
Duluth A7	173
Fairfield,Ala. T2	173
Houston S5	178
Jacksonville,Fla.(20) M8	184
Johnstown,Pa. B2	173
Joliet,Ill. A7	173
KansasCity,Mo. S5	178
Kokomo,Ind. C16	175
Minnequa,Colo. C10	178
Monessen,Pa. P7	173
Pittsburg,Calif. C11	192
Rankin,Pa. A7	173
S.Chicago,Ill. R2	173
SparrowsPt.,Md. B2	175
Sterling,Ill.(7) N15	175
Worcester,Mass. A7	179

(To Wholesalers; per cwt)

Galveston,Tex. D7	...$9.10

NAILS, Cut (100 lb keg) To Dealers (33)

Conshohocken,Pa. A3	..$9.80
Wheeling,W.Va. W10	...9.80

POLISHED STAPLES — **Col.**

AlabamaCity,Ala. R2	...175
Aliquippa,Pa. J5	175
Atlanta A11	177
Bartonville,Ill. K4	177
Crawfordsville,Ind. M8	..177
Donora,Pa. A7	175
Duluth A7	175
Fairfield,Ala. T2	175
Jacksonville,Fla.(20) M8	186
Johnstown,Pa. B2	175
Joliet,Ill. A7	175
Kokomo,Ind. C16	177
Minnequa,Colo. C10	180
Pittsburg,Calif. C11	194
Rankin,Pa. A7	175
S.Chicago,Ill. R2	175
SparrowsPt.,Md. B2	177
Sterling,Ill.(7) N15	175
Worcester,Mass. A7	181

TIE WIRE, Automatic Baler (14½ Ga.)(Per 97 lb Net Box) Coil No. 3150

AlabamaCity,Ala. R2	.$10.26
Atlanta A11	.....10.36
Bartonville,Ill. K4	....10.36
Buffalo W12	.....10.26
Chicago W13	.....10.26
Crawfordsville,Ind. M8	.10.36
Donora,Pa. A7	.....10.26
Duluth A7	.....10.26
Fairfield,Ala. T2	....10.26
Houston S5	.....10.51
Jacksonville,Fla. M8	..10.82
Johnstown,Pa. B2	....10.26
Joliet,Ill. A7	.....10.26
KansasCity,Mo. S5	....10.51
Kokomo,Ind. C16	.....10.36
LosAngeles B3	.....11.05
Minnequa,Colo. C10	...10.51
Pittsburg,Calif. C11	..11.04
S.Chicago,Ill. R2	.....10.26
S.SanFrancisco C10	..11.04
SparrowsPt.,Md. B2	..10.36
Sterling,Ill.(37) N15	..10.36

Coil No. 6500 Stand.

AlabamaCity,Ala. R2	.$10.60
Atlanta A11	.....10.70
Bartonville,Ill. K4	....10.70
Buffalo W12	.....10.60
Chicago W13	.....10.60
Crawfordsville,Ind. M8	.10.70
Donora,Pa. A7	.....10.60
Duluth A7	.....10.60
Fairfield,Ala. T2	.....10.60
Houston S5	.....10.85
Jacksonville,Fla. M8	..11.16
Johnstown,Pa. B2	....10.60
Joliet,Ill. A7	.....10.60
KansasCity,Mo. S5	....10.85
Kokomo,Ind. C16	....10.70
LosAngeles B3	.....11.40
Minnequa,Colo. C10	..10.85
Pittsburg,Calif. C11	..11.40
S.Chicago,Ill. R2	.....10.60
S.SanFrancisco C10	..11.40
SparrowsPt.,Md. B2	..10.70
Sterling,Ill.(37) N15	..10.70

Coil No. 6500 Interim

AlabamaCity,Ala. R2	..$10.65
Atlanta A11	.....10.75
Bartonville,Ill. K4	....10.75
Buffalo W12	.....10.65
Chicago W13	.....10.65
Crawfordsville,Ind. M8	.10.75
Donora,Pa. A7	.....10.65
Duluth A7	.....10.65
Fairfield,Ala. T2	.....10.65
Houston S5	.....10.90
Jacksonville,Fla. M8	..11.21
Johnstown,Pa. B2	....10.65
Joliet,Ill. A7	.....10.65
KansasCity,Mo. S5	....10.90
Kokomo,Ind. C16	....10.75
LosAngeles B3	.....11.45
Minnequa,Colo. C10	...10.90
Pittsburg,Calif. C11	...11.45
S.Chicago,Ill. R2	....10.65
S.SanFrancisco C10	...11.45
SparrowsPt.,Md. B2	...10.75
Sterling,Ill.(37) N15	..10.75

BALE TIES, Single Loop — **Col.**

AlabamaCity,Ala. R2	..212
Atlanta A11	214
Bartonville,Ill. K4	214
Crawfordsville,Ind. M8	..214
Donora,Pa. A7	212
Duluth A7	212
Fairfield,Ala. T2	212
Houston S5	217
Jacksonville,Fla. M8	...219
Joliet,Ill. A7	212
KansasCity,Mo. S5	217
Kokomo,Ind. C16	214
Minnequa,Colo. C10	217
Pittsburg,Calif. C11	236
S.SanFrancisco C10	236
SparrowsPt.,Md. B2	214
Sterling,Ill.(7) N15	214
Williamsport,Pa. S19	...175

FENCE POSTS

Birmingham C15	171
ChicagoHts.,Ill. C2, I-2	..172
Duluth A7	172
Franklin,Pa. F5	172
Huntington,W.Va. C15	..171
Johnstown,Pa. B2	172
Marion,O. P11	172
Minnequa,Colo. C10	177
Sterling,Ill.(1) N15	172
Tonawanda,N.Y. B12	..174

WIRE, Barbed — **Col.**

AlabamaCity,Ala. R2	..193**
Aliquippa,Pa. J5	.....190§
Atlanta A11	.....198*
Bartonville,Ill. K4	198
Crawfordsville,Ind. M8	...198
Donora,Pa. A7	.....193†
Duluth A7	.....193†
Fairfield,Ala. T2	.....193†
Houston S5	.....198**
Jacksonville,Fla. M8	...203
Johnstown,Pa. B2	....196§
Joliet,Ill. A7	.....193†
KansasCity,Mo. S5	...198**
Kokomo,Ind. C16	.....195†
Minnequa,Colo. C10	...198**
Monessen,Pa. P7	.....196*
Pittsburg,Calif. C11	...213†
Rankin,Pa. A7	.....193†
S.Chicago,Ill. R2	.....193**
S.SanFrancisco C10	..213**
SparrowsPoint,Md. B2	..198§
Sterling,Ill.(7) N15	....198§

WOVEN FENCE, 9-15 Ga. — **Col.**

Ala.City,Ala. R2	....187**
Aliq'ppa,Pa.9-14½ga.J5	190§
Atlanta A11	.....192*
Bartonville,Ill. K4	192
Crawfordsville,Ind. M8	..192
Donora,Pa. A7	.....187†
Duluth A7	.....187†
Fairfield,Ala. T2	.....187†
Houston S5	.....192**
Jacksonville,Fla. M8	...197
Johnstown,Pa.(43) B2	..190§
Joliet,Ill. A7	.....187†
KansasCity,Mo. S5	...192**
Kokomo,Ind. C16	.....189†
Minnequa,Colo. C10	...192**
Pittsburg,Calif. C11	...210†
Rankin,Pa. A7	.....187†
S.Chicago,Ill. R2	.....187**
Sterling,Ill.(7) N15	....192§

WIRE (16 gage)	An'ld Galv. Stone	Stone
Ala.City,Ala.R2	17.15	18.70**
Aliq'ppa,Pa. J5.	17.15	18.95
Bartonville K4.	17.25	19.05
Cleveland A7	17.15	....
Crawf'dsville M8	17.25	19.05
Fostoria,O. S1	17.65	19.20†
Houston S5	17.40	18.95**
Jacksonville M8.	17.50	19.30
Johnstown B2	17.15	18.95§
Kan.City,Mo. S5	17.40	....
Kokomo C16	17.25	18.80†
Minnequa C10.	17.40	18.95**
P'lm'r,Mass.W12	17.45	19.00†
Pitts.,Calif. C11.	17.50	19.05†
SparrowsPt. B2	17.25	19.05§
Sterling(37)N15	17.25	19.05§
Waukegan A7	17.15	18.70†
Worcester A7	17.45	....

WIRE, Merchant Quality

(6 to 8 gage)	An'ld Galv.	
Ala.City,Ala.	R2. 8.65	9.20**
Aliquippa	J5 .... 8.65	9.325§
Atlanta(48)	A11.. 8.75	9.425*
Bartonville(48)	K4 8.75	9.425
Buffalo	W12 .... 8.65	9.20†
Cleveland	A7 .... 8.65	....
Crawfordsville	M8 8.75	9.425
Donora,Pa.	A7 .. 8.65	9.20†
Duluth	A7 ..... 8.65	9.20†
Fairfield	T2 ..... 8.65	9.20†
Houston(48)	S5 .8.90	9.45**
Jacks'ville,Fla.	M8 9.00	9.675
Johnstown	B2(48) 8.65	9.325§
Joliet,Ill.	A7 .... 8.65	9.20†
Kans.City(48)	S5 8.90	9.45**
Kokomo	C16 ..... 8.75	9.30†
LosAngeles	B3 ..9.60	10.275§
Minnequa	C10 ..8.90	9.45**
Monessen	P7(48)..8.65	9.25*
Palmer,Mass.	W12 8.95	9.50†
Pitts.,Calif.	C11..9.60	10.15†
Rankin,Pa.	A7 ..8.65	9.20†
S.Chicago	R2 ...8.65	9.20**
S.SanFran.	C10. .9.60	10.15**
Spar'wsPt.	B2(48) 8.75	9.425§
Sterling(48)	N15 .8.90	9.575§
Sterling(1)(48)	..8.80	9.475§
Struthers,O.(48)	Y1 8.65	9.30†
Worcester,Mass.	A7 8.95	9.50†

Based on zinc price of: *13.50c. †5c. §10c. ‡Less than 10c. ††10.50c. **Subject to zinc equalization extras.

FASTENERS

(Base discounts, full container quantity, per cent off list, f.o.b. mill)

BOLTS

Carriage, Machine Bolts

Full Size Body (cut thread)

½ in. and smaller:	
6 in. and shorter....	49.0
Longer than 6 in. ..	39.0
⅝ in. thru 1 in.:	
6 in. and shorter...	39.0
Longer than 6 in. ..	35.0
1⅛ in. and larger:	
All lengths	35.0

Undersized Body (rolled thread)

½ in. and smaller:	
6 in. and shorter..	49.0

Carriage, Machine, Lag Bolts Hot Galvanized:

½ in. and smaller:	
6 in. and shorter..	29.0
Longer than 6 in. ..	15.0
⅝ in. and larger:	
All lengths	12.0

Lag Bolts (all diam.)

6 in. and shorter..	49.0
Longer than 6 in. ..	39.0

Plow and Tap Bolts

½ in. and smaller by 6 in. and shorter	49.0
Larger than ½ in. or longer than 6 in. ..	39.0
Blank Bolts	39.0
Step, Elevator, Tire Bolts	49.0

Stove Bolts, Slotted:

⅛ to ¼ in. incl., 3 in. and shorter.	55.0
5/16 to ½ in., inclusive	55.0

NUTS

Reg. & Heavy Square Nuts: All sizes	55.5
Square Nuts, Reg. & Heavy, Hot Galvanized: All sizes	41.0
Hex Nuts, Reg. & Heavy, Hot Pressed:	
¾ in. and smaller..	60.5
⅞ in. to 1 in., incl.	55.5
1⅛ in. to 1½ in., incl.	58.5
1⅝ in. and larger..	53.5
Hex Nuts, Reg. & Heavy, Cold Punched:	
¾ in. and smaller..	60.5
⅞ in. to 1½ in., incl.	55.5
1⅝ in. and larger..	53.5
Hex Nuts, All Types, Hot Galvanized:	
¾ in. and smaller..	46.5
⅞ in. to 1 in., incl.	41.5
1⅛ in. to 1½ in., incl.	46.5
Hex Nuts, Semifinished, Heavy (Incl. Slotted):	
¾ in. and smaller..	60.5
⅞ in. to 1½ in., incl.	55.5
1⅝ in. and larger..	53.5
Hex Nuts, Finished (Incl. Slotted and Castellated):	
1 in. and smaller..	63.0
1⅛ in. to 1½ in., incl.	59.0
1⅝ in. and larger..	53.5
Semifinished Hex Nuts, Reg. (Incl. Slotted):	
⅝ in. and smaller..	60.5
¾ in. to 1 in., incl	63.0
1⅛ in. to 1½ in., incl.	59.0
1⅝ in. and larger..	53.5

CAP AND SETSCREWS

(Base discounts, packages, per cent off list, f.o.b. mill)

Hex Head Capscrews, Coarse or Fine Thread, Bright:	
6 in. and shorter:	
⅝ in. and smaller..	40.0
¾, ⅞, and 1 in. diam.	22.0
Longer than 6 in.:	
⅝ in. and smaller..	8[illegible]
¾, ⅞, and 1 in. diam.	+6[illegible]
High Carbon, Heat Treated	
6 in. and shorter:	
⅝ in. and smaller..	26[illegible]
¾, ⅞, and 1 in. diam.	3[illegible]
Longer than 6 in.:	
⅝ in. and smaller..	+13[illegible]
¾, ⅞, and 1 in. diam.	+32[illegible]
Flat Head Capscrews: ¾ in. and smaller..	+76[illegible]
Setscrews, Square Head, Cup Point, Coarse Thread: Through 1 in. diam.:	
6 in. and shorter...	N[illegible]
Longer than 6 in...	+23[illegible]

RIVETS

F.o.b. Cleveland and/c[illegible] freight equalized with Pitts[illegible] burgh, f.o.b. Chicago and/c[illegible] freight equalized with Bir[illegible] mingham except where equa[illegible] ization is too great.

Structural ½ in., larger 12.2[illegible]

5/16 in. under: List less 19[illegible]

BOILER TUBES

Net base c.l. prices, dollars per 100 ft, mill; minimum wall thickness, cut lengths 10 to 24 ft, inclusive.

O.D. In.	B.W. Gage	Seamless H.R.	Seamless C.D.	Elec. Weld H.R.
1	13	....	25.98	23.54
1¼	13	....	30.78	23.36
1½	13	29.03	34.01	25.83
1¾	13	34.29	40.18	30.51
2	13	38.44	45.05	34.20
2¼	13	43.29	50.75	38.52
2¼	12	46.99	55.06	41.81
2½	12	51.76	60.65	46.05
2¾	12	56.04	65.67	49.88
3	12	59.76	70.03	53.19

RAILWAY MATERIALS

	Standard No. 1	Standard No. 2	Tee Rail No. 2	Tee Rail All 60 lb
Rails				
Bessemer,Pa. U5	5.525	5.425	....	6.56
Ensley,Ala. T2	5.525	5.425	....	6.56
Fairfield,Ala. T2	....	....	....	6.56
Gary,Ind. U5	5.525	5.425	....	....
Huntington,W.Va. C15	....	....	....	6.56
IndianaHarbor,Ind. I-2	5.525	5.425	5.475	....
Johnstown,Pa. B2	....	....	...(16)	6.56
Lackawanna,N.Y. B2	5.525	5.425	....	6.56
Minnequa,Colo. C10	5.525	5.425	....	7.00
Steelton,Pa. B2	5.525	5.425	....	....
Williamsport,Pa. S19	....	....	....	6.56

TIE PLATES

Fairfield,Ala. T2	.....6.60
Gary,Ind. U5	.....6.60
Ind.Harbor,Ind. I-2	....6.60
Lackawanna,N.Y. B2	..6.60
Minnequa,Colo. C10	....6.60
Seattle B3	.....6.75
Steelton,Pa. B2	.....6.60
Torrance,Calif. C11	....6.75

JOINT BARS

Bessemer,Pa. U5	.....6.975
Fairfield,Ala. T2	.....6.975
Ind.Harbor,Ind. I-2	...6.975
Joliet,Ill. U5	.....6.975
Lackawanna,N.Y. B2	..6.975
Minnequa, Colo. C10	..6.975
Steelton,Pa. B2	.....6.975

AXLES

Ind.Harbor,Ind. S13	...8.775
Johnstown, Pa. B2	....8.775

TRACK BOLTS, Untreated

Cleveland R2	.....14.75
KansasCity,Mo. S5	....14.75
Lebanon,Pa. B2	.....14.75
Minnequa,Colo. C10	...14.75
Pittsburgh P14	.....14.75
Seattle B3	.....15.25

SCREW SPIKES

Lebanon,Pa. B2	.....14.50

STANDARD TRACK SPIKES

Fairfield, Ala. T2	.....9.75
Ind.Harbor,Ind. I-2, Y1	.9.75
KansasCity,Mo. S5	...9.75
Lebanon, Pa. B2	.....9.75
Minnequa,Colo. C10	....9.75
Pittsburgh J5	.....9.75
Seattle B3	.....10.25
S.Chicago,Ill. R2	.....9.75
Struthers,O. Y1	.....9.75
Youngstown R2	.....9.75

Footnotes

(1) Chicago base.
(2) Angles, flats, bands.
(3) Merchant.
(4) Reinforcing.
(5) 1⅛ to under 1 7/16 in.; 1 7/16 to under 1 15/16 in., 6.70c; 1 15/16 to 8 in., inclusive, 7.05c.
(6) Chicago or Birm. base.
(7) Chicago base 2 cols. lower.
(8) 13 Ga. and heavier.
(9) Merchant quality; add 0.35c for special quality.
(10) Pittsburgh base.
(11) Cleveland & Pitts. base.
(21) Worcester, Mass. base.
(13) Add 0.25c for 17 Ga. & heavier.
(14) Gage 0.143 to 0.249 in.; for gage 0.142 and lighter, 5.80c.
(15) ¾" and thinner.
(16) 40 lb and under.
(17) Flats only; 0.25 in. & heavier.
(18) To dealers.
(19) Chicago & Pitts. base.
(20) Plus 1c per 100 lb.
(21) New Haven, Conn. base.
(22) Deld. San Francisco Bay area.
(23) Special quality.
(24) Deduct 0.15c, finer than 15 Ga.
(25) Bar mill bands.
(26) Delivered in mill zone,6.045c.
(27) Bar mill sizes.
(28) Bonderized.
(29) Youngstown base.
(30) Sheared; for universal mill add 0.45c.
(31) Widths over ⅝ in.; 7.60c, for widths ⅝ in. and under by 0.125 in. and thinner.
(32) Buffalo base.
(33) To jobbers, deduct 20c.
(34) 9.60c for cut lengths.
(35) 72" and narrower.
(36) 54" and narrower.
(37) Chicago base, 10 points lower.
(38) 14 Ga. & lighter; 48" & narrower.
(39) 48" and narrower.
(40) Lighter than 0.035"; 0.035" and heavier, 0.25c higher.
(41) 9.10c for cut lengths.
(42) Mill lengths, f.o.b. mill; deld. in mill zone or within switching limits, 5.685c.
(43) 9-14½ Ga.
(44) To fabricators.
(45) 0.022 in. and lighter, over 0.022", 8.20c.
(46) Special quality.
(48) 6-7 Ga.
(49) 3½ in. and smaller rounds; 9.30c, over 3½ in. and other shapes.

SEAMLESS STANDARD PIPE, Threaded and Coupled

Carload discounts from list, %

Size—Inches	2		2½		3		3½		4		5		6	
List Per Ft	37c		58.5c		76.5c		92c		$1.09		$1.48		$1.92	
Pounds Per Ft	3.68		5.82		7.62		9.20		10.89		14.81		19.18	
	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*
Aliquippa, Pa. J5	+9.25	+24.25	+2.75	+19.5	+0.25	+17	1.25	+15.5	1.25	+15.5	1	+15.75	3.5	+13.25
Ambridge, Pa. N2	+9.25	....	+2.75	....	+0.25	....	1.25	....	1.25	....	1	....	3.5	....
Lorain, O. N3	+9.25	+24.25	+2.75	+19.5	+0.25	+17	1.25	+15.5	1.25	+15.5	1	+15.75	3.5	+13.25
Youngstown Y1	+9.25	+24.25	+2.75	+19.5	+0.25	+17	1.25	+15.5	1.25	+15.5	1	+15.75	3.5	+13.25

ELECTRIC STANDARD PIPE, Threaded and Coupled

Carload discounts from list, %

Youngstown R2	+9.25	+24.25	+2.75	+19.5	+0.25	+17	1.25	+15.5	1.25	+15.5	1	+15.75	3.5	+13.25

BUTTWELD STANDARD PIPE, Threaded and Coupled

Carload discounts from list, %

Size—Inches	⅛		¼		⅜		½		¾		1		1¼	
List Per Ft	5.5c		6c		6c		8.5c		11.5c		17c		23c	
Pounds Per Ft	0.24		0.42		0.57		0.85		1.13		1.68		2.28	
	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*
Aliquippa, Pa. J5	....	....	....	....	....	....	5.25	+10	8.25	+6	11.75	+1.5	14.25	+0.75
Alton, Ill. L1	....	....	....	....	....	....	3.25	+12	6.25	+8	9.75	+3.5	12.25	+2.75
Benwood, W. Va. W10	4.5	+22	+7.5	+31	+18	+39.5	5.25	+10	8.25	+6	11.75	+1.5	14.25	+0.75
Butler, Pa. F6	5.5	+21	+6.5	+30	+17	+38.5	....	....	....	....	....	....	....	....
Etna, Pa. N2	....	....	....	....	....	....	5.25	+10	8.25	+6	11.75	+1.5	14.25	+0.75
Fairless, Pa. N3	....	....	....	....	....	....	3.25	+12	6.25	+8	9.75	+3.5	12.25	+2.75
Fontana, Calif. K1	....	....	....	....	....	....	+8.25	+23.5	+5.25	+19.5	+1.75	+15	0.75	+14.25
Indiana Harbor, Ind. Y1	....	....	....	....	....	....	4.25	+11	7.25	+7	10.75	+2.5	13.25	+3.25
Lorain, O. N3	....	....	....	....	....	....	5.25	+10	8.25	+6	11.75	+1.5	14.25	+0.75
Sharon, Pa. S4	5.5	+21	+6.5	+30	+17	+38.5	....	....	....	....	....	....	....	....
Sharon, Pa. M6	....	....	....	....	....	....	5.25	+10	8.25	+6	11.75	+1.5	14.25	+0.75
Sparrows Pt., Md. B2	3.5	+23	+8.5	+32	+19	+40.5	3.25	+12	6.25	+8	9.75	+3.5	12.25	+2.75
Wheatland, Pa. W9	5.5	+21	+6	+30	+17	+38.5	5.25	+10	8.25	+6	11.75	+1.5	14.25	+0.75
Youngstown R2, Y1	....	....	....	....	....	....	5.25	+10	8.25	+6	11.75	+1.5	14.25	+0.75

Size—Inches	1½		2		2½		3		3½		4	
List Per Ft	27.5c		37c		58.5c		76.5c		92c		$1.09	
Pounds Per Ft	2.73		3.68		5.82		7.62		9.20		10.89	
	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*	Blk	Galv*
Aliquippa, Pa. J5	14.75	0.25	15.25	0.75	16.75	0.5	16.75	0.5	....	....	....	....
Alton, Ill. L1	12.75	+1.75	13.25	+1.25	14.75	+1.5	14.75	+1.5	....	....	....	....
Benwood, W. Va. W10	14.75	0.25	15.25	0.75	16.75	0.5	16.75	0.5	6.25	+10.5	6.25	+10.5
Etna, Pa. N2	14.75	0.25	15.25	0.75	16.75	0.5	16.75	0.5	6.25	+10.5	6.25	+10.5
Fairless, Pa. N3	12.75	+1.75	13.25	+1.25	14.75	+1.5	14.75	+1.5	4.25	+12.5	4.25	+12.5
Fontana, Calif. K1	1.25	+13.25	1.75	+12.75	3.25	+13	3.25	+13	+7.25	+24	+7.25	+24
Indiana Harbor, Ind. Y1	13.75	+0.75	14.25	+0.25	15.75	+0.5	15.25	+0.5	5.25	+11.5	5.25	+11.5
Lorain, O. N3	14.75	0.25	15.25	0.75	16.75	0.5	16.75	0.5	....	....	....	....
Sharon, Pa. M6	14.75	0.25	15.25	0.75	16.75	0.5	16.75	0.5	....	....	....	....
Sparrows Pt., Md. B2	12.75	+1.75	13.25	+1.25	14.75	+1.5	14.75	+1.5	4.25	+12.5	4.25	+12.5
Wheatland, Pa. W9	14.75	0.25	15.25	0.75	16.75	0.5	16.75	0.5	6.25	+10.5	6.25	+10.5
Youngstown R2, Y1	14.75	0.25	15.25	0.75	16.75	0.5	16.75	0.5	6.25	+10.5	6.25	+10.5

*Galvanized pipe discounts based on current price of zinc (10.00c, East St. Louis).

Stainless Steel

Representative prices, cents per pound; subject to current lists of extras

AISI Type	—Rerolling— Ingot	Slabs	Forging Billets	H.R. Strip	Wire Rods; C.F. Wire	Bars; Structural Shapes	Plates	Sheets	C.R. Strip; Flat Wire
201	22.00	27.00	....	36.00	....	42.00	44.25	48.50	45.00
202	23.75	30.25	36.50	39.00	40.75	43.00	45.00	49.25	49.25
301	23.25	28.00	37.25	37.25	42.00	44.25	46.25	51.25	47.50
302	25.25	31.50	38.00	40.50	42.75	45.00	47.25	52.00	52.00
302B	25.50	32.75	40.75	45.75	45.00	47.25	49.50	57.00	57.00
303	....	32.00	41.00	....	45.50	48.00	50.00	56.75	56.75
304	27.00	33.25	40.50	44.25	45.25	47.75	50.75	55.50	55.50
304L	....	....	48.25	51.50	53.00	55.50	58.50	63.25	63.25
305	28.50	36.75	42.50	47.50	45.25	47.75	51.25	58.75	58.75
308	30.75	38.25	47.25	50.25	52.75	55.75	60.25	63.00	63.00
309	39.75	49.50	57.75	64.50	63.75	67.00	71.00	80.50	80.50
310	49.75	61.50	78.00	84.25	86.50	91.00	92.75	96.75	96.75
314	....	....	....	....	86.50	....	92.75	....	104.50
316	39.75	49.50	62.25	69.25	69.25	73.00	76.75	81.50	81.50
316L	....	....	70.00	76.50	77.00	80.75	84.50	89.25	89.25
317	48.00	60.00	76.75	88.25	86.25	90.75	93.50	101.00	101.00
321	32.25	40.00	47.00	53.50	52.50	55.50	59.75	65.50	65.50
330	....	....	106.75	....	106.75	106.75	105.50	108.00	149.25
18-8 CbTa	37.00	46.50	55.75	63.50	61.50	64.75	69.75	79.25	79.25
403	....	....	32.00	....	35.75	37.75	40.25	48.25	48.25
405	19.50	25.50	29.75	36.00	33.50	35.25	37.50	46.75	46.75
410	16.75	21.50	28.25	31.00	32.00	33.75	35.00	40.25	40.25
416	....	....	28.75	....	32.50	34.25	36.25	48.25	48.25
420	....	33.50	34.25	41.75	39.25	41.25	45.25	62.00	62.00
430	17.00	21.75	28.75	32.00	32.50	34.25	36.00	40.75	40.75
430F	....	....	29.50	....	33.00	34.75	36.75	51.75	51.75
431	....	28.75	37.75	....	42.00	44.25	46.00	56.00	56.00
446	....	....	39.25	59.00	44.25	46.50	47.75	70.00	70.00

Stainless Steel Producers Are: Allegheny Ludlum Steel Corp.; American Steel & Wire Div., U. S. Steel Corp.; Anchor Drawn Steel Co., division of Vanadium-Alloys Steel Co.; Armco Steel Corp.; Babcock & Wilcox Co.; Bethlehem Steel Co.; J. Bishop & Co.; A. M. Byers Co.; G. O. Carlson Inc.; Carpenter Steel Co.; Charter Wire Products; Crucible Steel Co. of America; Damascus Tube Co.; Dearborn Div., Sharon Steel Corp.; Wilbur B. Driver Co.; Driver-Harris Co., Eastern Stainless Steel Corp.; Firth Sterling Inc.; Fort Wayne Metals Inc.; Green River Steel Corp., subsidiary of Jessop Steel Co.; Indiana Steel & Wire Co.; Ingersoll Steel Div., Borg-Warner Corp.; Ellwood Ivins Steel Tube Works Inc.; Jessop Steel Co.; Johnson Steel & Wire Co. Inc.; Jones & Laughlin Steel Corp.; Joslyn Stainless Steels, division of Joslyn Mfg. & Supply Co.; Latrobe Steel Co.; Lukens Steel Co.; Maryland Fine & Specialty Wire Co. Inc.; McInnes Steel Co.; McLouth Steel Corp.; Metal Forming Corp.; Midvale-Heppenstall Co.; National Standard Co.; National Tube Div., U. S. Steel Corp.; Pacific Tube Co.; Page Steel & Wire Div., American Chain & Cable Co. Inc.; Pittsburgh Rolling Mills Inc.; Republic Steel Corp.; Riverside-Alloy Metal Div., H. K. Porter Company Inc.; Rodney Metals Inc.; Sawhill Tubular Products Inc.; Sharon Steel Corp.; Simonds Saw & Steel Co.; Specialty Wire Co. Inc.; Standard Tube Co.; Superior Steel Corp.; Superior Tube Co.; Swepco Tube Corp.; Techalloy Co. Inc.; Timken Roller Bearing Co.; Trent Tube Co., subsidiary of Crucible Steel Co. of America; Tube Methods Inc.; Ulbrich Stainless Steels Inc.; U. S. Steel Corp.; Universal-Cyclops Steel Corp.; Vanadium-Alloys Steel Co.; Wall Tube & Metal Products Co.; Wallingford Steel Co., subsidiary of Allegheny Ludlum Steel Corp.; Washington Steel Corp.

Clad Steel

	Plates 5%	Plates Carbon Base 10%	Plates Carbon Base 15%	Plates Carbon Base 20%	Sheets Carbon Base 20%
Stainless					
302	....	....	....	....	37.50
304	34.70	37.95	42.25	46.70	40.00
304L	36.90	40.55	45.10	49.85	....
316	40.35	44.40	49.50	54.50	58.75
316L	45.05	49.35	54.70	60.10	....
316 Cb	47.30	53.80	61.45	69.10	....
321	36.60	40.05	44.60	49.30	47.25
347	38.25	42.40	47.55	52.80	57.00
405	28.60	29.85	33.35	36.85	....
410	28.15	29.55	33.10	36.70	....
430	28.30	29.80	33.55	37.25	....
Inconel	48.90	59.55	70.15	80.85	....
Nickel	41.65	51.95	62.30	72.70	....
Nickel, Low Carbon	41.95	52.60	63.30	74.15	....
Monel	43.35	53.55	63.80	74.05	....
Copper*	....	....	....	....	46.00

	Strip, Carbon Base —Cold Rolled— 10%	Both Sides
Copper*	33.95	40.25

*Deoxidized. Production points: Stainless-clad sheets, New Castle, Ind. I-4; stainless-clad plates, Claymont, Del. C22, Coatesville, Pa. L7, New Castle, Ind. I-4, and Washington, Pa. J3; nickel, inconel, monel-clad plates, Coatesville L7; copper-clad strip, Carnegie, Pa. S18.

Tool Steel

Grade	$ per lb	Grade	$ per lb
Regular Carbon	0.305	Cr-Hot Work	0.475
Extra Carbon	0.360	W-Cr Hot Work	0.500
Special Carbon	0.475	V-Cr Hot Work	0.520
Oil Hardening	0.475	Hi-Carbon-Cr	0.925

Grade by Analysis (%) W	Cr	V	Co	Mo	$ per lb
20.25	4.25	1.6	12.25	...	4.285
18.25	4.25	1	4.75	...	2.500
18	4	2	9	...	2.870
18	4	2	....	...	1.960
18	4	1	....	...	1.795
9	3.5	..	....	...	1.395
13.5	4	3	....	...	2.060
13.75	3.75	2	5	...	2.440
6.4	4.5	1.9	....	5	1.300
6	4	3	....	6	1.545
1.5	4	1	....	8.5	1.155

Tool steel producers include: A4, A8, B2, B8, C4, C9, C13, C18, F2, J3, L3, M14, S8, U4, V2, and V3.

Pig Iron

F.o.b. furnace prices in dollars per gross ton, as reported to STEEL. Minimum delivered prices are approximate a do not include 3% federal transportation tax.

	Basic	No. 2 Foundry	Malle-able	Besse-mer
Birmingham District				
AlabamaCity,Ala. R2	62.00	62.50	....	....
Birmingham R2	62.00	62.50‡	....	....
Birmingham U6	....	62.50‡	66.50	....
Woodward,Ala. W15	62.00**	62.50‡	66.50	....
Cincinnati, deld.	....	70.20	....	....
Buffalo District				
Buffalo H1, R2	66.00	66.50	67.00	67.50
N.Tonawanda,N.Y. T9	....	66.50	67.00	67.50
Tonawanda,N.Y. W12	66.00	66.50	67.00	67.50
Boston, deld.	77.29	77.79	78.29	....
Rochester,N.Y., deld.	69.02	69.52	70.02	....
Syracuse,N.Y., deld.	70.12	70.62	71.12	....
Chicago District				
Chicago I-3	66.00	66.50	66.50	67.00
S.Chicago,Ill. R2	66.00	....	66.50	....
S.Chicago,Ill. W14	66.00	....	66.50	67.00
Milwaukee, deld.	68.62	69.12	69.12	69.62
Muskegon,Mich., deld.	....	74.12	74.12	....
Cleveland District				
Cleveland R2, A7	66.00	66.50	66.50	67.00
Akron,Ohio, deld.	69.12	69.62	69.62	70.12
Mid-Atlantic District				
Birdsboro,Pa. B10	68.00	68.50	69.00	69.50
Chester,Pa. P4	66.50	67.00	67.50	....
Swedeland,Pa. A3	68.00	68.50	69.00	69.50
NewYork, deld.	....	75.10	75.60	....
Newark,N.J., deld.	72.29	72.79	73.29	73.79
Philadelphia, deld.	70.01	70.51	71.01	71.59
Troy,N.Y. R2	68.00	68.50	69.00	69.50
Pittsburgh District				
NevilleIsland,Pa. P6	66.00	66.50	66.50	67.00
Pittsburgh (N&S sides), Aliquippa, deld.	....	67.95	67.95	68.48
McKeesRocks,Pa., deld.	....	67.60	67.60	68.13
Lawrenceville,Homestead, Wilmerding,Monaca,Pa., deld.	....	68.26	68.26	68.79
Verona,Trafford,Pa., deld.	68.29	68.82	68.82	69.35
Brackenridge,Pa., deld.	68.60	69.10	69.10	69.63
Midland,Pa. C18	66.00	....	....	....
Youngstown District				
Hubbard,Ohio Y1	....	....	66.50	....
Sharpsville,Pa. S6	66.00	....	66.50	67.0
Youngstown Y1	....	....	66.50	67.0
Mansfield,Ohio, deld.	70.90	....	71.40	71.9
Duluth I-3	66.00	66.50	66.50	67.0
Erie,Pa. I-3	66.00	66.50	66.50	67.0
Everett,Mass. E1	67.50	68.00	68.50	....
Fontana,Calif. K1	75.00	75.50	....	....
Geneva,Utah C11	66.00	66.50	....	....
GraniteCity,Ill. G4	67.90	68.40	68.90	....
Ironton,Utah C11	66.00	66.50	....	....
Minnequa,Colo. C10	68.00	68.50	69.00	....
Rockwood,Tenn. T3	....	62.50‡	66.50	....
Toledo,Ohio I-3	66.00	66.50	66.50	67.0
Cincinnati, deld.	72.54	73.04	....	....

**Phos. 0.70-0.90%; Phos. 0.30-0.69%, $63.
‡Phos. 0.70-0.90%; Phos. 0.30-0.69%, $63.50.

PIG IRON DIFFERENTIALS

Silicon: Add 75 cents per ton for each 0.25% Si or percentage there over base grade, 1.75-2.25%, except on low phos. iron on which ba is 1.75-2.00%.
Manganese: Add 50 cents per ton for each 0.25% manganese over 1 or portion thereof.
Nickel: Under 0.50% no extra; 0.50-0.74%, inclusive, add $2 per t and each additional 0.25%, add $1 per ton.

BLAST FURNACE SILVERY PIG IRON, Gross Ton

(Base 6.00-6.50% silicon; add $1 for each 0.50% silicon or portio thereof over the base grade within a range of 6.50 to 11.50%; startin with silicon over 11.50% add $1.50 per ton for each 0.50% silicon portion thereof up to 14%; add $1 for each 0.50% Mn over 1%)

Jackson,Ohio I-3, J1	78.0
Buffalo H1	79.5

ELECTRIC FURNACE SILVERY IRON, Gross Ton

(Base 14.01-14.50% silicon; add $1 for each 0.5% Si to 18%; $1.25 fo each 0.50% Mn over 1%; $2 per gross ton premium for 0.045% max P

CalvertCity,Ky. P15	$99.0
NiagaraFalls,N.Y. P15	99.0
Keokuk,Iowa Open-hearth & Fdry, $9 freight alowed K2	103.5
Keokuk,Iowa O.H. & Fdry, 12½ lb piglets, 16% Si, max fr'gt allowed up to $9, K2	106.5

LOW PHOSPHORUS PIG IRON, Gross Ton

Lyles,Tenn. T3 (Phos. 0.035% max)	$78.5
Troy,N.Y. R2 (Phos. 0.035% max)	74.5
Philadelphia, deld.	82.2
Cleveland A7 (Intermediate) (Phos. 0.036-0.075% max)	71.0
Duluth I-3 (Intermediate) (Phos. 0.036-0.075% max)	71.0
Erie,Pa. I-3 (Intermediate) (Phos. 0.036-0.075% max)	71.0
NevilleIsland,Pa. P6 (Intermediate) (Phos. 0.036-0.075% max)	71.0

Warehouse Steel Products

Representative prices, per pound, subject to extras, f.o.b. warehouse. City delivery charges are 15 cents per 100 lb except: Molin Norfolk, Richmond, Washington, 20 cents; Baltimore, Boston, Los Angeles, New York, Philadelphia, Portland, Spokane, San Fran cisco, 10 cents: Atlanta, Chattanooga, Houston, Seattle, no charge.

	SHEETS			STRIP	BARS			Standard	PLATES	
	Hot-Rolled	Cold-Rolled	Gal. 10 Ga.†	Stainless Type 302	Hot-Rolled*	H.R. Rounds	C.F. Rds.‡	H.R. Alloy 4140††§	Structural Shapes	Carbon	Floor
Atlanta	8.59§	9.86§	....	....	8.64	9.01	10.68	....	9.05	8.97	10.90
Baltimore	8.28	8.88	9.61	....	8.76	9.06	11.34#	15.18	9.19	8.66	10.14
Birmingham	8.18	9.45	11.07	....	8.23	8.60	10.57	....	8.64	8.56	10.70
Boston	9.38	10.44	11.45	53.50	9.42	9.73	12.90#	15.28	9.63	9.72	11.20
Buffalo	8.40	9.00	10.07	55.98	8.50	8.80	10.90#	15.00	8.90	8.90	10.45
Chattanooga	8.35	9.69	9.65	....	8.40	8.77	10.46	....	8.88	8.80	10.66
Chicago	8.20	9.45	10.00	53.00	8.23	8.60	8.80	14.65	8.64	8.56	9.88
Cincinnati	8.34	9.48	10.05	52.43	8.54	8.92	9.31	14.96	9.18	8.93	10.21
Cleveland	8.18	9.45	9.95	55.68	8.33	8.69	10.80#	14.74	9.01	8.79	10.11
Dallas	8.85	10.15	....	....	9.00	8.95	11.01	....	9.00	9.45	10.70
Denver	9.38	11.75	....	....	9.41	9.78	11.10	....	9.82	9.74	11.06
Detroit	8.43	9.70	10.35	56.50	8.58	8.90	9.15	14.91	9.18	8.91	10.13
Erie, Pa.	8.20	9.45	9.95[10]	....	8.50	8.75	9.05[10]	....	9.00	8.85	10.10
Houston	8.45	9.75	8.45	....	8.60	8.55	11.10	....	8.60	9.05	10.30
Jackson, Miss.	8.52	9.79	....	....	8.57	8.94	10.68	....	8.97	8.90	10.74
Los Angeles	9.50	10.75	11.65	57.60	9.50	9.80	12.75	....	9.10	9.55	11.70
Milwaukee	8.33	9.58	10.13	....	8.36	8.73	9.03	14.78	8.85	8.69	10.01
Moline, Ill.	8.55	9.80	10.35	....	8.58	8.95	9.15	....	8.99	8.91	....
New York	8.87	10.13	10.56	53.08	9.31	9.57	12.76#	15.09	9.35	9.43	10.71
Norfolk, Va.	8.05	....	....	....	8.55	8.60	10.80	....	8.95	8.45	9.95
Philadelphia	8.00	8.90	9.87	51.94	8.69	8.65	11.51#	15.01	8.50	8.77	9.77[9]
Pittsburgh	8.18	9.45	10.35	52.00	8.33	8.60	10.80#	14.65	8.64	8.56	9.88
Portland, Oreg.	8.50	11.20	11.55	57.38	9.55	8.65	14.65#	15.95	8.65	8.30	11.50
Richmond, Va.	8.45	....	10.40	....	9.15	9.15	....	....	9.40	8.85	10.35
St. Louis	8.54	9.79	10.36	....	8.59	8.97	9.41	15.01	9.10	8.93	10.25
St. Paul	8.79	10.04	10.61	....	8.84	9.21	9.66	....	9.38	9.30	10.49
San Francisco	9.35	10.75	11.00	55.10	9.45	9.70	13.00	16.10	9.50	9.60	12.00
Seattle	9.95	11.15	12.00	57.38	10.00	10.10	14.05	16.35	9.80	9.70	12.10
South'ton, Conn.	9.07	10.33	10.71	....	9.48	9.74	....	....	9.57	9.57	10.91
Spokane	9.95	11.15	12.00	57.38	10.00	10.10	14.05	17.20	9.80	9.70	12.10
Washington	8.48	9.58	....	....	9.06	9.15	9.73	....	9.35	8.86	10.36

*Prices do not include gage extras; †prices include gage and coating extras; ‡includes 35-cent bar quality extras; §42 in. and under; **⅛ in and heavier; ††as annealed; ‡‡over 4 in.; §§over 3 in.; #1 in. round C-1018.

Base quantities, 2000 to 4999 lb except as noted; cold-rolled strip and cold-finished bars, 2000 lb and over except in Seattle, 2000 to 9999 lb, an in Los Angeles, 6000 lb and over; stainless sheets, 8000 lb except in Chicago, New York, Boston, Seattle, Portland, Oreg. 10,000 lb and in Sa Francisco, 2000 to 4999 lb; hot-rolled products on West Coast, 2000 to 9999 lb, except in Portland, Oreg., 1000 to 9999 lb; [8]—400 to 9999 lb; [5]— 1000 to 1999 lb; [8]—2000 to 3999 lb; [10]—2000 lb and over.

Refractories

Fire Clay Brick (per 1000)

High-Heat Duty: Ashland, Grahn, Hayward, Hitchins, Haldeman, Oliver Hill, Ky., Athens, Troup, Tex., Beech Creek, Clearfield, Curwensville, Lock Haven, Lumber, Orviston, West Decatur, Pa., Bessemer, Ala., Farber, Mexico, St. Louis, Vandalia, Mo., Ironton, Oak Hill, Parral, Portsmouth, Ohio, Ottawa, Ill., Stevens Pottery, Ga., $135; Salina, Pa., $140; Niles, Ohio, $138; Cutler, Utah, $165.

Super-Duty: Ironton, Ohio, Vandalia, Mo., Olive Hill, Ky., Clearfield, Salina, Pa., New Savage, Md., St. Louis, $175; Stevens Pottery, Ga., $185; Cutler, Utah, $233.

Silica Brick (per 1000)

Standard: Alexandria, Claysburg, Mt. Union, Sproul, Pa., Ensley, Ala., Pt. Matilda, Pa., Portsmouth, Ohio, Hawstone, Pa., $150; Warren, Niles, Windham, Ohio, Hays, Latrobe, Morrisville, Pa., $155; E. Chicago, Ind., Joliet, Rockdale, Ill., $160; Lehigh, Utah, $175; Los Angeles, $180.

Super-Duty: Sproul, Hawstone, Pa., Niles, Warren, Windham, Ohio, Leslie, Md., Athens, Tex., $157; Morrisville, Hays, Latrobe, Pa., $160; E. Chicago, Ind., $167; Curtner, Calif., $182.

Semisilica Brick (per 1000)

Clearfied, Pa., $140; Philadelphia, $137; Woodbridge, N. J., $135.

Ladle Brick (per 1000)

Dry Pressed: Alsey, Ill., Chester, New Cumberland, W. Va., Freeport, Johnstown, Merrill Station, Vanport, Pa., Mexico, Vandalia, Mo., Wellsville, Irondale, New Salisbury, Ohio, $96.75; Clearfield, Pa., Portsmouth, Ohio, $102.

High-Alumina Brick (per 1000)

50 *Per Cent:* St. Louis, Mexico, Vandalia, Mo., $235; Danville, Ill., $238; Philadelphia, Clearfield, Pa., $230; Orviston, Pa., $245.

60 *Per Cent:* St. Louis, Mexico, Vandalia, Mo., $295; Danville, Ill., $298; Philadelphia, Clearfield, Orviston, Pa., $305.

70 *Per Cent:* St. Louis, Mexico, Vandalia, Mo., $335; Danville, Ill., $338; Phiadelphia, Clearfield, Orviston, Pa., $345.

Sleeves (per 1000)

Reesdale, Johnstown, Bridgeburg, Pa., St. Louis, $188.

Nozzles (per 1000)

Reesdale, Johnstown, Bridgeburg, Pa., St. Louis, $310.

Runners (per 1000)

Reesdale, Johnstown, Bridgeburg, Pa., $234.

Dolomite (per net ton)

Domestic, dead-burned, bulk, Billmeyer, Blue Bell, Williams, Plymouth Meeting, York, Pa., Millville, W. Va., Bettsville, Millersville, Martin, Woodville, Gibsonburg, Narlo, Ohio, $16.75; Thornton, McCook, Ill., $17; Dolly Siding, Bonne Terre, Mo., $15.

Magnesite (per net ton)

Domestic, dead-burned, bulk ½ in. grains with fines: Chewelah, Wash., Luning, Nev., $46; ⅜ in. grains with fines: Baltimore, $73.

Fluorspar

Metallurgical grades, f.o.b. shipping point in Ill., Ky., net tons, carloads, effective CaF_2 content 72.5%, $37-41; 70%, $36.40; 60%, $33-36.50. Imported, net tons, f.o.b. cars point of entry, duty paid, metallurgical grade: European, $33-34; Mexican, all rail, duty paid, $25.25-25.75; barge, Brownsville, Tex., $27.25-27.75.

Ores

Lake Superior Iron Ore

(Prices effective for the 1957 shipping season, gross ton, 51.50% iron natural, rail of vessel, lower lake ports.)

Mesabi bessemer	$11.60
Mesabi nonbessemer	11.45
Old Range bessemer	11.85
Old Range nonbessemer	11.70
Open-hearth lump	12.70
High phos.	11.45

The foregoing prices are based on upper lake rail freight rates, lake vessel freight rates, handling and unloading charges, and taxes thereon, which were in effect Jan. 30, 1957, and increases or decreases after that date are absorbed by the seller.

Eastern Local Iron Ore

Cents per unit, deld. E. Pa.

New Jersey, foundry and basic 62-64% concentrates	25.00-27.00

Foreign Iron Ore

Cents per unit, c.i.f. Atlantic ports

Swedish basic, 65%	27.00-27.50
N. African hematite (spot)	nom.
Brazilian iron ore, 68-69%	28.00

Tungsten Ore

Net ton, unit

Foreign wolframite, good commercial quality	$13.00-14.00*
Domestic, concentrates f.o.b. milling points	20.00-22.00

*Before duty.

Manganese Ore

Mn 46-48%, Indian (export tax included), $1.39-1.42 per long ton unit, c.i.f. U. S. ports, duty for buyer's account: other than Indian, nomnial; contracts by negotiation.

Chrome Ore

Gross ton, f.o.b. cars New York, Philadelphia, Baltimore, Charleston, S. C., plus ocean freight differential for delivery to Portland, Oreg., Tacoma, Wash.

Indian and Rhodesian

48% 3:1	$51.00-53.00
48% 2.8:1	48.00-50.00
48% no ratio	41.00-43.00

South African Transvaal

48% no ratio	$40.00-41.00
44% no ratio	30.00-30.50

Turkish

48% 3:1	$55.00-57.00

Domestic

Rail nearest seller

18% 3:1	$39.00

Molybdenum

Sulfide concentrate, per lb of Mo content, mines, unpacked	$1.18

Antimony Ore

Per short ton unit of Sb content, c.i.f. seaboard

55-60%	$2.50-2.60
60-65%	2.60-2.90

Vanadium Ore

Cents per lb V_2O_5

Domestic	31.00

Metal Powder

(Per pound f.o.b. shipping point in ton lots for minus 100 mesh, except as noted)

	Cents
Sponge Iron, Swedish: Deld. east of Mississippi River, ocean bags 23,000 lb and over.. F.o.b. Riverton or Camden, N. J., west of Mississippi River.	10.50 9.50
Sponge Iron, Domestic, 98 + % Fe: Deld. east of Mississippi River, 23,000 lb and over F.o.b. Riverton, N. J., west of Mississippi River	10.50 9.50
Electrolytic Iron: Melting stock, 99.9% Fe, irregular fragments of ⅛ in. x 1.3 in.	28.00
Annealed, 99.5% Fe..	36.50
Unannealed (99 + % Fe)	36.00
Unannealed (99 + % Fe) (minus 325 mesh)	59.00
Powder Flakes (minus 16, plus 100 mesh)..	29.00
Carbonyl Iron: 98.1-99.9%, 3 to 20 microns, depending on grade, 93.00-290.00 in standard 200-lb containers; all minus 200 mesh.	
Aluminum: Atomized, 500 lb drum, freight allowed Carlots Ton lots	39.50 41.50
Antimony, 500 lb lots	42.00*
Brass, 5000-lb lots	31.30-38.40†
Bronze, 5000-lb lots	48.10-52.70†
Copper: Electrolytic Reduced	14.25* 14.25*
Lead	7.50*
Manganese: Minus 35 mesh .... Minus 100 mesh .... Minus 200 mesh	64.00 70.00 75.00
Nickel, unannealed	$1.065
Nickel-Silver, 5000-lb lots	49.20-61.30†
Phosphor-Copper, 5000-lb lots	59.80
Copper (atomized) 5000-lb lots	40.30-48.80‡
Silicon	47.50
Solder	7.00*
Stainless Steel, 304 ..	$1.02
Stainless Steel, 316 ..	$1.20
Tin	14.50*
Zinc, 5000-lb lots	17.50-30.70‡
Tungsten:	Dollars
Melting grade, 99% 60 to 200 mesh: 1000 lb and over .. Less than 1000 lb ..	3.15 3.30
Chromium, electrolytic 99.8% Cr min metallic basis	5.00

*Plus cost of metal. †Depending on composition. ‡Depending on mesh.

Electrodes

Threaded with nipple; unboxed, f.o.b. plant

GRAPHITE

Inches Diam	Inches Length	Per 100 lb
2	24	$60.75
2½	30	39.25
3	40	37.00
4	40	35.00
5⅛	40	34.75
6	60	31.50
7	60	28.25
8, 9, 10	60	28.00
12	72	26.75
14	60	26.75
16	72	25.75
17	60	26.25
18	72	26.25
20	72	25.25
24	84	26.00

CARBON

8	60	13.30
10	60	13.00
12	60	12.95
14	60	12.85
14	72	11.95
17	60	11.85
17	72	11.40
20	84	11.40
20	90	11.00
24	72, 84	11.25
24	96	10.95
30	84	11.05
40, 35	110	10.70
40	100	10.70

Metallurgical Coke

Price per net ton

Beehive Ovens

Connellsville, Pa., furnace	$14.75-15.75
Connellsville, Pa., foundry	18.00-18.50

Oven Foundry Coke

Birmingham, ovens	$28.85
Cincinnati, deld.	31.84
Buffalo, ovens	30.50
Camden, N. J., ovens	29.50
Detroit, ovens	30.50
Pontiac, Mich., deld.	32.25
Saginaw, Mich., deld.	33.83
Erie, Pa., ovens	30.50
Everett, Mass., ovens: New England, deld.	31.55*
Indianapolis, ovens	29.75
Ironton, Ohio, ovens	29.00
Cincinnati, deld.	31.84
Kearny, N. J., ovens	29.75
Milwaukee, ovens	30.50
Neville Island (Pittsburgh), Pa., ovens.	29.25
Painesville, Ohio, ovens	30.50
Cleveland, deld.	32.69
Philadelphia, ovens	29.50
St. Louis, ovens	31.50
St. Paul, ovens	29.75
Chicago, deld.	33.24
Swedeland, Pa., ovens	29.50
Terre Haute, Ind. ovens	29.75

*Or within $4.85 freight zone from works.

Imported Steel

(Base per 100 lb, landed, duty paid, based on current ocean rates. Any increase in these rates is for buyer's account. Source of shipment: Western continental European countries)

	North Atlantic	South Atlantic	Gulf Coast	West Coast
Deformed Bars, Intermediate, ASTM-A 305...	$6.28	$6.23	$6.23	$6.48
Bar Size Angles	6.62	6.57	6.57	6.75
Structural Angles	6.62	6.57	6.57	6.75
I-Beams	6.87	6.82	6.82	7.00
Channels	6.87	6.82	6.82	7.00
Plates (basic bessemer)	8.35	8.30	8.30	8.60
Sheets, H.R.	8.25	8.20	8.20	8.50
Sheets, C. R. (drawing quality)	9.00	8.95	8.95	9.25
Furring Channels, C.R., 1000 ft, ¾ x 0.30 lb per ft	26.79	26.67	26.67	27.36
Barbed Wire (†)	6.95	6.95	6.95	7.40
Merchant Bars	6.87	6.82	6.82	7.22
Hot-Rolled Bands	7.20	7.15	7.15	7.55
Wire Rods, Thomas Commercial No. 5	6.73	6.73	6.73	7.13
Wire Rods, O.H. Cold Heading Quality No. 5	7.07	7.07	7.07	7.47
Bright Common Wire Nails (§)	8.38	8.38	8.38	8.58

†Per 82 lb, net, reel. §Per 100-lb kegs, 20d nails and heavier.

Coal Chemicals

Spot, cents per gallon, ovens

Pure benzene	36.00
Toluene, one deg.	29.50
Industrial xylene	32.00-34.00

Per ton, bulk, ovens

Ammonium sulfate	$32.00-34.00

Cents per pound, producing point

Phenol: Grade 1, 17.50; Grade 2-3, 15.50; Grade 4, 17.50; Grade 5, 16.50; Grade 6, 14.50.

Ferroalloys

MANGANESE ALLOYS

Spiegeleisen: Carlot, per gross ton, Palmerton, Pa. 21-23% Mn, $105; 19-21% Mn, 1-3% Si, $102.50; 16-19% Mn, $100.50.

Standard Ferromanganese: (Mn 74-76%, C 7% approx). Base price per net ton; $245, Johnstown, Duquesne, Sheridan, Pa.; Alloy, W. Va.; Ashtabula, Marietta, O.; Sheffield, Ala.; Portland, Oreg. Add or subtract $2 for each 1% or fraction thereof of contained manganese over 76% or under 74% respectively.

(Mn 79-81%). Lump $263 per net ton, f.o.b. Anaconda or Great Falls, Mont. Add $2.60 for each 1% above 81%; subtract $2.60 for each 1% below 79%, fractions in proportion to nearest 0.1%.

High-Grade Low-Carbon Ferromanganese: (Mn 85-90%). Carload, lump, bulk, max 0.07% C, 35.1c per lb of contained Mn, carload packed 36.4c, ton lots 37.9c, less ton 39.1c. Delivered. Deduct 1.5c for max 0.15% C grade from above prices, 3c for max 0.03% C, 3.5c for max 0.50% C, and 6.5c for max 75% C—max 7% Si. **Special Grade:** (Mn 90% min, C 0.07% max, P 0.06% max). Add 2.05c to the above prices. Spot, add 0.25c.

Medium-Carbon Ferromanganese: (Mn 80-85%, C 1.25-1.5%, Si 1.5% max). Carload, lump, bulk, 25.5c per lb of contained Mn, packed, carload 26.8c, ton lot 28.4c, less ton 29.6c. Delivered, Spot, add 0.25c.

Manganese Metal: 2" x D (Mn 95.5% min, Fe 2% max, Si 1% max, C 0.2%). Carload, lump, bulk, 45c per lb of metal; packed, 45.75c; ton lot 47.25c; less ton lot 49.25c. Delivered. Spot, add 2c.

Electrolytic Manganese Metal: Min carload, 34c; 2000 lb to min carload, 36c; 500 lb to 1999 lb, 38c; 50 lb cans, add 0.5c per lb. Premium for hydrogen-removed metal, 0.75c per lb. Prices are f.o.b. cars, Knoxville, Tenn., freight allowed to St. Louis or any point east of Mississippi; or f.o.b. Marietta, O., freight allowed.

Silicomanganese: (Mn 65-68%). Contract, lump, bulk 1.50% C grade, 18-20% Si, 12.8c per lb of alloy. Packed, c.l. 14c, ton 14.45c, less ton 15.45c, f.o.b. Alloy, W. Va.; Ashtabula, Marietta, O.; Sheffield, Ala.; Portland, Oreg. For 2% C grade, Si 15-17%, deduct 0.2c from above prices. For 3% C grade Si 12-14.5%, deduct 0.4c from above prices. Spot, add 0.25c.

TITANIUM ALLOYS

Ferrotitanium, Low-Carbon: (Ti 20-25%, Al 3.5% max, Si 4% max, C 0.10% max). Contract, ton lot, 2" x D, $1.50 per lb of contained Ti; less ton $1.55. (Ti 38-43%, Al 8% max, Si 4% max, C 0.10% max). Ton lot $1.35, less ton $1.37, f.o.b. Niagara Falls, N. Y., freight allowed to St. Louis. Spot, add 5c.

Ferrotitanium, High-Carbon: (Ti 15-18%, C 6-8%). Contract $200 per ton, f.o.b. Niagara Falls, N. Y., freight allowed to destinations east of Mississippi River and north of Baltimore and St. Louis.

Ferrotitanium, Medium-Carbon: (Ti 17-21%, C 2-4.5%). Contract $225 per ton, f.o.b. Niagara Falls, N. Y., freight not exceeding St. Louis rate allowed.

CHROMIUM ALLOYS

High-Carbon Ferrochrome: Contract, c.l. lump, bulk 28.75c per lb of contained Cr; c.l. packed 30.30c, ton lot 32.05c; less ton 33.45c. Delivered. Spot, add 0.25c.

Low-Carbon Ferrochrome: Cr 63-66% (Simplex), carload, lump, bulk. C 0.025% max, 36.75c per lb contained Cr; 0.010% max, 37.75c. Ton lot, add 3.5c; less ton, add 5.2c. Delivered.

Cr 67.71%, carload, lump, bulk, C 0.02% max, 41.00c per lb contained Cr; 0.025% max, 39.75c; 0.05% max, 39.00c; 0.10% max, 38.50c; 0.20% max, 38.25c; 0.50% max, 38.00c; 1.0% max, 37.75c; 1.5% max, 37.50c; 2.0% max, 37.25c. Ton lot, add 3.4c; less ton lot, add 5.1c. Delivered.

Foundry Ferrochrome, High-Carbon: (Cr 62-66%, C 5-7%, Si 7-10%). Contract, c.l., 2 in. x D, bulk 30.05c per lb of contained Cr. Packed, c.l. 31.65c, ton 33.45c, less ton 34.95c. Delivered. Spot, add 0.25c.

Foundry Ferrosilicon Chrome: (Cr 50-54%, Si 28-32%, C 1.25% max). Contract, carload, packed, 8M x D, 21.25c, per lb of alloy, ton lot 22.50c; less ton lot 23.70c. Delivered. Spot, add 0.25c.

Ferrochrome-Silicon: Cr 39-41%, Si 42-45%, C 0.05% max or Cr 33-36%, Si 45-48%, C 0.05% max. Carload, lump, bulk. 3" x down and 2" x down, 27.50c per lb contained Cr, 14.20c per lb contained Si. 0.75" x down, 28.65c per lb contained Cr, 14.20c per lb contained Si. Delivered.

Chromium Metal Electrolytic: Commercial grade (Cr 99.8% min, metallic basis, Fe 0.2% max). Contract, carlot, packed 2" x D plate (about ⅛" thick) $1.29 per lb, ton lot $1.31, less ton lot $1.33. Delivered. Spot, add 5c.

VANADIUM ALLOYS

Ferrovanadium: Open-hearth grade (V 50-55%, Si 8% max, C 3% max). Contract, any quantity, $3.20 per lb of contained V. Delivered. Spot, add 10c. **Special Grade:** (V 50-55% or 70-75%, Si 2% max, C 0.5% max) $3.30. **High Speed Grade:** (V 50-55%, or 70-75%, Si 1.50% max, C 0.20% max) $3.40.

Grainal: Vanadium Grainal No. 1 $1.05 per lb; No. 6, 68c; No. 79, 50c, freight allowed.

Vanadium Oxide: Contract less carload lot, packed $1.38 per lb contained V_2O_5, freight allowed. Spot, add 5c.

SILICON ALLOYS

25-30% Ferrosilicon: Contract, carload, lump, bulk, 20.0c per lb of contained Si. Packed 21.40c; ton lot 22.50c, f.o.b. Niagara Falls, N. Y., freight not exceeding St. Louis rate allowed.

50% Ferrosilicon: Contract, carload, lump, bulk, 14.20c per lb of contained Si. Packed c.l. 16.70c, ton lot 18.15c, less ton 19.80c, f.o.b. Alloy, W. Va.; Ashtabula, Marietta, O.; Sheffield, Ala.; Portland, Oreg. Spot, add 0.45c.

Low-Aluminum 50% Ferrosilicon: (Al 0.40% max). Add 1.45c to 50% ferrosilicon prices.

65% Ferrosilicon: Contract, carload, lump, bulk, 15.25c per lb contained silicon. Packed, c.l. 17.25c, ton lot 19.05c; less ton 20.4c. Delivered. Spot, add 0.35c.

75% Ferrosilicon: Contract, carload, lump, bulk, 16.4c per lb of contained Si. Packed, c.l. 18.30c, ton lot 19.95c, less ton 21.2c. Delivered. Spot, add 0.3c.

90% Ferrosilicon: Contract, carload, lump, bulk, 19.5c per lb of contained Si. Packed, c.l. 21.15c, ton lot 22.55c, less ton 23.6c. Delivered. Spot, add 0.25c.

Silicon Metal: (98% min Si, 0.75% max Fe, 0.07% max Ca). C.l. lump, bulk, 22.00c per lb of Si. Packed, c.l. 23.65c, ton lot 24.95c, less ton 25.95c. Add 0.5c for max 0.03% Ca grade. Deduct 0.5c for max 1% Fe grade analyzing min 99.75% Si; 0.75c for max 1.25% Fe grades analyzing min 96.75% Si. Spot, add 0.25c.

Alsifer: (Approx 20% Al, 40% Si, 40% Fe). Contract, basis f.o.b. Niagara Falls, N. Y., lump, carload, bulk, 10.65c per lb of alloy; ton lot, packed, 11.8c.

ZIRCONIUM ALLOYS

12-15% Zirconium Alloy: (Zr 12-15%, Si 39-43%, C 0.20% max). Contract, c.l. lump, bulk 9.25c per lb of alloy. Packed, c.l. 10.45c, ton lot 11.6c, less ton 12.45c. Delivered. Spot, add 0.25c.

35-40% Zirconium Alloy: (Zr 35-40%, Si 47-52%, Fe 8-12%, C 0.50% max). Contract, carload, lump, packed 27.25c per lb of alloy, ton lot 28.4c, less ton 29.65c. Freight allowed. Spot, add 0.25c.

BORON ALLOYS

Ferroboron: (B 17.50% min, Si 1.50% max, Al 0.50% max, C 0.50% max). Contract, 100 lb or more 1" x D, $1.20 per lb of alloy; less than 100 lb $1.30. Delivered. Spot, add 5c. F.o.b. Washington, Pa., prices, 100 lb and over, are as follows: Grade A (10-14% B) 85c per lb; Grade B (14-18% B) $1.20; Grade C (19% min B) $1.50.

Borosil: (3 to 4% B, 40 to 45% Si). Carload, bulk, lump, or 3" x D, $5.25 per lb of contained B. Packed, carload $5.40, ton to c.l. $5.50, less ton $5.60. Delivered.

Bortam: (B 1.5-1.9%). Ton lot, 45c per lb; less than ton lot, 50c per lb.

Carbortam: (1 to 2%). Contract, lump, carload 9.50c, per lb f.o.b. Suspension Bridge, N. Y., freight allowed same as high-carbon ferrotitanium.

CALCIUM ALLOYS

Calcium-Manganese-Silicon: (Ca 16-20%, Mn 14-18% and Si 53-59%). Contract, carload lump, bulk 23c per lb of alloy, carload packed 24.25c, ton lot 26.15c, less ton 27.15c. Delivered. Spot, add 0.25c.

Calcium-Silicon: (Ca 30-33%, Si 60-65%, Fe 1.5-3%). Contract, carload, lump, bulk 24c per lb of alloy, carload packed 25.65c, ton lot 27.95c, less ton 29.45c. Delivered. Spot, add 0.25c.

BRIQUETTED ALLOYS

Chromium Briquets: (Weighing approx 3½ lb each and containing 2 lb of Cr). Contract carload, bulk 19.60c per lb of briquet, carload packed in box pallets 19.80c, in bags 20.70c; 3000 lb to c.l. in box pallets 21.00c; 2000 lb to c.l. in bags, 21.90c; less than 2000 lb in bags 22.80c. Delivered. Add 0.25c for notching. Spot, add 0.25c.

Ferromanganese Briquets: (Weighing approx 3 lb and containing 2 lb of Mn). Contract carload, bulk 14.8c per lb of briquet; c.l. packed, pallets 15c, bags 16c; 3000 lb to c.l. pallets 16.2c; 2000 lb to c.l. bags, 17.2c; less ton 18.1c. Delivered. Add 0.25c for notching. Spot, add 0.25c.

Silicomanganese Briquets: (Weighing approx 3½ lb and containing 2 lb of Mn and approx ½ lb of Si). Contract, c.l. bulk 15.1c per lb of briquet; c.l. packed, pallets, 15.3c; bags 16.3c, 3000 lb to c.l., pallets, 16.5c; 2000 lb to c.l., bags 17.5c; less ton 18.4c. Delivered. Add 0.25c for notching. Spot, add 0.25c.

Silicon Briquets: (Large size—weighing approx 5 lb and containing 2 lb of Si). Contract, carload, bulk 7.7c per lb of briquet; packed, pallets, 7.9c; bags 8.9c; 3000 lb to c.l., pallets 9.5c; 2000 lb to c.l. bags 10.5c; less ton 11.4c. Delivered. Spot, add 0.25c. (Small size—weighing approx 2½ lb and containing 1 lb of Si). Carload, bulk 7.85c. Packed, pallets 8.05c; bags 9.05c; 3000 lb to c.l. pallets 9.65c; 2000 lb to c.l. bags 10.65c; less ton 11.55c. Delivered. Add 0.25c for notching, small size only. Spot, add 0.25c.

Molybdic-Oxide Briquets: (Containing 2½ lb of Mo each). $1.41 per pound of Mo contained, f.o.b. Langeloth, Pa.

TUNGSTEN ALLOYS

Ferrotungsten: (70-80%), 5000 lb W or more $2.95 per lb of contained W; 2000 lb W to 5000 lb W, $3.05; less than 2000 lb W, $3.17. Delivered.

OTHER FERROALLOYS

Ferrocolumbium: (Cb 50-60%, Si 8% max, C 0.4% max). Contract, ton lot 2" x D, $4.90 per lb of contained Cb. Delivered. Spot, add 10c.

Ferrotantalum—Columbium: (Cb 40% approx, Ta 20% approx, and Cb plus Ta 60% min, C 0.30% max). Ton lot 2" x D, $4.25 per lb of contained Cb plus Ta, delivered; less ton lot $4.30.

SMZ Alloy: (Si 60-65%, Mn 5-7%, Zr 5.7%, Fe 20% approx). Contract, c.l. packed ½-in. x 12 M 20.00c per lb of alloy, ton lot 21.15c, less ton 22.40c. Delivered. Spot, add 0.25c.

Graphidox No. 5: (Si 48-52%, Ca 5-7%, Ti 9-11%). C.l. packed, 19c per lb of alloy, ton lot 20.15c; less ton lot 21.4c, f.o.b. Niagara Falls, N. Y.; freight allowed to St. Louis.

V-5 Foundry Alloy: (Cr 38-42%, Si 17-19%, Mn 8-11%). C.l. packed 18.1c per lb of alloy; ton lot 19.55c; less ton lot 20.8c, f.o.b. Niagara Falls, N. Y., freight allowed to St. Louis.

Simanal: (Approx 20% each Si, Mn, Al; bal Fe). Lump, carload, bulk 18.50c. Packed c.l. 19.50c, 2000 lb to c.l. 20.50c, less than 2000 lb 21c per lb of alloy. Delivered.

Ferrophosphorus: (23-25% based on 24% P content with unitage of $4 for each 1% of P above or below the base); carload, f.o.b. sellers' works. Mt. Pleasant, Sigio, Tenn., $110 per gross ton.

Ferromolybdenum: (55-75%). Per lb of contained Mo, in 200-lb container, f.o.b. Langeloth and Washington, Pa. $1.68 in all sizes except powdered which is $1.74.

Technical Molybdic-Oxide: Per lb of contained Mo, in cans, $1.39; in bags, $1.38, f.o.b. Langeloth and Washington, Pa.



Scrap Prices Resuming Downtrend

Market stability is short-lived. STEEL's composite on the prime steelmaking grade declines 17 cents to $33 after holding unchanged the preceding week

Scrap Prices, Page 158

Philadelphia—Steel scrap buying is light and spotty, but prices are stabilized following the steady decline of recent weeks. No. 1 heavy melting is $33.50, with No. 1 bundles and busheling $1 higher. Electric furnace bundles are moving in small lots at $37, delivered. Scrap is not coming out in normal volume. Buying for export is slow. One vessel is loading tonnage bought some weeks back.

New York — Brokers' buying prices are steadier, and the movement of scrap against new orders is light. Borings and turnings are noticeably slow; so are the cast grades, with No. 1 cupola quoted at $38-$39, shipping point. Yards are not taking in their usual tonnage at the current low prices.

Including 1500 tons, No. 1 heavy melting steel, Panama Canal Co., closes Jan. 10 on 3200 net tons of steel scrap.

Chicago—Steel scrap prices here continue to sag, and important grades are off about $1 a ton on the average. Every market factor is of deflationary nature. Lack of consumer buying is the principal factor; it stems from a slowly declining steelmaking rate.

Inventories are substantial, and there is no interest in enlarging them. Hot metal is used more generously since blast furnace production exceeds demand for iron. Plenty of scrap is available. Depressing the market even farther is the fact that only a declining steelmaking rate is in prospect for the remainder of this year.

Pittsburgh—Several scrap dealers report improvement in number of inquiries, indicating customers are taking more interest in present prices. Inventory correction has not been completed; and it's unlikely that there will be any major purchases by leading consumers the rest of the year. But market observers think the price slump has largely been completed. Prices of No. 2 heavy melting and No. 2 bundles are firming slightly.

Cleveland—Pending the outcome of bids on automotive lists at the end of November, scrap marked time last week. Heavy auto tonnage is before the market, one seller offering 40,000 tons. Quoted prices are largely nominal. Factory bundles are off $1 on a number of broker bids on auto lists.

Detroit—Scrap sellers here have a pessimistic outlook. Dealers and brokers think prices will continue to drop following month-end closings on the auto lists. Brokers who bought for speculative purposes are particularly concerned. They'll have to pay personal property tax on scrap in their yards on Dec. 31. It is apt to depress the market more as brokers seek to unload at any price before the deadline.

Cincinnati — Prices are off another $1 here in anticipation of lower bids on industrial lists. It is expected that heavy tonnages will be offered by the auto plants at month's end.

St. Louis—Scrap continues dull with mills and foundries disinterested in purchases. Volume business is too low to make any price quotations firm.

Consumers' inventories are substantial in the light of current operating rates. Industrial scrap is coming out in better volume, but rural supplies are drying up.

Buffalo—Buying is almost completely lacking in the local scrap market. Prices are holding but the market undertone is soft. Deal-

(*Please turn to Page* 163)

WARD STEEL CO.
We specialize in FINISHED STEEL BARS—TUBES—STRIP
PROMPT WAREHOUSE SERVICE ONLY
Most Complete Stock in America of BLUE TEMPERED SPRING STEEL
We believe that the way to sell is to carry a stock which permits satisfying any reasonable warehouse demand.
87A Rindge Ave. Ext. Phone UN 4-2460
CAMBRIDGE 40, MASS.
Branch:
3042-3058 W. 51st Street, CHICAGO, ILL.
Phone: Grovehill 6-2600

Iron and Steel Scrap

Consumer prices per gross ton, except as otherwise noted, including broker's commission, as reported t
STEEL, Nov. 27, 1957. *Changes shown in italics.*

STEELMAKING SCRAP COMPOSITE

Nov. 27	$33.00
Nov. 20	33.17
Oct. Avg.	37.37
Nov. 1956	61.83
Nov. 1952	43.00

Based on No. 1 heavy melting grade at Pittsburgh, Chicago, and eastern Pennsylvania.

PITTSBURGH

No. 1 heavy melting	33.00-34.00
No. 2 heavy melting	*31.00-32.00*
No. 1 factory bundles	36.00-37.00
No. 1 dealer bundles	33.00-34.00
No. 2 bundles	*29.00-30.00*
No. 1 busheling	33.00-34.00
Machine shop turnings	17.00-18.00
Mixed borings, turnings	17.00-18.00
Short shovel turnings	20.00-21.00
Cast iron borings	20.00-21.00
Cut structurals:	
2 ft and under	*37.00-38.00*
3 ft lengths	*36.00-37.00*
Heavy turnings	30.00-31.00
Punchings & plate scrap	*36.00-37.00*
Electric furnace bundles	*36.00-37.00*

Cast Iron Grades

No. 1 cupola	41.00-42.00
Stove plate	35.00-36.00
Unstripped motor blocks	28.00-29.00
Clean auto cast	44.00-45.00
Drop broken machinery	53.00-54.00

Railroad Scrap

No. 1 R.R. heavy melt.	*36.00-37.00*
Rails, 2 ft and under	*56.00-57.00*
Rails, 18 in. and under	*57.00-58.00*
Angles, splice bars	*50.00-51.00*
Rails, rerolling	*56.00-57.00*

Stainless Steel Scrap

18-8 bundles & solids	210.00-215.00
18-8 turnings	115.00-120.00
430 bundles & solids	95.00-100.00
430 turnings	50.00-55.00

CLEVELAND

No. 1 heavy melting	28.00-29.00
No. 2 heavy melting	22.00-23.00
No. 1 factory bundles	*30.00-31.00*
No. 1 bundles	28.00-29.00
No. 2 bundles	19.00-20.00
No. 1 busheling	28.00-29.00
Machine shop turnings	11.00-12.00
Short shovel turnings	15.00-16.00
Mixed borings, turnings	15.00-16.00
Cast iron borings	15.00-16.00
Cut foundry steel	33.00-34.00
Cut structurals, plates 2 ft and under	35.00-36.00
Low phos. punchings & plate	29.00-30.00
Alloy free, short shovel turnings	21.00-22.00
Electric furnace bundles	29.00-30.00

Cast Iron Grades

No. 1 cupola	38.00-39.00
Charging box cast	33.00-34.00
Heavy breakable cast	29.00-30.00
Stove plate	36.00-37.00
Unstripped motor blocks	23.00-24.00
Brake shoes	30.00-31.00
Clean auto cast	37.00-38.00
Burnt cast	28.00-29.00
Drop broken machinery	40.00-41.00

Railroad Scrap

No. 1 R.R. heavy melt.	32.00-33.00
R.R. malleable	49.00-50.00
Rails, 2 ft and under	55.00-56.00
Rails, 18 in. and under	56.00-57.00
Rails, random lengths	48.00-49.00
Cast steel	43.00-44.00
Railroad specialties	46.00-47.00
Uncut tires	39.00-40.00
Angles, splice bars	46.00-47.00
Rails, rerolling	54.00-55.00

Stainless Steel
(Brokers' buying prices; f.o.b. shipping point)

18-8 bundles, solids	205.00-210.00
18-8 turnings	90.00-95.00
430 clips, bundles, solids	75.00-80.00
430 turnings	40.00-50.00

YOUNGSTOWN

No. 1 heavy melting	31.00-32.00
No. 2 heavy melting	24.00-25.00
No. 1 bundles	31.00-32.00
No. 2 bundles	24.00-25.00
No. 1 busheling	31.00-32.00
Machine shop turnings	13.00-14.00
Short shovel turnings	17.00-18.00
Cast iron borings	17.00-18.00
Low phos.	33.00-34.00
Electric furnace bundles	33.00-34.00

Railroad Scrap

No. 1 R.R. heavy melt.	35.00-36.00

CHICAGO

No. 1 heavy melt., indus.	*33.00-34.00*
No. 1 hvy melt., dealer	30.00-31.00
No. 2 heavy melting	29.00-30.00
No. 1 factory bundles	*35.00-36.00*
No. 1 dealer bundles	*30.00-31.00*
No. 2 bundles	20.00-21.00
No. 1 busheling, indus.	*33.00-34.00*
No. 1 busheling dealer	30.00-31.00
Machine shop turnings	16.00-17.00
Mixed borings, turnings	18.00-19.00
Short shovel turnings	18.00-19.00
Cast iron borings	18.00-19.00
Cut structurals, 3 ft.	*38.00-39.00*
Punchings & plate scrap	*39.00-40.00*

Cast Iron Grades

No. 1 cupola	35.00-36.00
Stove plate	*33.00-34.00*
Unstripped motor blocks	27.00-28.00
Clean auto cast	*39.00-40.00*
Drop broken machinery	*39.00-40.00*

Railroad Scrap

No. 1 R.R. heavy melt.	*35.00-36.00*
R.R. malleable	45.00-46.00
Rails, 2 ft and under	*48.00-49.00*
Rails, 18 in. and smaller	*49.00-50.00*
Angles, splice bars	46.00-47.00
Axles	*48.00-49.00*
Rails, rerolling	*47.00-49.00*

Stainless Steel Scrap

18-8 bundles & solids	205.00-215.00
18-8 turnings	105.00-115.00
430 turnings & solids	80.00-90.00
430 turnings	50.00-55.00

DETROIT

(Brokers' buying prices; f.o.b. shipping point)

No. 1 heavy melting	21.00-22.00
No. 2 heavy melting	18.00-19.00
No. 1 bundles	23.00-24.00
No. 2 bundles	18.00-19.00
No. 1 busheling	21.00-22.00
Machine shop turnings	8.00-9.00
Mixed borings, turnings	9.00-10.00
Short shovel turnings	10.00-11.00
Punchings & plate scrap	27.00-28.00

Cast Iron Grades

No. 1 cupola	31.00
Stove plate	25.00
Charging box cast	25.00
Heavy breakable	24.00
Unstripped motor blocks	15.00†
Clean auto cast	33.00
Malleable	34.00†

†Nominal

ST. LOUIS

(Brokers' buying prices)

No. 1 heavy melting	37.00
No. 2 heavy melting	34.00
No. 1 bundles	37.00
No. 2 bundles	26.00
No. 1 busheling	37.00
Machine shop turnings	17.00
Short shovel turnings	19.00

Cast Iron Grades

No. 1 cupola	43.00
Charging box cast	35.00
Heavy breakable cast	35.00
Unstripped motor blocks	35.00
Brake shoes	40.00
Clean auto cast	43.00
Stove plate	38.00

Railroad Scrap

No. 1 R.R. heavy melt.	*36.25*
Rails, 18 in. and under	50.00
Rails, random lengths	45.00
Rails, rerolling	*51.00*
Angles splice bars	47.00

PHILADELPHIA

No. 1 heavy melting	33.50
No. 2 heavy melting	30.50
No. 1 bundles	34.50
No. 2 bundles	24.50
No. 1 busheling	34.50
Electric furnace bundles	37.00
Mixed borings, turnings	22.50
Short shovel turnings	24.00
Machine shop turnings	22.00†
Heavy turnings	30.50
Structurals & plate	42.00-43.00
Couplers, springs, wheels	46.00
Rail crops, 2 ft & under	63.00-65.00

Cast Iron Grades

No. 1 cupola	39.00
Heavy breakable cast	38.00
Malleable	57.00
Drop broken machinery	50.00-51.00

†Nominal

NEW YORK

(Brokers' buying prices)

No. 1 heavy melting	33.50
No. 2 heavy melting	29.00-30.00
No. 1 bundles	33.50
No. 2 bundles	21.00-22.00
Machine shop turnings	11.00-12.00
Mixed borings, turnings	13.00-14.00
Short shovel turnings	15.00-16.00
Low phos. (structurals & plate)	45.00-46.00

Cast Iron Grades

No. 1 cupola	38.00-39.00
Unstripped motor blocks	32.00
Heavy breakable	33.00-34.00

Stainless Steel

18-8 sheets, clips, solids	160.00-165.00
18-8 borings, turnings	55.00-60.00
430 sheets, clips, solids	65.00-70.00
410 sheets, clips, solids	55.00-60.00

BOSTON

(Brokers' buying prices; f.o.b. shipping point)

No. 1 heavy melting	23.00-24.00
No. 2 heavy melting	20.00-21.00
No. 1 bundles	23.00-24.00
No. 2 bundles	12.50-14.00
No. 1 busheling	23.00-24.00
Machine shop turnings	10.00-11.00
Mixed borings, turnings	11.00-12.00
Short shovel turnings	12.00-13.00
No. 1 cast	33.00-34.00
Mixed cupola cast	28.00-29.00
No. 1 machinery cast	35.00-36.00

BUFFALO

No. 1 heavy melting	32.00-33.00
No. 2 heavy melting	29.00-30.00
No. 1 bundles	32.00-33.00
No. 2 bundles	27.00-28.00
No. 1 busheling	32.00-33.00
Mixed borings, turnings	18.00-19.00
Machine shop turnings	16.00-17.00
Short shovel turnings	20.00-21.00
Cast iron borings	18.00-19.00
Low phos.	37.00-38.00

Cast Iron Grades
(F.o.b. shipping point)

No. 1 cupola	*37.00-38.00*
No. 1 machinery	*42.00-43.00*

Railroad Scrap

Rails, random lengths	44.00-45.00
Rails, 3 ft and under	51.00-52.00
Railroad specialties	37.00-38.00

CINCINNATI

(Brokers' buying prices; f.o.b. shipping point)

No. 1 heavy melting	*29.00-30.00*
No. 2 heavy melting	*24.00-25.00*
No. 1 bundles	*29.00-30.00*
No. 2 bundles	20.00-21.00
No. 1 busheling	*29.00-30.00*
Machine shop turnings	*14.00-15.00*
Mixed borings, turnings	*17.00-18.00*
Short shovel turnings	*17.00-18.00*
Cast iron borings	*17.00-18.00*
Low phos. 18 in.	*36.00-37.00*

Cast Iron Grades

No. 1 cupola	35.00-36.00
Heavy breakable cast	32.00-33.00
Charging box cast	32.00-33.00
Drop broken machinery	47.00-48.00

Railroad Scrap

No. 1 R.R. heavy melt.	34.00-35.00
Rails, 18 in. and under	54.00-55.00
Rails, random lengths	44.00-45.00

BIRMINGHAM

No. 1 heavy melting	31.00-32.00
No. 2 heavy melting	26.00-27.00
No. 1 bundles	31.00-32.00
No. 2 bundles	16.00-17.00
No. 1 busheling	31.00-32.00
Cast iron borings	15.00-16.00
Short shovel turnings	21.00-22.00
Machine shop turnings	20.00-21.00
Bar crops and plates	38.00-39.00
Structurals & plate	38.00-39.00
Electric furnace bundles	35.00-36.00
Electric furnace:	
3 ft and under	33.00-34.00
2 ft and under	34.00-35.00

Cast Iron Grades

No. 1 cupola	47.00-48.00
Stove plate	47.00-48.00
Unstripped motor blocks	35.00-36.00
Charging box cast	22.00-23.00
No. 1 wheels	37.00-38.00

Railroad Scrap

No. 1 R.R. heavy melt.	34.00-35.00
Rails, 18 in. and under	49.00-50.00
Rails, rerolling	50.00-51.00
Rails, random lengths	41.00-42.00
Angles, splice bars	40.00-41.00

SEATTLE

No. 1 heavy melting	*34.00*
No. 2 heavy melting	*32.00*
No. 1 bundles	*33.00*
No. 2 bundles	*25.00*
Machine shop turnings	26.00
Mixed borings, turnings	26.00
Electric furnace No. 1	46.00

Cast Iron Grades

No. 1 cupola	35.00†
Heavy breakable cast	32.00†
Unstripped motor blocks	27.00†
Stove plate (f.o.b. plant)	25.00†

†Nominal

LOS ANGELES

No. 1 heavy melting	39.00
No. 2 heavy melting	37.00
No. 1 bundles	38.00
No. 2 bundles	30.00
Machine shop turnings	20.00
Shoveling turnings	25.00
Cast iron borings	25.00
Cut structurals and plate 1 ft and under	54.00

Cast Iron Grades
(F.o.b. shipping point)

No. 1 cupola	52.00

Railroad Scrap

No. 1 R.R. heavy melt.	39.00

SAN FRANCISCO

No. 1 heavy melting	36.00
No. 2 heavy melting	34.00
No. 1 bundles	34.00
No. 2 bundles	26.00
Machine shop turnings	20.00
Mixed borings, turnings	20.00
Cast iron borings	20.00
Heavy turnings	20.00
Short shovel turnings	20.00
Cut structurals, 3 ft	48.00

Cast Iron Grades

No. 1 cupola	47.00
Charging box cast	40.00
Stove plate	39.00
Heavy breakable cast	38.00
Unstripped motor blocks	36.00
Clean auto cast	47.00
No. 1 wheels	40.00
Drop broken machinery	47.00

HAMILTON, ONT.

No. 1 heavy melting	35.00
No. 2 heavy melting	30.00
No. 1 bundles	35.00
No. 2 bundles	25.00
Mixed steel scrap	30.00
Mixed borings, turnings	20.00
Busheling, new factory:	
Prepared	35.00
Unprepared	29.00
Short steel turnings	24.00
Rails, rerolling	43.00

Cast Iron Grades†

No. 1 machinery cast	50.00

†F.o.b. Hamilton, Ont.

MACHINING PERFECTION always starts with the right steel

Pick exactly the right steel for any job from J & L's complete cold finished line



"Machines window pivot pins 35% faste with J & L C-1117 leaded steel"

Conversion to J&L "C-1117" leaded steel from regu "C-1117" steel cut total machining time 35% for this pi pin used in linkage for turning quarter windows. Cycle ti was cut from 3.5 to 2.6 seconds for this part machined fr 3/8" cold finished round. J&L leaded steels give you hig cutting speeds, longer tool life, improved finish. Call y local distributor or write to Jones & Laughlin, 3 Gatew Center, Pittsburgh 30, Pennsylvania.

J&L STEEL

Jones & Laughlin

. . . a great name in steel

Tariff Hearings End

Report should be ready by late winter. Commission expected to recommend higher lead and zinc duties but oppose import quotas. Custom smelted copper falls to 25 cents

Nonferrous Metal Prices, Pages 162 & 163

HEARINGS on increased duties for lead and zinc imports ended last week at U. S. Tariff Commission headquarters in Washington. Status quo and higher tariff forces unleashed salvos of facts, figures, and predictions.

When—Now that about 50 industry spokesmen have had their say, it's up to the commission. Washington sources believe it will be late winter or early spring before the commission's report is sent to the President. Such time consumers as the Christmas holidays, the 30-day period allowed for the filing of briefs, and staff analysis still stand in the way.

The betting is the commission will vote for an increase in tariffs: 2.55 cents a pound for lead, 2.1 cents a pound for zinc. Present rates are 1.06 cents for lead, 0.7 cent for zinc. But it's felt the commissioners won't recommend establishing quotas. (In 1954 they went on record as being against them.)

Possibilities—In theory, the commission can submit any of three findings to the President: 1. That there is no injury and no need for a tariff adjustment. 2. A finding that injury is present and an adjustment needed. 3. A tie vote.

If the commission brings in a decision of no injury, the President's hands are tied as far as adjustment is concerned. But he has wide discretionary power if the majority favors an increase, or if there is a split vote. For example: A recommendation to raise tariffs could be accepted, rejected, or substantially altered by the President. In the case of an evenly divided vote, he could accept the recommendations of either side, reject both, or modify any proposed increase. Indications are that any recommendation to strengthen the domestic lead and zinc industry will be favorably received by the White House.

Copper Cut Again

Custom smelted copper fell to 25 cents a pound on Nov. 21, down one-half cent. It was the second half-cent cut in ten days.



A further decline would surprise no one since it's doubtful if the latest reduction will boost demand substantially.

The big question is whether primary copper can sustain a price 2 cents a pound above the custom smelters' quotation. (Primary has been at 27 cents since Sept. 3. Most metalmen believe primary producers will have to chop their price by at least 1 cent a pound unless custom smelters come back up or demand improves substantially. Neither condition appears likely.

Other minus factors: 1. The LME is hovering at 23 cents a pound. 2. Katanga copper has been cut to 23.6 cents a pound, c.i.f New York.

The pricing situation is of concern in world capitals. Rumor has it that the Chilean government is trying to negotiate with other countries to establish a world price. Though the movement reportedly has many supporters, it's doubtful if any such agreement could ever be reached.

Market Memos

- Aluminum Co. of America has set up a new marketing group to stimulate sales to the mobile home industry.
- Ingot brass and bronze shipments in October hit 22,800 tons, reports the Defense Council of the Ingot Brass & Bronze Industry. This compares with the September figure of 19,670.
- The Panamanian government has signed a contract with Kaiser Aluminum & Chemical Corp. granting the company exclusive rights to explore for and mine bauxite in the western areas along the Costa Rican border.
- Magnesium casting shipments totaled 12,343 tons in the first nine months, compared with 13,522 tons in the same period last year.

NONFERROUS PRICE RECORD

	Price Nov. 26	Last Change	Previous Price	Oct. Avg	Sept. Avg	Nov., 1956 Avg
Aluminum ..	26.00	Aug. 1, 1957	25.00	26.000	26.000	25.000
Copper	25.00–27.00	Nov. 21, 1957	25.50–27.00	26.361	26.469	35.956
Lead	13.30	Oct. 14, 1957	13.80	13.504	13.800	15.800
Magnesium .	35.25	Aug. 13, 1956	33.75	35.250	35.250	35.250
Nickel	74.00	Dec. 6, 1956	64.50	74.000	74.000	64.500
Tin	87.50	Nov. 26, 1957	87.125	91.843	93.422	111.049
Zinc	10.00	July 1, 1957	10.50	10.000	10.000	13.500

Quotations in cents per pound based on: COPPER, deld. Conn. Valley; LEAD, common grade, deld. St. Louis; ZINC, prime western, E. St. Louis; TIN, Straits, deld. New York; NICKEL, electrolytic cathodes, 99.9%, base size at refinery, unpacked; ALUMINUM, primary pig, 99.5+%, f.o.b. shipping point; MAGNESIUM, pig, 99.8%, Velasco, Tex.

You get speedier service from the

ZINC ZONE

Central location of American Zinc plants assures prompt deliveries of slab zinc to any point in the nation.



PRODUCERS OF

ALL GRADES OF SLAB ZINC
ZINC ANODES (Plating & Galvanic)
METALLIC CADMIUM
SULPHURIC ACID
LEAD-FREE and LEADED ZINC OXIDES
ZINC CARBONATE
GERMANIUM DIOXIDE
AGRICULTURAL LIMESTONE
CRUSHED STONE

American Zinc Sales Company

Distributors for AMERICAN ZINC, LEAD & SMELTING COMPANY

Columbus, Ohio • Chicago • St. Louis • New York • Detroit • Pittsburgh

Nonferrous Metals

Cents per pound, carlots except as otherwise noted.

PRIMARY METALS AND ALLOYS

Aluminum: 99.5%, pigs, 26.00; ingots, 28.10, 10,000 lb or more, f.o.b. shipping point. Freight allowed on 500 lb or more.

Aluminum Alloy: No. 13, 29.90; No. 43, 29.70; No. 195, 31.30; No. 241, 31.50; No. 356, 29.90, 30-lb ingots.

Antimony: R.M.M. brand, 99.5%, 33.00; Lone Star brand, 33.50, f.o.b. Laredo, Tex., in bulk. Foreign brands, 99.5%, 25.50-26.50, New York, duty paid, 10,000 lb or more.

Beryllium: 97% lump or beads, $71.50 per lb, f.o.b. Cleveland or Reading, Pa.

Beryllium Aluminum: 5% Be, $74.75 per lb of contained Be, with balance as Al at market price, f.o.b. shipping point.

Beryllium Copper: 3.75-4.25% Be, $43 per lb of contained Be, with balance as Cu at market price on shipment date, f.o.b. shipping point.

Bismuth: $2.25 per ton, ton lots.

Cadmium: Sticks and bars, $1.70 per lb deld.

Cobalt: 97-99%, $2.00 per lb for 550-lb keg; $2.02 per lb for 100 lb case; $2.07 per lb under 100 lb.

Columbium: Powder, $120 per lb, nom.

Copper: Electrolytic, 27.00 deld.; custom smelters, 25.00; lake, 27.00 deld.; fire refined, 26.75 deld.

Germanium: First reduction, $179.17-197.31 per lb; intrinsic grade, $197.31-220 per lb, depending on quantity.

Gold: U. S. Treasury, $35 per oz.

Indium: 99.9%, $2.25 per troy oz.

Iridium: $80-110 nom. per troy oz.

Lead: Common, 13.30; chemical, 13.40; corroding, 13.40, St. Louis. New York basis, add 0.20.

Lithium: 98 + %, 50-100 lb, cups or ingots, $12; rod, $15; shot or wire, $16. 100-500 lb, cups or ingots, $10.50; rod, $14; shot or wire, $15, f.o.b. Minneapolis.

Magnesium: Pig, 35.25; ingot, 36.00 f.o.b. Velasco, Tex.; 12 in. sticks, 59.00 f.o.b. Madison, Ill.

Magnesium Alloys: AZ91A (diecasting), 40.75 deld.; AZ63A, AZ92A, AZ91C (sand casting), 40.75, f.o.b. Velasco, Tex.

Mercury: Open market, spot, New York, $225-230 per 76-lb flask.

Molybdenum: Unalloyed, turned extrusions, 3.75-5.75 in. round, $9.60 per lb in lots of 2500 lb or more, f.o.b. Detroit.

Nickel: Electrolytic cathodes, sheets (4 x 4 in. and larger), unpacked, 74.00; 10-lb pigs, unpacked, 78.25; "XX" nickel shot, 79.50; "F" nickel shot for addition to cast iron, 74.50; "F" nickel 5 lb ingots in kegs for addition to cast iron, 75.50. Prices f.o.b. Port Colborne, Ont., including import duty. New York basis, add 1.01. Nickel oxide sinter, 71.25 per lb of nickel content before 1 cent freight allowance, f.o.b. Copper Cliff, Ont.

Osmium: $80-100 per troy oz nom.

Palladium: $21-24 per troy oz.

Platinum: $81-87 per troy oz from refineries.

Radium: $16-21.50 per mg radium content, depending on quantity.

Rhodium: $118-125 per troy oz.

Ruthenium: $45-55 per troy oz.

Selenium: $7.50 per lb, commercial grade.

Silver: Open market, 90.00 per troy oz.

Sodium: 16.50, c.l.; 17.00 l.c.l.

Tantalum: Rod, $60 per lb; sheet, $55 per lb.

Tellurium: $1.65-1.85 per lb.

Thallium: $12.50 per lb.

Tin: Straits, N. Y., spot and prompt, 87.50.

Titanium: Sponge, 99.3+%, grade A-1 ductile (0.3% Fe max.), $2.25; grade A-2 (0.5% Fe max.), $2.00 per lb.

Tungsten: Powder, 98.8%, carbon reduced, 1000-lb lots, $3.50 per lb nom., f.o.b. shipping point; less than 1000 lb, add 15.00; 99+% hydrogen reduced, $4.10-4.20.

Zinc: Prime Western, 10.00; brass special, 10.25; intermediate, 10.50, East St. Louis, freight allowed over 0.50 per lb, New York basis, add 0.50. High grade, 11.35; special high grade, 11.75 deld. Die casting alloy ingot No. 3, 14.25; No. 2, 15.25; No. 5, 14.75 deld.

Zirconium: Sponge, commercial grade, $5-10 per lb.

(Note: Chromium, manganese, and silicon metals are listed in ferroalloy section.)

SECONDARY METALS AND ALLOYS

Aluminum Ingot: Piston alloys, 23.75-30.25; No. 12 foundry alloy (No. 2 grade), 21.75-23.00; 5% silicon alloy, 0.60 Cu max., 25.50-26.00; 13 alloy, 0.60 Cu max., 25.50-26.00; 195 alloy, 24.75-26.75; 108 alloy, 22.25-23.00. Steel deoxidizing grades, notch bars, granulated or shot; Grade 1, 23.75; grade 2, 22.00; grade 3, 20.75; grade 4, 19.00.

Brass Ingot: Red brass, No. 115, 27.25; tin bronze, No. 225, 36.00; No. 245, 30.75; high-leaded tin bronze, No. 305, 31.25; No. 1 yellow, No. 405, 22.75; manganese bronze, No. 421, 24.50.

Magnesium Alloy Ingot: AZ63A, 37.50; AZ91B, 37.50; AZ91C, 41.25; AZ92A, 37.50.

NONFERROUS PRODUCTS

BERYLLIUM COPPER

(Base prices per lb, plus mill extras, 2000 to 5000 lb; nom. 1.9% Be alloy.) Strip, $1.82, f.o.b. Temple, Pa., or Reading, Pa.; rod, bar, wire, $1.80, f.o.b. Temple, Pa.

COPPER WIRE

Bare, soft, f.o.b. eastern mills, 30,000-lb lots, 32.355; l.c.l., 32.98. Weatherproof, 30,000-lb lots, 33.66; l.c.l., 34.78. Magnet wire deld., 40.43, before quantity discounts.

LEAD

(Prices to jobbers, f.o.b. Buffalo, Cleveland, Pittsburgh.) Sheets, full rolls, 140 sq ft or more, $19.00 per cwt; pipe, full coils, $19.00 per cwt; traps and bends, list prices plus 30%.

TITANIUM

(Prices per lb, 10,000 lb and over, f.o.b. mill.) Sheets and strip, $9.50-15.95; sheared mill plate, $8.00-11.50; wire, $7.50-11.50; forging billets, $6.00-7.60; hot-rolled and forged bars, $6.15-7.90.

ZINC

(Prices per lb, c.l., f.o.b. mill.) Sheets, 24.00; ribbon zinc in coils, 20.50; plates 19.00.

ZIRCONIUM

Plate, $12.50-19.20; H.R. strip, $12.50-22.90; C.R. strip, $15.00-31.25; forged or H.R. bars, $11.00-17.40.

NICKEL, MONEL, INCONEL

	"A" Nickel	Monel	Inconel
Sheets, C.R.	126	106	128
Strip, C.R.	124	108	138
Plate, H.R.	120	105	121
Rod, Shapes, H.R.	107	89	109
Seamless Tubes	157	129	200

ALUMINUM

Sheets: 1100 and 3003 mill finish (30,000 lb base; freight allowed).

Thickness Range Inches	Flat Sheet	Coiled Sheet
0.249-0.136	43.10-47.60	.....
0.135-0.096	43.60-48.70	40.50-41.10
0.095-0.077	44.30-50.50	40.60-41.30
0.076-0.061	44.90-52.80	40.80-42.00
0.060-0.048	45.60-55.10	41.40-43.10
0.047-0.038	46.20-57.90	41.90-44.50
0.037-0.030	46.60-62.90	42.30-46.30
0.029-0.024	47.20-54.70	42.60-47.00
0.023-0.019	48.20-58.10	43.70-45.40
0.018-0.17	49.00-55.40	44.30-46.00
0.016-0.015	49.90-56.30	45.10-46.80
0.014	50.90	46.10-47.80
0.013-0.012	52.10	46.80
0.011	53.10	48.00
0.010-0.0095	54.60	49.40
0.009-0.0085	55.90	50.90
0.008-0.0075	57.50	52.10
0.007	59.00	53.60
0.006	60.60	55.00

ALUMINUM (continued)

Plates and Circles: Thickness 0.250-3 in. 24-60 in. width or diam., 72-240 in. lengths.

Alloy	Plate Base	Circle Base
1100-F, 3003-F	42.70	47.50
5050-F	43.80	48.60
3004-F	44.80	50.50
5052-F	45.40	51.20
6061-T6	46.90	53.00
2024-T4*	50.60	57.40
7075-T6*	58.40	66.00

*24-48 in. width or diam., 72-180 in. lengths

Screw Machine Stock: 30,000 lb base.

Diam.(in.)or across flats	Round 2011-T3	Round 2017-T4	Hexagonal 2011-T3	Hexagonal 2017-T
Drawn				
0.125	78.20	75.20	....	....
0.156-0.172	66.20	63.40	....	....
0.188	66.20	63.40	....	81.60
0.219-0.234	63.00	61.50	....	....
0.250-0.281	63.00	61.50	....	77.90
0.313	63.00	61.50	....	74.20
0.344	62.50	....	....	....
Cold-Finished				
0.375-0.547	62.50	61.30	74.80	69.80
0.563-0.688	62.50	61.30	71.10	65.50
0.719-1.000	61.00	59.70	64.90	61.70
1.063	61.00	59.70	....	59.60
1.125-1.500	58.60	57.40	62.80	59.60
Rolled				
1.563	57.00	55.70	....	....
1.625-2.000	56.30	54.90	....	57.50
2.125-2.500	54.80	53.40	....	....
2.563-3.375	53.20	51.70	....	....

Forging Stock: Round, Class 1, 45.20-58.6 in specific lengths, 36-144 in., diam. 0.375-8 in. Rectangles and squares, Class 1, 50.50-66.60 in random lengths, 0.375-4 in. thick, width 0.750-10 in.

Pipe: ASA schedule 40, alloy 6063-T6, standard lengths, plain ends, 90,000-lb base, per 100 ft

Nom. Pipe Size (in.)		Nom. Pipe Size (in.)	
¾	$19.40	2	$ 59.80
1	30.50	4	165.00
1¼	41.30	6	296.10
1½	49.40	8	445.50

Extruded Solid Shapes:

Factor	Alloy 6063-T5	Alloy 6062-T6
9-11	45.40-47.00	60.60-64.80
12-14	45.70-47.20	61.30-65.80
15-17	45.90-47.90	62.50-67.50
18-20	46.50-48.30	64.50-70.10

MAGNESIUM

Sheet and Plate: AZ31B standard grade, 0.3 in., 103.10; .081 in., 77.90; .125 in., 70.40; .18 in., 69.00; .250-2.0 in., 67.90. AZ31B spec grade, .032 in., 171.30; .081 in., 108.70 .125 in., 98.10; .188 in., 95.70; .250-2.00 in 93.30. Tread plate, 60-192 in. lengths, 24-72 in widths; .125 in., 74.90; .188 in., 71.70-72.70 .25-.75 in., 70.60-71.60. Tooling plate, .25-3 in., 73.00.

Extruded Solid Shapes:

Factor	Com. Grade (AZ31C)	Spec. Grad (AZ31B)
6-8	69.60-72.40	84.60-87.4
12-14	70.70-73.00	85.70-88.0
24-26	75.60-76.30	90.60-91.3
36-38	89.20-90.30	104.20-105.3

NONFERROUS SCRAP

DEALER'S BUYING PRICES

(Cents per pound, New York, in ton lots.)

Aluminum: 1100 clippings, 13.50-14.00; ob sheets, 10.50-11.00; borings and turnings, 6.50

BRASS MILL PRICES

MILL PRODUCTS a

	Sheet, Strip, Plate	Rod	Wire	Seamless Tubes	SCRAP ALLOWANCES Clean Heavy	Rod Ends	Clean Turning
Copper	50.13b	47.36c	....	50.32	23.000	23.000	22.250
Yellow Brass	44.02	32.30d	44.56	46.93	17.375	17.125	15.750
Low Brass, 80%	46.50	46.44	47.04	49.31	19.500	19.250	18.750
Red Brass, 85%	47.37	47.31	47.91	50.18	20.250	20.000	19.500
Com. Bronze, 90%	48.78	48.72	49.32	51.34	21.000	20.750	20.000
Manganese Bronze	52.01	46.11	56.61	....	16.125	15.875	15.375
Muntz Metal	46.39	42.20	....	....	16.375	16.125	15.625
Naval Brass	48.27	42.58	55.33	51.68	16.125	15.875	15.375
Silicon Bronze	54.76	53.95	54.80	56.74e	22.625	22.375	21.625
Nickel Silver, 10%	60.43	62.75	62.75	....	23.625	23.375	11.813
Phos. Bronze, A-5%	69.07	69.57	69.57	70.75	23.750	23.500	22.500

a. Cents per lb, f.o.b. mill; freight allowed on 500 lb or more. b. Hot-rolled. c. Cold-drawn d. Free cutting. e. 3% silicon. f. prices in cents per lb for less than 20,000 lb, f.o.b. shipping point. On lots over 20,000 lb at one time, or any or all kinds of scrap, add 1 cent per lb.

.00; crankcases, 10.50-11.00; industrial castings, 10.50-11.00.

Copper and Brass: No. 1 heavy copper and wire, 18.75-19.25; No. 2 heavy copper and wire, 16.75-17.25; light copper, 14.50-15.00; No. 1 composition red brass, 15.00-15.50; No. 1 composition turnings, 14.50-15.00; new brass clippings, 13.00-13.50; light brass, 9.00-9.50; heavy yellow brass, 11.00-11.50; new brass rod ends, 12.00-12.50; auto radiators, unsweated, 11.50-12.00; cocks and faucets, 12.00-12.50; brass pipe, 12.50-13.00.

Lead: Heavy, 8.50-9.00; battery plates, 4.00-4.25; linotype and stereotype, 10.50-11.00; electrotype, 9.50-10.00; mixed babbitt, 10.50-11.00.

Monel: Clippings, 30.00-32.00; old sheets, 29.00-30.00; turnings, 23.00-24.00; rods 30.00-32.00.

Nickel: Sheets and clips, 42.00-47.00; rolled anodes, 42.00-47.00; turnings, 40.00-42.00; rod ends, 42.00-47.00.

Zinc: Old zinc, 3.00-3.25; new diecast scrap, 2.75-3.00; old diecast scrap, 1.50-1.75.

REFINERS' BUYING PRICES

(Cents per pound, carlots, delivered refinery)

Aluminum: 1100 clippings, 16.50-17.50; 3003 clippings, 16.50-17.50; 6151 clippings, 16.00-17.50; 5052 clippings, 16.00-17.00; 2014 clippings, 15.50-17.00; 2017 clippings, 15.50-17.00; 2024 clippings, 15.50-17.00; mixed clippings, 15.00-16.00; old sheets, 13.50; old cast, 13.50; clean old cable (free of steel), 16.00-16.50; borings and turnings, 13.50-15.00.

Beryllium Copper: Heavy scrap, 0.020-in. and heavier, not less than 1.5% Be, 53.00; light scrap, 48.00; turnings and borings, 33.00.

Copper and Brass: No. 1 heavy copper and wire, 21.50; No. 2 heavy copper and wire, 19.50; light copper, 17.25; refinery brass (60% copper) per dry copper content, 19.25.

INGOTMAKERS' BUYING PRICES

(Cents per pound, carlots, delivered)

Copper and Brass: No. 1 heavy copper and wire, 21.50; No. 2 heavy copper and wire, 19.50; light copper, 17.25; No. 1 composition borings, 18.25; No. 1 composition solids, 18.75; heavy yellow brass solids, 13.00; yellow brass turnings, 12.00; radiators, 14.75.

PLATING MATERIALS

(F.o.b. shipping point, freight allowed on quantities)

ANODES

Cadmium: Special or patented shapes, $1.70 per lb.

Copper: Flat-rolled, 45.29; oval, 43.50, 5000-10,000 lb; electrodeposited, 35.75, 2000-5000 lb lots; cast, 36.25, 5000-10,000 lb quantities.

Nickel: Depolarized, less than 100 lb, 114.25; 10-499 lb, 112.00; 500-4999 lb, 107.50; 5000-29,999 lb, 105.25; 30,000 lb, 103.00. Carbonized, deduct 3 cents a lb.

Tin: Bar or slab, less than 200 lb, 105.50; 200-499 lb, 104.00; 500-999 lb, 103.50; 1000 lb or more, 103.00.

Zinc: Balls, 17.50; flat tops, 17.50; flats, 19.25; ovals, 18.50, ton lots.

CHEMICALS

Cadmium Oxide: $1.70 per lb in 100-lb drums.

Chromic Acid: 100 lb, 33.30; 500 lb, 32.80; 2000 lb, 32.15; 5000 lb, 31.80; 10,000 lb, 31.30; f.o.b. Detroit.

Copper Cyanide: 100-200 lb, 71.60; 300-900 lb, 69.60.

Copper Sulphate: 100-1900 lb, 14.55; 2000-5900 lb, 12.55; 6000-11,900 lb, 12.30; 12,000-22,900 lb, 12.05; 23,000 lb or more, 11.55.

Nickel Chloride: Less than 400 lb, 35.00; 400-9990 lb, 33.00; 10,000 lb, 32.50.

Nickel Sulphate: 5000-22,000 lb, 33.50; 23,000-35,900 lb, 33.00; 36,000 lb or more, 32.50.

Sodium Cyanide: 100 lb, 27.60; 200 lb, 25.90; 400 lb, 22.90; 1000 lb, 21.90; f.o.b. Detroit.

Sodium Stannate: Less than 100 lb, 71.50; 100-600 lb, 62.80; 700-1900 lb, 60.10; 2000-9900 lb, 58.20; 10,000 lb or more, 56.90.

Stannous Chloride (anhydrous): Less than 25 lb, 160.40; 25 lb, 124.50; 100 lb, 110.40 400 lb, 108.00; 5200-19,600 lb, 95.80; 20,000 lb or more, 83.60.

Stannous Sulphate: Less than 50 lb, 123.50; 50 lb, 93.50; 100-1900 lb, 91.50; 2000 lb or more, 89.50.

Zinc Cyanide: 100-200 lb, 59.00; 300-900 lb, 57.00.

(*Concluded from Page* 157)

ers, awaiting placement of December business, think prices may drop another $2 a ton. Cast scrap is off $2, cupola now being quoted $38 and No. 1 machinery cast $43.

Birmingham—The scrap market here continues slow with only a few sales, principally cast grades, reported. A check of mills indicates little likelihood of a pickup in buying the remainder of this year.

Opinions of brokers differ on the price outlook. Some think quotations will go lower; others think they are bumping bottom.

San Francisco—The steel scrap market is marking time. Shipments slowed down further last week because of the Thanksgiving Day observance. Prices are unchanged.

Washington—Stocks of ferrous materials (scrap and pig iron) totaled 11,185,000 gross tons at the end of September, reports the U. S. Bureau of Mines. Of the total, 7,942,000 tons were scrap, 3,243,000

METALLURGICAL ENGINEERS

With experience in investigation and analysis of mechanical failures, shop methods, processes and devices employed in the manufacture of parts for heavy duty earth-moving equipment; and metallurgical and heat-treating studies to evaluate materials, chemical properties and heat-treating specifications based on analyses of service performance.

Direct replies to:

Personnel Director
THE EIMCO CORPORATION
P. O. Box 300
Salt Lake City 10, Utah

MELTER

Need melter with stainless steel background. Induction melting facilities 30 to 2000 lbs. capacity.
Excellent opportunity to grow with aggressive young company in suburban Milwaukee area.
Reply Box 622, STEEL
Penton Bldg. Cleveland 13, Ohio

CLASSIFIED

Help Wanted

CLEANING ROOM SUPERINTENDENT: Must have supervisory experience and be completely familiar with all phases of cleaning room operations for a miscellaneous steel jobbing foundry producing castings up to 10,000 pounds. Excellent opportunity for an aggressive qualified man with a modern and progressive foundry located in the Middle West producing 600-700 tons per month. Advise full particulars including salary requirements. Box 603, STEEL, Penton Bldg., Cleveland 13, Ohio.

STEEL MILL SUPERINTENDENT for small plant consisting of electric furnace and Merchant Mill. Must have experience all phases. Southern location. Give complete account of experience, references and salary anticipated. Write Box 624, STEEL, Penton Bldg., Cleveland 13, Ohio.

PLANNING A VENTURE IN CANADA

Do It the Easy Way

Canadian Metalworking plant, central Canada, available for lease (or sale) to reputable U. S. firm. Exceptional opportunity for concern contemplating Canada to avoid capital outlay, startup and personnel problems, by acquiring a going concern by lease; small, but well equipped and with extremely competent production staff. Experienced machining and fabricating in precision aircraft and ordnance fields. Current field of operations (aircraft, ordnance, aluminum boats) can be maintained, expanded, or eliminated to suit your requirements. Approx. $250,000 worth equipment (hand and automatic turning, milling, press, welding, treating, etc.) in 8,000 sq. feet plus brick building. This advertisement by principals—no fees or commissions involved.

Box 625, STEEL
Penton Bldg. Cleveland 13, Ohio

FOR SALE
175 TRANSFORMERS
1.5 to 1000 KVA
Current listing
sent upon request
GENERAL METALS
of the Aleutians, Inc.
1919 Canal Street • Tacoma 2, Wn.
Tel.: FUlton 3-3443

GET CASH NOW
for your new surplus motors, controls and transformers!
NEW MOTORS AVAILABLE: Over 5,000 new motors, in stock, from ¼HP to 200 HP. Special low prices.
Write, wire or phone collect!

AJAX ELECTRIC MOTOR CORP.
P.O. Box 262, Rochester, N.Y.
Long Distance Phone LD. 132

FOR SALE
PELS IRONWORKER'S SHEAR MOD. EFF35 shear 3⅜ Rd; 3" Sq; 6x2; 8x1¼ Flats; 8x8x¾ Angles; 12x35# Channels; Factory motorized. Reasonably priced. WEIDEMANN TURRET PUNCH MOD. 10-B 12 Sta.
SEABOARD STEEL CO., INC.
New Haven, Conn.

FOR SALE
Pig Machine—Conveyor type motorized pig machine. Pours 25—40# steel pigs. Details on request.
CRUCIBLE STEEL CASTING COMPANY
2850 So. 20th St.
Milwaukee 15, Wis.

MANUFACTURERS REPRESENTATIVE
AAA-1 company interested in experienced stainless steel casting representation in New York, East Coast area. Straight commission. Write at once giving complete resume.
Box 623, STEEL
Penton Bldg. Cleveland 13, Ohio

. . . check with Milford Engineers!

Riveting raises *special* problems and requires *special* skills. You must have the right type and size rivet for each application, or the results can be costly . . . in production and in profits. When you're faced with a riveting problem, let Milford engineers lend a hand before designs are fixed!

To improve product appearance and strength
. . . to take full advantage of automatic assembly
. . . to cut delivery time and production costs
—get in touch with Milford first!

THE MILFORD RIVET

MILFORD RIVET & MACHINE CO.

MILFORD, CONNECTICUT • HATBORO, PENNSYLVANIA
ELYRIA, OHIO • AURORA, ILLINOIS • NORWALK, CALIF.

pig iron. Stocks of both regis tered new highs, scrap being u 6 per cent and pig iron 5 per cen from the totals reported at th end of August.

Domestic consumption durin September totaled 5,034,000 ton of scrap (down 5 per cent fro August), and 5,646,000 tons of pi iron (down 3 per cent). The to tal melt (10,680,000 tons) consist ed of 47 per cent scrap and 53 pe cent pig iron, compared with 4 and 52 per cent in August.

Scrap for consumption (hom production plus purchases) in Sep tember amounted to 5,482,000 gros tons, a decrease of 5 per cent fro August. Home scrap accounte for 3,193,000 tons, and purchase 2,289,000. Of the purchased mat rial, 84 per cent was received fro dealers, 16 per cent from othe sources.

Los Angeles—Scrap prices a unchanged, but absence of m buying continues. Collections ha virtually stopped. Most dealers r port plentiful supplies.

Metallurgical Coke . .

Metallurgical Coke Prices, Page 153

U. S. Steel Corp. will discontinu operations at its Joliet, Ill., co plant March 1, after a half ce tury of service. First ovens the plant were put in operation 1908 to complete integration the then Joliet Works of the Ill nois Steel Co. Originally, the were four batteries of ovens, b in 1952 No. 3 battery was sh down.

Iron Ore . . .

Iron Ore Prices, Page 153

Shipments of Lake Superior iro ore totaled only 492,964 gross to in the week ended Nov. 25, repor the American Iron Ore Associ tion. In the like week a year a 1,866,960 tons were moved.

With the lake shipping seas rapidly coming to a close, shi ments of ore from the upper lak to Nov. 25 total 84,439,976 tons up 9,439,976 tons from the 74,87 061 tons moved to the like date 1956.

Shipments have been complet for the season at all U. S. la ports except Escanaba and Ma quette, Mich. Ore is still movi through Michipicoten in Canada.